

Punjab Cities Program

Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab

Ref: MMP/PMDFC/1076/COM/341/2022

Date: 06 December 2022

Mr. Syed Zahid Aziz
Managing Director, PD PCP
Punjab Municipal Development Fund Company (PMDFC)
House No. 184, Scotch Corner, Upper Mall,
Lahore, Pakistan

MMP

MM Pakistan (Pvt) Ltd.

AID Associates in Development (AID) Pvt. Ltd.
Development and Management Consulting

Urban and Infrastructure
Department, CTI Building
27-Empress Road Lahore

mmpdcc@mmpakistan.com

042-36300460,
36363234, 36292525-7

042-36292528, 36360267

http://www.mmpakistan.com

Subject: Updated Draft PC-I for Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Okara City - Package-V

Dear Sir,

Please refer to observation raised by the MC Okara received through WhatsApp. They have sent observations on the Draft PC-I submitted to PMDFC costing PKR 100.53 Million vide our letter No. MMP/PMDFC/1076/283/2022 dated 15 November 2022.

Para wise comments appended below: -

1. Removal of Tack coat.
2. Formatting of BOQ.
3. Earth work rates updated from MRS 2nd Bi-Annual.
4. Update Non Schedule item of Electrical work to Schedule item.

After incorporating a/m observations, kindly find enclosed the copy of the **Updated Draft PC-I Costing PKR 98.33 Million for the project "Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Okara City"** under PCP Package-V.

This deliverable is submitted under **Consultancy Agreement Clause Appendix A, V, Serial No.2 c of Package-V** for your review and further necessary action, please.

Assuring you of our best technical services and cooperation at all times.

Yours faithfully,

Brig Pervez-Hayat Niazi (R)

Team Leader Package-V

MMP – PCP

Cc:

- Iftikhar Rasool, Deputy Project Director, PMDFC
- Muhammad Ashiq Chuadhry, Senior Program Officer, PMDFC
- Malik Ahsan Gulzar, Manager Projects, Associates in Development (Pvt.) Ltd.
- Dr. Javed Iqbal, Project Director, PCP – MMP
- Syed Aslam Sabzwari, W&W Head, PCP – MMP
- Tanvir Masud, Contract Specialist, PCP – MMP
- The Chief Officer, Municipal Committee Khanewal
- Muhammad Abdullah, Senior Engineer Transportation, PCP – MMP
- Zubair Qadir, Field Coordinator, PCP – MMP
- Master File MMP- PCP


Encl:

- i. **Draft PC-I for Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Okara City - Package-V (01 Hard Copy and 01 Soft Copy)**

OFFICE COPY



Registered in Pakistan no K-527/9363
Offices:
Lahore, Karachi, Islamabad, Peshawar, Hyderabad



DRAFT

**Local Government & Community Development
Department**



**Punjab Cities Program
PC-I Form**

For

Improvement, Widening and Raising of Road from Tank

Chowk to Akbar Chowk along Canal Road

Estimated Cost 98.33 Million PKR

December 2022

Municipal Committee Okara

Punjab Cities Program
PC-I Form Widening / Raising and Improvement of Existing Roads
Including Installation of Street Lights in Okara City
Table of contents

| S. No. | Description | Page No (from - to) |
|---------------|--|----------------------------|
| 1 | PC-I Form | 1-12 |
| 2 | Annexure-A Location Map | 13 |
| 3 | Annexure-B Project Cost Estimates | 14-56 |
| 4 | Annexure-C Project Economic Analysis, Sensitivity Analysis & Cost Benefit Ratio | 57-60 |
| 5 | Annexure-D Project Implementation Period (Gant Chart) | 61 |
| 6 | Annexure-E Environment Impact Assessment | - |
| 7 | Annexure-F Project Drawings | - |

PC-I FORM
for
**Widening / Raising and Improvement of Existing Roads Including
Installation of Street Lights in Okara City**

Project Serial Number

Sector : Local Government & Community Development Department

Sub Sector : Social

| | | | |
|---|--|--------------------|--|
| 1. Name of the project | Punjab Cities Program 1. Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road | | |
| 2.Location | Okara is 127 Km south west of Lahore. The city coordinates are 30-8138' North latitude, and 73-4534' East longitude. Location map of the city is attached in Annexure-A | | |
| 3. Authorities responsible for | | | |
| I- Sponsoring | Government of the Punjab (through World Bank funding) | | |
| ii- Execution | District Council Unit Okara | | |
| iii- Operation and Maintenance | District Council Unit Okara | | |
| iv-Concerned Provincial Department | Local Government and Community Development Department Punjab | | |
| 4a.Plan Provision | | | |
| i. If the project is included in medium term/five year plan, specify actual allocation | Punjab Cities Program (PCP) is a World Bank funded Program with a total cost of 236.00 million USD and comprises of below mentioned components. | | |
| | Total loan from World Bank | 200.00 million USD | |
| | Component-1 Infrastructure development (PforR) | 180.00 million USD | |
| | Component-2 Technical Assistance | 20.00 million USD | |
| | MCs share (20% of PforR component) equivalent to: | 36.00 million USD | |
| | Total Program cost | 236.00 million USD | |
| Component-2 i-e Technical Assistance component of Program costing 20.00 million USD is meant for management cost of the Program and capacity building of MCs & Government | | | |

| | |
|--|---|
| | Departments and is included in the medium term/ five year plan and has been funded now in ADP 2022-23 - under General Serial No-1769 with allocation of PKR 100 million as foreign component. |
| ii- If not included in the current plan, what warrants its inclusion and how it is now proposed to be accommodated | Not applicable |
| iii If the project is proposed to be financed out of block provision indicate. | The Project is being financed by World Bank as Donor along with 20% co-financing from the Program Units and is not proposed to be financed out of Block Allocation. |
| 4b- Provision in the current year PSDP/ADP | Rs.100.00 million under ADP 2022-23 General Serial No 1769 for Component-2 of the Program i-e Technical Assistance as described above. |
| 5. Project objectives and its relationship with sector objectives | <p><u>Sector Objectives</u> The sector objectives include:</p> <ol style="list-style-type: none"> 1. Provision of efficient and effective municipality services to the masses. 2. Community development through improving basic infrastructure. 3. Clean and green environment for better living standards. 4. Ease in mobility and communication. 5. Capacity building of Local Governments. <p><u>Objectives of the Project</u> The Main objective of project is to improve the quality of roads / streets leading to enhance quality of life of residents of the area and safety for pedestrians and traffic.</p> <p>The Project has the following objectives;</p> <ol style="list-style-type: none"> 1. Improvement of service delivery level of the municipal services in the sector of communication. 2. Better travelling facilities for the commuters. 3. Reduction in road accidents. 4. Saving in travelling and repair cost of the vehicles. 5. Reduction in annual maintenance charges of roads and parks 6. Improvement in environments of the city making them livable. 7. Improvement in local and province economy. |

| | |
|--|---|
| | <p>8. Improvement in the economic growth potential of the city.</p> <p>Hence, the objectives of the project are in line with the sector objectives mentioned at Sr. No-1, 2, 3 and 4 above and the project forms integral part of the concerned sector.</p> |
| 6. Description, justification, technical parameters and technology transfer aspects | |
| i)Description | Improvement and widening of existing Roads with allied drainage Works at Okara district. |
| ii)Justification | <p>There are a lot of areas of Okara District where Roads have been constructed in past years. Due to various activities for installation of utilities in these areas the condition of the areas highlighted by district council, Okara has been deteriorated and needed immediate attention to improve the vehicles/ Pedestrian traffic to ease out the public at large in the area. The same shall also enhance the quality of life and improve area environment also.</p> <p>Presently the roads taken in the project are in miserable condition and show problems regarding surface riding quality, surface drainage and aesthetics. The reconnaissance and detailed surveys were done to identify the condition of existing infrastructure quality and suggest remedial measures to improve the condition of roads pointed out by the client. About 04 Nos of roads were surveyed and the detailed x-sections were developed for different width of road and pavement design.</p> <p>Providing technical parameters and discuss technology aspect of the project</p> |
| iii)Technical Parameters | <ul style="list-style-type: none"> • Sub – Grade compaction to act as levelling layer. • Sub – Base 6 to 8 inches compacted. • Base course 6 inches compacted • Pre-mixed Wearing course with binding coats • Kerb stone is provided as protection of the edges • 7000 Psi Tuff Pavers of approved quality 80mm thick with Sand bedding 2” to 3”. |
| iv) Detail of civil works, equipment & machinery and other physical facilities | <p>Location of Okara city area highlighted by the client.</p> <p>The detail of roads to be improved, rehabilitated or constructed in the city, is attached in Annexure-B</p> |

| <p>v) Indicate governess issues of the sector relevant to the project and strategy to resolve them</p> | <ul style="list-style-type: none"> • The smooth sailing of the Punjab Cities Program can only be assured when the required staff for maintenance is available with Okara Unit. • The Repair and maintenance of the municipal services seem to be not up to the mark in the Unit. Trainings will be imparted by PMDFC to the officers as well as the field staff under the Program but practicing the interventions and method/procedures learnt in these trainings is the actual requirement in which Units are lacking at present. The same are to be given due considerate for improving the delivery level. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|--|---|----------------------|-------------|-------------------|-------------------|--|--|---|---|---------------|--------------------------------------|--|--|---|---|---------------|---|-------------------|----------------------|--|-------------------|---------------------|--|-----------------------|---------------------|--|------------------------------------|---------------------|--|-------------------------|----------------------|--|-------------------------|-----------------|--|-----------------------------------|--|
| <p>7- Capital Cost of Project</p> | <p>The summary of the works included in the project is given below;</p> <table border="1" data-bbox="523 831 1455 1800"> <thead> <tr> <th data-bbox="523 831 635 927">S. No</th> <th data-bbox="635 831 1102 927">Description</th> <th data-bbox="1102 831 1455 927">Total Cost (PKR)</th> </tr> </thead> <tbody> <tr> <td colspan="3" data-bbox="523 927 1455 976">Road Works</td> </tr> <tr> <td data-bbox="523 976 635 1151">1</td> <td data-bbox="635 976 1102 1151">Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road</td> <td data-bbox="1102 976 1455 1151">Rs 67,349,609</td> </tr> <tr> <td colspan="3" data-bbox="523 1151 1455 1200">Installation of Street Lights</td> </tr> <tr> <td data-bbox="523 1200 635 1375">2</td> <td data-bbox="635 1200 1102 1375">Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road</td> <td data-bbox="1102 1200 1455 1375">Rs 23,298,395</td> </tr> <tr> <td data-bbox="523 1375 635 1458">3</td> <td data-bbox="635 1375 1102 1458">Total cost</td> <td data-bbox="1102 1375 1455 1458">Rs 90,648,004</td> </tr> <tr> <td></td> <td data-bbox="635 1458 1102 1507">Contingencies @2%</td> <td data-bbox="1102 1458 1455 1507">Rs 1,812,960</td> </tr> <tr> <td></td> <td data-bbox="635 1507 1102 1556">Punjab Sales Tax & 5%</td> <td data-bbox="1102 1507 1455 1556">Rs 4,532,400</td> </tr> <tr> <td></td> <td data-bbox="635 1556 1102 1639">Environment Impact Assessment Cost</td> <td data-bbox="1102 1556 1455 1639">Rs 1,333,000</td> </tr> <tr> <td></td> <td data-bbox="635 1639 1102 1688">GRAND TOTAL (RS)</td> <td data-bbox="1102 1639 1455 1688">Rs 98,326,364</td> </tr> <tr> <td></td> <td data-bbox="523 1688 1102 1738">Say Rs (Million)</td> <td data-bbox="1102 1688 1455 1738">Rs 98.33</td> </tr> <tr> <td></td> <td colspan="2" data-bbox="523 1738 1455 1800">See Annexure-B for details</td> </tr> </tbody> </table> | S. No | Description | Total Cost (PKR) | Road Works | | | 1 | Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road | Rs 67,349,609 | Installation of Street Lights | | | 2 | Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road | Rs 23,298,395 | 3 | Total cost | Rs 90,648,004 | | Contingencies @2% | Rs 1,812,960 | | Punjab Sales Tax & 5% | Rs 4,532,400 | | Environment Impact Assessment Cost | Rs 1,333,000 | | GRAND TOTAL (RS) | Rs 98,326,364 | | Say Rs (Million) | Rs 98.33 | | See Annexure-B for details | |
| S. No | Description | Total Cost (PKR) | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Road Works | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1 | Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road | Rs 67,349,609 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Installation of Street Lights | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 2 | Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road | Rs 23,298,395 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 3 | Total cost | Rs 90,648,004 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | Contingencies @2% | Rs 1,812,960 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | Punjab Sales Tax & 5% | Rs 4,532,400 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | Environment Impact Assessment Cost | Rs 1,333,000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | GRAND TOTAL (RS) | Rs 98,326,364 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | Say Rs (Million) | Rs 98.33 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | See Annexure-B for details | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <p>i- Indicate date of estimation of the project cost</p> | <p>The project estimates have been framed during the month of December, 2022</p> | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <p>ii- Basis of determining the</p> | <p>The cost estimates have been framed on the basis of bill of quantities actually measured at site and unit rates from the Market</p> | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

| estimates be provided. | Rate System (MRS) issued by the Government of Punjab (District Okara 2 nd biannual of year 2022). For items not available in the MRS, the same have been analyzed as per prevailing market rates. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|--|--|----------------------|--------------|-------------------|-------------------|-----------------------------------|------|---|---|---------------|--------------------------------------|--------------------------------------|------|---|---|---------------|-------------------|--|----------------------|-------------------|--|---------------------|-----------------------|--|---------------------|------------------------------------|--|---------------------|-------------------------|--|----------------------|-------------------------|--|-----------------|-----------------------------------|--|--|
| iii- Provide year wise estimation of physical activities | <p>The physical and financial requirements, year wise are included in the following table:</p> <table border="1" data-bbox="531 533 1453 882"> <thead> <tr> <th data-bbox="531 533 635 618">S. #</th> <th data-bbox="635 533 1115 618">Name of road</th> <th data-bbox="1115 533 1453 618">Year 2022-23</th> </tr> </thead> <tbody> <tr> <td data-bbox="531 618 635 703">1</td> <td data-bbox="635 618 1115 703">Widening and Improvement of Roads</td> <td data-bbox="1115 618 1453 703">100%</td> </tr> <tr> <td data-bbox="531 703 635 775">2</td> <td data-bbox="635 703 1115 775">Drainage Works</td> <td data-bbox="1115 703 1453 775">100%</td> </tr> <tr> <td data-bbox="531 775 635 882">3</td> <td data-bbox="635 775 1115 882">Contingencies, taxes and other items</td> <td data-bbox="1115 775 1453 882">100%</td> </tr> </tbody> </table> | S. # | Name of road | Year 2022-23 | 1 | Widening and Improvement of Roads | 100% | 2 | Drainage Works | 100% | 3 | Contingencies, taxes and other items | 100% | | | | | | | | | | | | | | | | | | | | | | | | |
| S. # | Name of road | Year 2022-23 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1 | Widening and Improvement of Roads | 100% | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 2 | Drainage Works | 100% | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 3 | Contingencies, taxes and other items | 100% | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| iv- Phasing of capital cost on the basis of each item of work. | <p>The phasing of capital cost of the project is included in the following table: (All figures are in million rupees)</p> <table border="1" data-bbox="531 1048 1453 2013"> <thead> <tr> <th data-bbox="531 1048 635 1146">S. No</th> <th data-bbox="635 1048 1115 1146">Description</th> <th data-bbox="1115 1048 1453 1146">Total Cost (PKR)</th> </tr> </thead> <tbody> <tr> <td colspan="3" data-bbox="531 1146 1453 1196">Road Works</td> </tr> <tr> <td data-bbox="531 1196 635 1370">1</td> <td data-bbox="635 1196 1115 1370">Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road</td> <td data-bbox="1115 1196 1453 1370">Rs 67,349,609</td> </tr> <tr> <td colspan="3" data-bbox="531 1370 1453 1420">Installation of Street Lights</td> </tr> <tr> <td data-bbox="531 1420 635 1594">2</td> <td data-bbox="635 1420 1115 1594">Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road</td> <td data-bbox="1115 1420 1453 1594">Rs 23,298,395</td> </tr> <tr> <td colspan="2" data-bbox="531 1594 1115 1675">Total cost</td> <td data-bbox="1115 1594 1453 1675">Rs 90,648,004</td> </tr> <tr> <td colspan="2" data-bbox="531 1675 1115 1729">Contingencies @2%</td> <td data-bbox="1115 1675 1453 1729">Rs 1,812,960</td> </tr> <tr> <td colspan="2" data-bbox="531 1729 1115 1783">Punjab Sales Tax & 5%</td> <td data-bbox="1115 1729 1453 1783">Rs 4,532,400</td> </tr> <tr> <td colspan="2" data-bbox="531 1783 1115 1863">Environment Impact Assessment Cost</td> <td data-bbox="1115 1783 1453 1863">Rs 1,333,000</td> </tr> <tr> <td colspan="2" data-bbox="531 1863 1115 1917">GRAND TOTAL (RS)</td> <td data-bbox="1115 1863 1453 1917">Rs 98,326,364</td> </tr> <tr> <td colspan="2" data-bbox="531 1917 1115 1971">Say Rs (Million)</td> <td data-bbox="1115 1917 1453 1971">Rs 98.33</td> </tr> <tr> <td colspan="3" data-bbox="531 1971 1453 2024">See Annexure-B for details</td> </tr> </tbody> </table> | S. No | Description | Total Cost (PKR) | Road Works | | | 1 | Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road | Rs 67,349,609 | Installation of Street Lights | | | 2 | Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road | Rs 23,298,395 | Total cost | | Rs 90,648,004 | Contingencies @2% | | Rs 1,812,960 | Punjab Sales Tax & 5% | | Rs 4,532,400 | Environment Impact Assessment Cost | | Rs 1,333,000 | GRAND TOTAL (RS) | | Rs 98,326,364 | Say Rs (Million) | | Rs 98.33 | See Annexure-B for details | | |
| S. No | Description | Total Cost (PKR) | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Road Works | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1 | Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road | Rs 67,349,609 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Installation of Street Lights | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 2 | Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road | Rs 23,298,395 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Total cost | | Rs 90,648,004 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Contingencies @2% | | Rs 1,812,960 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Punjab Sales Tax & 5% | | Rs 4,532,400 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Environment Impact Assessment Cost | | Rs 1,333,000 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| GRAND TOTAL (RS) | | Rs 98,326,364 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Say Rs (Million) | | Rs 98.33 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| See Annexure-B for details | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

| | | | |
|--|---|-----------------|--|
| | | | |
| 8-Annual recurrent cost after completion of the project and source of financing | The roads are already being repaired and maintained by the District Council Unit Okara out of its own financial resources. No additional cost will be required after completion of the improvement and upgradation of the roads, rather the repair cost will be reduced for the initial years. However, the efficiency of the infrastructure and service delivery level will be improved after completion of the project. | | |
| 9- Demand & Supply Analysis | B. Existing supply level | | |
| i- Existing Capacity of services | The roads are in much deteriorated condition which are hampering the mobility of residents. | | |
| ii- Projected Demand for 10 years | 1. Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road | | |
| iii- Capacity of other similar projects being implemented in public/private sector | No other project of similar nature is being executed in city at present. | | |
| iv- Supply and Demand gaps | <p>The roads are old and condition is deteriorated due to a number of maintenance and construction operation for different utility departments.</p> <p>The construction/ rehabilitation is needed to bring the area to a good condition of roads by strengthening the existing structure using sub – base , base and wearing courses has been conceived by the client also for this purpose. This PC-1 is prepared keeping into consideration, above requirement.</p> | | |
| v-Designed capacity and output of the project | Roads having total Length of 6152 ft. shall be designed for about ten year’s life with minimum O&M cost. | | |
| 10. Financial Plan | Below given loan for the Punjab Cities Program has been funded by World Bank for 16 PCP cities in Punjab. | | |
| Sources of financing | | | |
| <u>Debt</u> | | | |
| a) Indicate the local and foreign debt Loan | Total loan to Government of Pakistan/Punjab | 200 million USD | |
| | Component-1 for Infrastructure Development | 180 million USD | |
| | Component-2 for Investment Project Financing For capacity building of MCs & three Govt. organization and program management. | 20 million USD | |

| | | | | | | | | |
|---|--|-----------------|---|-------------------|---|-------------------|---|-------------------|
| | 20% share of Municipalities is equivalent to | 36 million USD | | | | | | |
| | Total funds available for Infrastructure Development | 216 million USD | | | | | | |
| | This project will be funded under this financing. | | | | | | | |
| b) Equity | <p>A. Loan/grant to MC</p> <p>The amount of loan converted to grant to Okara Unit will be Rs 98.33 (cost of the PC-I). The financing of the project will be as given below:</p> <table border="1"> <tr> <td>Grant to Unit for the year 2021-22 (80% of cost of PC-I) worked out</td> <td>PKR 78.66 million</td> </tr> <tr> <td>20% Co-finance by MC (20% of the cost of PC-I) worked out</td> <td>PKR 19.66 million</td> </tr> <tr> <td>Total available funds (Total cost of PC-I) worked out</td> <td>PKR 98.33 million</td> </tr> </table> <p>B. Project Cost 98.33 Million PKR</p> <p>*The loan is from World Bank to Government of Pakistan/Punjab which will trickle down to Okara Unit as grant.</p> | | Grant to Unit for the year 2021-22 (80% of cost of PC-I) worked out | PKR 78.66 million | 20% Co-finance by MC (20% of the cost of PC-I) worked out | PKR 19.66 million | Total available funds (Total cost of PC-I) worked out | PKR 98.33 million |
| Grant to Unit for the year 2021-22 (80% of cost of PC-I) worked out | PKR 78.66 million | | | | | | | |
| 20% Co-finance by MC (20% of the cost of PC-I) worked out | PKR 19.66 million | | | | | | | |
| Total available funds (Total cost of PC-I) worked out | PKR 98.33 million | | | | | | | |
| c) Grants | No grant is being given by Government of Punjab out of ADP funds. The World Bank loan to Government of Pakistan/Punjab will trickle down as grant to MC from Government of Punjab. | | | | | | | |
| d) Weighted cost of capital | Nil | | | | | | | |
| 11-Project benefits and analysis | | | | | | | | |
| i. Financial: Income to the project with assumption | (Attached Economic Analysis, Cost benefit ratio and Sensitivity Analysis as Annexure-C) | | | | | | | |
| ii. Social benefits to the target group | (Attached at Annexure-E) | | | | | | | |
| iii. Environmental Impact negative/positive | (Attached at Annexure-E) | | | | | | | |
| iv. Quantifiable project outputs | (Attached at Annexure-C) | | | | | | | |
| v. Unit cost analysis | Unit cost of construction shall be Rs. 15,982.83 per Rft (98,326,364/ 6152 ft) | | | | | | | |

| | |
|--|--|
| <p>vi. Employment generation (direct and indirect)</p> | <p><u>Employment Analysis</u></p> <p>Direct Employment</p> <p>a) <i>Planning and Design of projects</i></p> <p>The planning and design of the project has been entrusted to local consultants who have appointed staff and experts in road and related disciplines along with their support staff. The consultants will also appoint their staff for resident supervision of the project to verify and certify the items of works to be executed under this PC-I.</p> <p>b) <i>Execution of the Project</i></p> <p>a) <i>PMDFC</i></p> <p>PMDFC has the project monitoring and supervisory role and the company has enough experts and staff to complete this assignment. PMDFC has already deployed under mentioned staff for these projects:</p> <ul style="list-style-type: none"> • Civil Engineers • Accounts, administration and audit personnel • Urban planners • GIS experts • Support staff like computer operators, vehicle drivers, office boys and guards. • Procurement experts • Communication experts • Environmental and social experts • Contract management experts <p>b) <i>Consultants</i></p> <p>PMDFC has employed consultants for detailed design and resident supervision of the projects who will deploy their staff for execution of the project.</p> <p>c) <i>Municipality</i></p> <p>Okara Unit has regular staff like engineers, sub engineers and other administrative & accounts keeping staff which will be responsible for execution of the project and contract management. No additional staff will be needed for execution of this project</p> <p>d) <i>Contractor</i></p> <p>The contractor responsible for execution of the sub project will employ skilled and un-skilled labor on this work.</p> |
|--|--|

| | |
|--|---|
| | <p>Indirect Employment Indirect employment for production of material such as cement, steel, stone metal, bitumen, bricks etc. will be generated.</p> |
| vii. Impacts of delays on project cost and viability | <p>The impact of delay in project implementation will;</p> <ul style="list-style-type: none"> • Result in increased project cost due to escalation in cost of material and labor. • Delay the benefits to the target group • Result in further deterioration of the infrastructure and the service delivery level. |
| 12-Implementation Schedule | |
| a) Indicate starting and completion date of the project | The project is anticipated to commence by December 2022 and to be completed by the end of financial year 2022-2023 i.e. May,2023 |
| b) Item wise/year wise schedule in line chart | The chart is attached as Annexure – D |
| 13- Management Structure and manpower requirements | |
| i. Administrative arrangements for the implementation of the project | <p>i. Planning & design of the project The project has been designed by the consultants employed by PMDFC and will also carry out the resident supervision of the project.</p> <p>ii. Preparation of cost estimation The cost estimates have been prepared by the MM Pakistan (PVT) Ltd. The execution of the items of works included in these estimates /PC-I will be certified by these consultants.</p> <p>iii. Execution of the project</p> <ul style="list-style-type: none"> • The project will be executed by District Council Unit Okara and supervised by the Consultants appointed by PMDFC in resident supervision mode. The technical staff & experts in PMDFC will oversee, co-ordinate and collaborate in the project planning, design and implementation through their experts in head office located in Lahore and regional offices. The reporting of progress to LG & CDD & World bank and troubleshooting will also be responsibility of PMDFC. |

| | <ul style="list-style-type: none"> • MO (I&S) of the Unit has been designated as Project Manager /Engineer in Charge of the project. The supervision of the works will also be carried out by these municipal officers along with their support engineering staff. All supervisory staff is available with MC. • The procurement of works and goods will be done by Procurement Committee of Okara Unit as per PPRA Rules. | | | | | | | | | | | | |
|---|--|-----|--|-----|---------------|---|-------------------------------------|----|--|---|-----------------|----|--|
| | <p>iv. Verification of quantities included in PC-Is and Resident Supervision of the works by consultants</p> <p>The works will be supervised by Supervision Consultants in resident supervision mode by assuring the quantity and quality of works. The consultants will verify the items of work and their quantities contained in the PC-Is and cost estimates initially and then the quantities and quality of works included in the contractor claims at the stage of payments. Payments will be made by the Unit after these contractor claims have been entered in the measurement books by the Resident Engineer in Charge and pre audited as per LG Works Rules.</p> | | | | | | | | | | | | |
| <p>ii- The manpower requirements by skills during execution and operation of the project and; The job description, qualification, experience, age and salary of each post</p> | <p>a) PMDFC experts and staff</p> <p>For rendering assistance in implementation of infrastructure projects in 16 MCs, PMDFC has the experts and staff in the required fields. In order to facilitate the Program Units, three regional offices have been established by PMDFC at Gujranwala, Faisalabad and Multan/Okara.</p> <p>b) Resident Supervision Consultants</p> <p>The project will be supervised by consultants. The tentative staff to be employed/deployed by the consultants for the certification of quantities of works and resident supervision of the project is given below.</p> <table border="1" data-bbox="523 1563 1513 1977"> <thead> <tr> <th>S #</th> <th>Personnel</th> <th>Nos</th> <th>Qualification</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>Chief Resident Engineer/Team Leader</td> <td>01</td> <td>BSc;/BE in Civil engineering with minimum 20 years' professional experience or MSC; Civil Engineering/Public Health Engineering/Environmental Engineering with Bachelor in Civil Engineering and minimum 15 years, experience, with 5 years on similar assignments in both cases</td> </tr> <tr> <td>2</td> <td>Senior Engineer</td> <td>01</td> <td>BSc/BE Civil engineering with minimum 08 years' relevant design experience or MSc engineering, with 5 years on similar assignments in both cases</td> </tr> </tbody> </table> | S # | Personnel | Nos | Qualification | 1 | Chief Resident Engineer/Team Leader | 01 | BSc;/BE in Civil engineering with minimum 20 years' professional experience or MSC; Civil Engineering/Public Health Engineering/Environmental Engineering with Bachelor in Civil Engineering and minimum 15 years, experience, with 5 years on similar assignments in both cases | 2 | Senior Engineer | 01 | BSc/BE Civil engineering with minimum 08 years' relevant design experience or MSc engineering, with 5 years on similar assignments in both cases |
| S # | Personnel | Nos | Qualification | | | | | | | | | | |
| 1 | Chief Resident Engineer/Team Leader | 01 | BSc;/BE in Civil engineering with minimum 20 years' professional experience or MSC; Civil Engineering/Public Health Engineering/Environmental Engineering with Bachelor in Civil Engineering and minimum 15 years, experience, with 5 years on similar assignments in both cases | | | | | | | | | | |
| 2 | Senior Engineer | 01 | BSc/BE Civil engineering with minimum 08 years' relevant design experience or MSc engineering, with 5 years on similar assignments in both cases | | | | | | | | | | |

| | | | | | |
|--|--|-----------------------------|----|--|--|
| | 3 | Resident Engineer | 01 | BSc; /BE Civil engineering with minimum 10 years' experience in site supervision and execution for projects of similar nature. | |
| | 4 | Assistant Resident Engineer | 01 | Bachelor Degree in Civil engineering with minimum 8 years' experience in site supervision and execution for projects of similar nature | |
| | 5 | Site Inspectors | 01 | DAE in Civil with minimum 10 years' experience in site supervision for projects of similar nature | |
| | 6 | Quantity Surveyor | 01 | DAE in Civil Technology with minimum 10 years' experience in estimation & costing of projects of similar nature. The person having public sector projects will be preferred. | |
| | 7 | AutoCAD Operator | 01 | DAE in Civil Technology with minimum 5 years' experience in preparation of drawings for projects of similar nature. (situated at Lahore office) | |
| | <p>c) Contractor's Technical staff, skilled & non skilled labor The contractors will employ the supervisory technical staff and skilled & non skilled labor for execution of works. The works will be supervised by experienced Engineers and sub engineers and the number of slots for engineers and skilled and non-skilled will depend upon the type and quantity of work and its period of completion.</p> <p>d) Repair & maintenance of the project MC has its own regular staff which has been deployed for Repair and maintenance of the municipal services infrastructure. However, it has been observed that the existing staff is not adequate to repair and maintain the services in a manner which can give good service delivery. Hence it is proposed to;</p> <ul style="list-style-type: none"> • Fill up the presently vacant slots • Recruit additional staff as per need of the infrastructure after obtaining the sanctions from the competent authorities. | | | | |

| | |
|-----------------------|---|
| 15-Certificate | Certified that the project proposal has been prepared on the basis of guidelines provided by the Planning Commission for the preparation of PC-I for Local Government and community development Department. |
|-----------------------|---|




| | | | | |
|-------------------------|---|--|-----------------------|---|
| Prepared by | MM Pakistan (Pvt) Ltd | | Stamp & Signatures |  |
| Checked by | Municipal officer (Infrastructure) District Council Unit Okara | | Stamp & Signatures | |
| | Chief Officer District Council Unit Okara | | Stamp & Signatures | |
| Forwarded by | Administrator District Council Okara | | Stamp & Signatures | |

ANNEXURES

ANNEXURE – A

Location Map

Okara City Road Projects



| Sr.No. | Project Title |
|--------|---|
| 1 | Improvement, Widening and Raising from Tank Chowk to Akbar Chowk along Canal Road |

| Legend | |
|--------------------------|--|
| NAME | |
| Proposed Canal Road | |
| Canal | |
| Existing Primary Roads | |
| Existing Secondary Roads | |
| Railway Line | |
| MC Boundary PLGA 2019 | |

PUNJAB MUNICIPAL DEVELOPEMENT FUND COMPANY

PROJECT:
PUNJAB CITIES PROGRAM (PCP)
 DETAILED DESIGN OF INFRASTRUCTURE
 SUB-PROJECTS, SECTORAL PLANNING & RESIDENT
 SUPERVISION IN 16 CITIES OF PUNJAB (PACKAGE-5)

Map Code
 0830 02 1022

Map Version
 1.0

DISCLAIMER:
 INFORMATION IS PROVIDED BY MC,
 PHED & OTHER SOURCES.

Scale:
 1:26,000

Date
 September 2022

Drawing No.
 MMP-1076P05-OKR-RD-LP-001

MMP
 MM Pakistan (Pvt) Ltd.

ANNEXURE – B

Cost Estimates

**Detail Design of Infrastructure Sub - Projects Sectoral Planning &
Resident Supervision in 16 Cities of Punjab**
**Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk
along Canal Road, Okara**
TOTAL LENGTH = 1.875 KM
SUMMARY OF COST

| ITEM | DESCRIPTION | AMOUNT | |
|------------|---|-----------|--------------------------|
| A - | ROAD WORKS | | |
| 1 | Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road | Rs | 67,349,609 |
| B - | STREET LIGHTING NETWORK | | |
| 2 | Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road | Rs | 23,298,395 |
| | TOTAL (RS) : | Rs | 90,648,004 |
| | ADD 2% CONTINGENCY | Rs | 1,812,960 |
| | ADD 5% PST | Rs | 4,532,400 |
| | Environment Impact Assessment Cost | Rs | 1,333,000 |
| | GRAND TOTAL (RS) | Rs | <u>98,326,364</u> |
| | COST IN (MILLIONS) | Rs | <u>98.33</u> |

Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab

Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road

Calculation of Quantities

NOTE: Description of all items shall be considered same as of referred MRS item number.

NOTE: Market Rate System (MRS) issued by the Government of Punjab (District Okara 2nd biannual of year 2022).

| Sr. No | MRS 02-2022 | | Detail of Item | Nos | Measurements | | | Quantity | Unit | Rate | Unit | Amount |
|--------|-------------|-------|--|-----------------------|--|----------------------------------|------------------------------|---|------|----------|------|---------------|
| | Chap | Item | | | Length | Width | Height | | | | | |
| 1 | 4 | 11 | A) ROAD WORKS Dismantling dry brick masonry / existing road edging. STA : 0+000 to 6+152 Total Qty | 2 | 6,152.00 | 0.25 | 0.75 | 2,307.00 <u>2,307.00</u> | Cft | 863.50 | 100 | Rs. 19,921 |
| 2 | 4 | 45 | Dismantling and removing road metalling STA : 0+000 to 6+152 Total Qty of Item No - 12 | 1 | 89,854.00 | - | 0.17 | 15,275.18 <u>15,275.18</u> | Cft | 2,031.75 | 100 | Rs. 310,353 |
| 3 | 4 | 11 | Dismantling Tuff pavers STA : 4+690 to 4+885 SOLING Total Qty | 1 | 195.00 | 14.50 | | 2,827.50 <u>2,827.50</u> | Sft | 863.50 | 100 | 24,415 |
| 4 | 3 | 17 | Transportation of earth all types when the total distance, including the lead covered in the item of work, is more than 1000 ft. (300 m) Tuff Pavers (Broken) As above Total Qty | | 2,827.50 | 0.26 | 50% | 371.06 <u>371.06</u> | Cft | 6,002.40 | 1000 | 2,227 |
| 5 | 3 | 6 | Regular excavation dressed. Widened Portion STA : 0+000 to 2+000 24 15.50 STA : 2+000 to 4+690 24 14.00 STA : 4+690 to 4+825 24 14.50 STA : 4+825 to 6+152 24 14.50 Total Qty | 1 1 1 1 | 2,000.00 2,690.00 135.00 1,327.00 | 24.00 24.00 24.00 24.00 | 1.00 1.00 1.00 1.00 | 48,000.00 64,560.00 3,240.00 31,848.00 | Cft | 5,241.45 | 1000 | Rs. 773,890 |
| 6 | 3 | 5 - i | Earthwork in ordinary soil for embankments lead upto 100 ft. (30 m), including ploughing and mixing with blade gradeor disc harrow or other suitable equipment, and compaction by mechanical means at optimum moisture content and dressing to designed section, complete in all respects:- Excavated Material to be used Old Carriage way Expnded Carriage way STA : 0+000 to 2+000 24 15.50 STA : 2+000 to 4+690 24 14.00 STA : 4+690 to 4+825 24 14.50 STA : 4+825 to 6+152 24 14.50 for Shoulders Edging Total Qty | 1 1 1 1 1 | 2,000.00 2,690.00 135.00 1,327.00 | 24.00 24.00 24.00 24.00 | 0.75 0.75 0.75 0.75 | 24,619.50 16,146.33 36,000.00 48,420.00 2,430.00 23,886.00 1,659.00 <u>16,842.95</u> | Cft | 9,527.90 | 1000 | Rs. 1,619,779 |

Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab
Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road

Calculation of Quantities

NOTE: Description of all items shall be considered same as of referred MRS item number.

NOTE: Market Rate System (MRS) issued by the Government of Punjab (District Okara 2nd biannual of year 2022).

| Sr. No | MRS 02-2022 | | Detail of Item | Nos | Measurments | | | Quantity | Unit | Rate | Unit | Amount |
|--------|-------------|------|---|-----|-------------|-----------|--|------------|----------|----------|---------------|-------------|
| | Chap | Item | | | Length | Width | Height | | | | | |
| 7 | 3 | 7-i | <p>Earthwork excavation in open cutting Earthwork excavation in open cutting upto 5'-0" (1.5 m) depth for storm water channels, drains, sullage drains in open areas, roads, streets, lanes, including under pinning walls and shoring to protect existing works, shuttering and timbering the trenches, dressed to designed level and dimensions, trimming, removal of surface water from trenches, back filling and surplus excavated material disposed of and dressed within 50 ft. (15 m) lead:-</p> <p>i) Ordinary Soil Old Carriage way Expnded Carriage way STA : 0+000 to 2+000 24 15.50 1 2,000.00 8.50 0.75 12,750.00 STA : 2+000 to 4+690 24 14.00 1 2,690.00 10.00 0.75 20,175.00 STA : 4+690 to 4+825 24 14.50 1 135.00 9.50 0.75 961.88 STA : 4+825 to 6+152 24 14.50 1 1,327.00 9.50 0.75 9,454.88 In addition to 0.58 depth for Shoulders _____ Total Qty</p> | | | | | | | | | |
| | | | | | | | 59,820.14 | Cft | 9,016.70 | 1000 | Rs. 539,380 | |
| 8 | 4 | 45 | <p>Dismantling and removing road metalling</p> <p>ii) Hard soil (WBM) Old Carriage way STA 0+000 to 2+000 = 15.50 Width 1 2,000.00 15.50 0.58 17,980.00 STA : 2+000 to 4+690 = 14.00 Width 1 2,690.00 14.00 0.58 21,842.80 STA : 4+690 to 4+825 = 14.50 Width 1 135.00 14.50 0.58 1,135.35 STA : 4+825 to 6+152 = 14.50 Width 1 1,327.00 14.50 0.58 11,160.07 Existing Footpath _____ Total Qty</p> | | | | | | | | | |
| | | | | | | | 55,535.22 | Cft | 2,031.75 | 100 | Rs. 1,128,337 | |
| 9 | 3 | 17 | <p>Transportation of earth all types when the total distance, including the lead covered in the item of work, is more than 1000 ft. (300 m)</p> <p>Filling required To be brought in _____ _____ Less Ordinary soil can be used Hard soil To be carried away _____ Total Qty</p> | | | | | | | | | |
| | | | | | | | 170,003.78 (59,820.14) 15,635.47 | | | | | |
| | | | | | | 52,118.22 | 30% | 125,819.10 | Cft | 6,002.40 | 1000 | Rs. 755,217 |

Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab

Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road

Calculation of Quantities

NOTE: Description of all items shall be considered same as of referred MRS item number.

NOTE: Market Rate System (MRS) issued by the Government of Punjab (District Okara 2nd biannual of year 2022).

| Sr. No | MRS 02-2022 | | Detail of Item | Nos | Measurments | | | Quantity | Unit | Rate | Unit | Amount |
|--------|-------------|----------|--|------------------|--|----------------------------------|------------------|---|------------|------------------|------------|-----------------------|
| | Chap | Item | | | Length | Width | Height | | | | | |
| 14 | 18 | 10a | Providing and laying plant premixed bituminous 2" thick carpet, including compaction and finishing to required camber, grade and density. iv) 4.5% Bitumen STA : 0+000 to 2+000 STA : 2+000 to 4+690 STA : 4+690 to 4+825 STA : 4+825 to 6+152 Total Qty | 1 1 1 1 | 2,000.00 2,690.00 135.00 1,327.00 | 24.00 24.00 24.00 24.00 | - - - - | 48,000.00 64,560.00 3,240.00 31,848.00 | | | | |
| | | | | | | | | 147,648.00 | Sft | 16,462.51 | 100 | Rs. 24,306,561 |
| 15 | 13 | 36 - b | Painting Traffic Lane Marking of specified width (1.5mm thick), with Thermoplastic (TP) Paint including Glass Beads, complete in all respect, as approved and directed by Engineer incharge. 6" wide STA : 0+000 to 6+152 Total Qty of Item No - 14 | 2 1 | 6,152.00 2,051.00 | - - | - - | 12,304.00 2,051.00 | | | | |
| | | | | | | | | 14,355.00 | Rft | 56.20 | 1 | Rs. 806,751 |
| 16 | 6 | 52 -b- i | Providing and fixing precast Edge Kerb Stone (4"to6" thick), of 3500PSI Compressive Strength, embeded in PCC1:2:4 over lean concrete1:4:8 etc complete in all respect. STA : 0+000 to 6+152 Total Qty | 2 | 6,152.00 | - | - | 12,304.00 | | | | |
| | | | | | | | | 12,304.00 | Rft | 516.90 | 1 | Rs. 6,359,938 |
| 17 | 18 | 25a | Providing, fabrication and fixing pole mounted Direction Board/road delineator of any shape and size, with specified Sheet and thickness, supported with G.I.Channel, (excluding the cost of vertical post and painting) etc complete in all respect If 3 mm thick Aluminium sheet is used, increase composite rate by Rs 627/- Psft or Rs 6747/- Per Sq.Mtr (a) G. I. Sheet 14 SWG i) CIRCULAR/TRIANGULAR 3 ft size Total Qty | 4 | | | 3.00 | 12.00 | | | | |
| | | | | | | | | 12.00 | Sft | 948.15 | 1 | Rs. 11,378 |
| 18 | 18 | 27b | Providing, fabrication and fixing Vertical Post comprising of medium quality G.I Pipe of specified diameter, including the cost of clamping arrangements, top cover, hold fasts embeded in PCC1:2:4 etc complete in all respect. (b) 3 inch diameter Total Qty | 4 | | | 10.17 | 40.68 | | | | |
| | | | | | | | | 40.68 | Rft | 1,259.95 | 1 | Rs. 51,255 |

**Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab
Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road
Calculation of Quantities**

NOTE: Description of all items shall be considered same as of referred MRS item number.

NOTE: Market Rate System (MRS) issued by the Government of Punjab (District Okara 2nd biannual of year 2022).

| Sr. No | MRS 02-2022 | | Detail of Item | Nos | Measurements | | | Quantity | Unit | Rate | Unit | Amount |
|--------|-------------|------|---|-----|--------------|-------|--------|-------------|------|-----------|------|-----------------------|
| | Chap | Item | | | Length | Width | Height | | | | | |
| 19 | 18 | 28 | Providing & fixing Cat Eyes of size 4"x4"x3/4" duly casted with specified material having plastic strip containing mini retro-reflective glass beads of color white/red/yellow having specifid reflections, quality & shape i/c the cost of self builtin 12mm dia x 120mm long steel zinc plated nail, fixing to road with epoxy/ hammering with separate nail complete b) Aluminium Alloy (B) Uni-Directional (ii) 43 Glass beads a side @ 30' c/c | 3 | 206 | | | 618.00 - | | | | |
| | | | | | | | | 618.00 | Each | 543.80 | 1 | Rs. 336,068 |
| | | | Total of Road Work | | | | | | | | | Rs. 67,017,825 |
| | | | B) ROAD DRAINAGE WORKS | | | | | | | | | |
| 20 | | | Raising of Man Holes (As per attached | 1 | 28.00 | | | 28.00 | | | | |
| | | | Total Qty | | | | | 28.00 | No. | 11,849.43 | 1 | Rs. 331,784 |
| | | | Total of Drainage Works | | | | | | | | | Rs. 331,784 |
| | | | Total of Road + Drainage Works | | | | | | | | | Rs. 67,349,609 |

Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab

Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road

Calculation of Quantities

NOTE: Description of all items shall be considered same as of referred MRS item number.

NOTE: Market Rate System (MRS) issued by the Government of Punjab (District Okara 2nd biannual of year 2022).

| Sr. No | MRS 02-2022 | | Detail of Item | Nos | Measurements | | | Quantity | Unit | Rate | Unit | Amount |
|--------|-------------|-----------|---|-----|--------------|-------|--------|-----------------|------------|------------------|-------------|--------------------|
| | Chap | Item | | | Length | Width | Height | | | | | |
| | | | C) CIVIL WORKS FOR ELECTRICAL WORKS | | | | | | | | | |
| 21 | 3 | 7-i | Earthwork excavation in open cutting upto 5'-0" (1.5 m) depth for storm water channels, drains, sullage drains in open areas, roads, streets, lanes, including under pinning of walls and shoring to protect existing works, shuttering and timbering the trenches, dressed to designed level and dimensions, trimming, removal of surface water from trenches, back filling and surplus excavated material disposed of and dressed within 50 ft. (15 m) lead i) Ordinary For 1 Foundation = 3' x 3' x 4.25' = 38.25 Cft For 16 Foundations = 13 x 38.25 = 555.75 Cft | 53 | 3.00 | 3.00 | 4.25 | 2,027.25 | | | | |
| | | | Total Qty | | | | | 2,027.25 | Cft | 9,016.70 | 1000 | Rs. 18,279 |
| 22 | 3 | 17 | Transportation of earth all types when the total distance, including the lead covered in the item of work, is more than 1000 ft. (300 m) Ordinary soil | | | | | 2,027.25 | | | | |
| | | | Total Qty | | | | | 2,027.25 | Cft | 6,002.40 | 1000 | Rs. 12,168 |
| 23 | 6 | 5-i | Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): i) 1:4:8 | 53 | 3.00 | 3.00 | 0.25 | 119.25 | | | | |
| | | | | | | | | 119.25 | Cft | 38,504.48 | 100 | Rs. 45,917 |
| 24 | 6 | 6-a-iii-3 | Providing and laying reinforced cement concrete (including prestressed concrete), using coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete (but excluding the cost of steel reinforcement, its fabrication and placing in position, etc.) (a)(iii) Reinforced cement concrete in slab of rafts / strip foundation, base slab of column and retaining walls; etc and footing beams, other structural members other than those mentioned in 6(a) (i)&(ii) above not requiring form work (i.e. horizontal shuttering) complete in all respects: (3) Type C (nominal mix 1: 2: 4) | 53 | 2.00 | 2.00 | 6.00 | 1,272.00 | Cft | | | |
| | | | | | | | | 1,272.00 | Cft | 644.88 | 1 | Rs. 820,284 |
| 25 | 6 | 12-c | Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- (c) Deformed bars (Grade-60) @ 5lbs/Cft | | | | | 2,885.66 | Kg | 31,781.75 | 100 | Rs. 917,114 |

Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab

Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road

Calculation of Quantities

NOTE: Description of all items shall be considered same as of referred MRS item number.

NOTE: Market Rate System (MRS) issued by the Government of Punjab (District Okara 2nd biannual of year 2022).

| Sr. No | MRS 02-2022 | | Detail of Item | Nos | Measurments | | | Quantity | Unit | Rate | Unit | Amount |
|--------|-------------|-------|---|-----------|--------------|--------------|--------------|----------------------|-----------|----------|-------------|----------------------|
| | Chap | Item | | | Length | Width | Height | | | | | |
| 26 | 24 | 6-ii | Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:- iii) 80mm (7 Rft/Foundation) | 53 | 7.00 | | 371.00 | Rft | | | | |
| | | | | | | | 371.00 | Rft | 233.75 | 1 | Rs. 86,721 | |
| 27 | 7 | 30 | Supplying and filling sand under floor; or plugging in wells. Less foundation | 53 -53 | 3.00 2.00 | 3.00 2.00 | 3.75 3.75 | 1,788.75 (795.00) | | | | |
| | | | | | | | 993.75 | Cft | 2,943.30 | 100 | Rs. 29,249 | |
| 28 | 25 | 9 | Small iron work, such as gusset plates, knees, bends, stirrups, straps, rings, etc. including cutting, drilling, riveting, handling, assembling and fixing; but excluding erection in position. (Supply & Installation of 470x470x20 mm Base plate for 10 meter Single & Double Arms Poles.) | 53 | 0.47 | 0.47 | 0.02 | 1,838.11 | Kg | | | |
| | | | | | | | 1,838.11 | Kg | 41,131.85 | 100 | Rs. 756,048 | |
| | | | Sub Head 2: laying of Underground Cables | | | | | | | | | |
| 29 | | 3/7/i | Earthwork excavation in open cutting upto 5'-0" (1.5 m) depth for storm water channels, drains, sillage drains in open areas, roads, streets, lanes, including under pinning of walls and shoring to protect existing works, shuttering and timbering the trenches, dressed to designed level and diaphragms, trimming, removal of surface water from trenches, back filling and surplus excavated material disposed of and dressed within 50 ft. (15 m) lead i) Ordinary | 1 | 6,123.72 | 1.50 | 3.00 | 27,556.74 | Cft | | | |
| | | | | | | | | 27,556.74 | Cft | 9,016.70 | 1000 | Rs. 248,471 |
| 30 | 24 | 6-iii | Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:- iii) 100 mm i/d (4 inch) | 0 | 6,123.72 | | | - | Rft | | | |
| | | | | | | | | - | Rft | 290.75 | 1 | Rs. 000 |
| | | | Total Civil Works for Electrical Works | | | | | | | | | |
| | | | | | | | | | | | | Rs. 2,934,252 |

**Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab
Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara
STREET LIGHTING NETWORK TANK CHOWK TO AKBAR ROAD VIA CANAL DISTRICT OKARA
ENGINEERING COST ESTIMATE (ELECTRICAL WORKS)**

| ITEM NO. | Okara 2022 2nd MRS Ref. | DESCRIPTION | UNIT | QTY | RATE (Rs.) | AMOUNT (Rs.) |
|--|----------------------------|---|------|-------|---------------|-----------------|
| Sub Head 1: Street Light Poles | | | | | | |
| 1 | 24/68 | Supplying, installation testing and commissioning of Octagonal shape electric street light pole, made of hot dipped 4.5 mm thick (7 SWG) galvanized steel ,tapered from 225 mm at bottom to 100 mm at top, with 1500 mmx60 mm dia. arm for luminaire installation, duly G.I.welded with 470x470x20 mm base plate with the help of 4 no triangular stiffeners 100x350x20 mm of GI sheet, with built in junction box with shutter, I/c the cost of nuts & J-rag bolts, duly fixed in prelaid concrete foundation, foundation will be paid additionally as approved and directed by the Engineer Incharge. | | | | |
| a | j) | Single Arm 10 Meter | Each | 53 | 106,236.55 | 5,630,537.15 |
| 2 | NS | Supply, installation, testing and commissioning of Pole Base Connection Plates complete comprising of four number (4 Nos.) line up terminal for 35 mm square cables connection for incoming and outgoing, nut & bolts, end covers and stoppers and covers etc. with Main 6 Amp Single Pole MCB at outgoing. make Legrand or equivalent | | | | |
| | | Single Arm 10 Meter | Each | 53 | 3,540.68 | 187,656.09 |
| Sub Head 2: Cables | | | | | | |
| 3 | 24/13/d/iv/v | Supply and erection of copper conductor cables for service connection, in prelaid pipe/G.I. wire/trenches, etc d) PVC insulated, PVC sheathed 4 Core, 600/1000 volt armoured cable:- | | | | |
| | v | 25 mm ² 4-Core Cable. | Rft | 30 | 1,340.70 | 40,221.00 |
| | iv | 16 mm ² 4-Core Cable. | Rft | 10882 | 816.10 | 8,880,800.20 |
| 4 | 24/13/a/iii | Supply and erection of copper conductor cables for service connection, in prelaid pipe/G.I. wire/trenches, etc a) PVC insulated, PVC sheathed twin core, 250/440 volts. iii) 2.5mmsq [7/0.74 mm (7/0.029")] | Rft | 2198 | 86.55 | 190,229.11 |
| Sub Head 3: Conduits | | | | | | |
| 5 | 24/6/iii | Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:- iii) 100 mm i/d (4 inch) | Rft | 6736 | 290.75 | 1,958,512.35 |
| Sub Head 4: Street Light Control Panel (SLCP) | | | | | | |
| | 24/90/a/i | P/F wall mounted DB (Distribution Board) made with 16SWG Sheet (Recessed/Surface mounted Type), Powder coated Paint, i/c the cost of Lock, Indication lights, Thimble, Copper Comb, Wiring, Netural & Earth Bar, Door Earthing, Digital Voltmeter,Digital Ammeter,Volt Selector Switch,Ammeter selector switch,Current Transformers and Controles Complete in all respect as approved and directed by the Engineer Incharge a) 6" Deep i) 20~60A | Each | 1 | 18,634.45 | 18,634.45 |
| | 24/87/a/ii | Incoming Supplying ,Installation and commissioning of MCCB (Moulded Case Circuit Breaker) of specified rating made of LEGRAND FRA NCE/ GE U.S.A / SCHNEIDER GERMANY / TERASAKI JAPAN/SIEMEN/ABB SWITZERLAND (with fixed Thermal-Magnetic Trip) in prelaid DBs and Panels i / c the cost of screws, necessary wire complete in all respect as approved and directed by the Engineer Incharge. a) Tripple Pole (ii) 40 Amp (10 KA) | Each | 1 | 11,433.00 | 11,433.00 |

**Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab
Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara
STREET LIGHTING NETWORK TANK CHOWK TO AKBAR ROAD VIA CANAL DISTRICT OKARA
ENGINEERING COST ESTIMATE (ELECTRICAL WORKS)**

| ITEM NO. | Okara 2022 2nd MRS Ref. | DESCRIPTION | UNIT | QTY | RATE (Rs.) | AMOUNT (Rs.) |
|-------------------------------------|----------------------------|--|------|-----|---------------|-----------------|
| 6 | 24/94/xv/b | Providing and fixing DB/Panel accessories of required rating and size i/c copper screws of approved brand Complete in all respect as approved and directed by the Engineer Incharge. (xv) Magnetic Contactor (b) 40 A (AC 3) for 25 KVAR | Each | 1 | 20,193.00 | 20,193.00 |
| | 24/94/viii | Providing and fixing DB/Panel accessories of required rating and size i/c copper screws of approved brand Complete in all respect as approved and directed by the Engineer Incharge (viii) Control MCB S/P 6A (Make: Schneider/ Terasaki/ABB) | Each | 1 | 1,173.00 | 1,173.00 |
| | 24/94/x | Providing and fixing DB/Panel accessories of required rating and size i/c copper screws of approved brand Complete in all respect as approved and directed by the Engineer Incharge (x) Auto/Manual Switch 3-Steps (Make: GGT/Camsco) | Each | 1 | 1,833.00 | 1,833.00 |
| | NS | Photo Electric Switch Type (10 Amp) | Each | 1 | 16,252.50 | 16,252.50 |
| | 24/21/i | Supply and erection of bus bars, for 500 volts 3 phase A.C.supply with four copper bars, including glazed porcelain bridges, on angle iron board, fixed with rag bolts and M.S.sheet box 1.5 mm thick, etc. complete:- i)60 Amp. with 4 copper bars size 1½"x1/8" (40 x 3 mm) | Each | 1 | 4,924.60 | 4,924.60 |
| | 24/94/vi | Providing and fixing DB/Panel accessories of required rating and size i/c copper screws of approved brand Complete in all respect as approved and directed by the Engineer Incharge (vi) Push Button ON/OFF (Make: Schneider/Himal/Eqv.) | Each | 1 | 447.50 | 447.50 |
| | Outgoing | | | | | |
| 24/86/c/ii | | Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaid DBs and Panels i/c the cost of screwes,necessary wire complete in all respect as approved and directed by the Engineer Incharge. c) Tripple Pole ii) 20 Amps TP 6 KA MCB | Each | 3 | 6,753.00 | 20,259.00 |
| | | c) Tripple Pole ii) 16 Amps TP 6 KA MCB | Each | 2 | 6,753.00 | 13,506.00 |
| | | 16 Amps TP 6 KA MCB as spare | Each | 2 | 6,753.00 | 13,506.00 |
| Sub Head 5: LED Street Light | | | | | | |
| 7 | 24/69/a/v | Supplying, installation and commissioning of LED Cobra-head Luminaries of specified wattage and lumens conforming to IP 65, Philips/Osram/Thorn with corrosion resistant die casted aluminum housing, silicon gas kit, thermally hardened glass complete with LED drivers, surge protection i/c the cost of all accessories/components required for proper operation , fully flexible for future upgradation and easy replacements for maintenance purposes,bucket elevator charges as approved and directed by the Engineer Incharge a) 140 Lm/Watt. (v) 120 Watt with 16800 Lumens <i>The LEDs shall be in compliance with latest NEECA/PEECA standards. Along with the minimum of 5 year Manufacturer's warrenty</i> | Each | 53 | 53,301.85 | 2,824,998.05 |
| Sub Head 5: Replacement LEDs | | | | | | |

**Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab
Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara
STREET LIGHTING NETWORK TANK CHOWK TO AKBAR ROAD VIA CANAL DISTRICT OKARA
ENGINEERING COST ESTIMATE (ELECTRICAL WORKS)**

| ITEM NO. | Okara 2022 2nd MRS Ref. | DESCRIPTION | UNIT | QTY | RATE (Rs.) | AMOUNT (Rs.) |
|----------|----------------------------|---|------|-----|---------------|-----------------|
| 8 | 24/69/a/v | <p>Supplying, installation and commissioning of LED Cobra-head Luminaries of specified wattage and lumens conforming to IP 65, Philips/Osram/Thorn with corrosion resistant die casted aluminum housing, silicon gas kit, thermally hardened glass complete with LED drivers, surge protection i/c the cost of all accessories/components required for proper operation , fully flexible for future upgradation and easy replacements for maintenance purposes, bucket elevator charges as approved and directed by the Engineer Incharge</p> <p>a) 140 Lm/Watt. (v) 50 Watt with 7000 Lumens</p> <p><i>The LEDs shall be in compliance with latest NEECA/PEECA standards. Along with the minimum of 5 year Manufacturer's warrenty</i></p> | Each | 2 | 50,172.95 | 100,345.90 |

**Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab
Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara
STREET LIGHTING NETWORK TANK CHOWK TO AKBAR ROAD VIA CANAL DISTRICT OKARA
ENGINEERING COST ESTIMATE (ELECTRICAL WORKS)**

| ITEM NO. | Okara 2022 2nd MRS Ref. | DESCRIPTION | UNIT | QTY | RATE (Rs.) | AMOUNT (Rs.) |
|---|----------------------------|--|------|-----|---------------|----------------------|
| Sub Head 5: Transformer & Energy Meter | | | | | | |
| 9 | 24/105/iii | Supply, installation, commissioning and testing of oil cooled type, Step down Power Transformer of specified rating, 11/0.415 kV, i/c the cost of lifting hooks, thermometers, LT & HT bushing 5-steps, tap changer, imported double float buchholz relay, 2 earthing terminals, roller wheels, connecting terminals for cables M .S box on transformer i n order to cover complete L.T side, all necessary materials required for connections on H.T & L.T side, rated voltage 11000/415/240 V impedance 6.25% or as specified by WAPDA/IEC system earth: Delta / Star, neutral solidly earthed, i/c Wapda test i ng charges, complete in all respects made of PEL , Siemens, as approved and directed by the Engineer Incharge iii) 25KVA | Each | 1 | 329,487.70 | 329,487.70 |
| 10 | 24/77/b/ii | Supply and erection of electric energy meter, including meter testing fee, etc. b) Three phase, 4 wires: ii) 3x50 Amp, 400 volts | Each | 1 | 14,659.25 | 14,659.25 |
| Sub Head 6: Earthing | | | | | | |
| 11 | 24/70 | Earthing of iron clad/aluminum switches, etc. with G.I. wire No. 8 SWG in G.I. pipe 15 mm (½") dia, recessed or on surface of wall and floor, complete with 1.5 metre long G.I. pipe, 50 mm (2") dia with reducing socket 4 to 5 metre below ground level, and 2 metre away from building plinth. | Job | 1 | 9,592.65 | 9,592.65 |
| 12 | 24/71-i | Earthing of Metallic cases, etc. with G.I. wire No. 8 SWG, in 15 mm (½") dia G.I. pipe, best quality:- i) on surface, including clamps, etc. | Each | 530 | 141.40 | 74,942.00 |
| TOTAL (Rs.) | | | | | | 20,364,143.51 |
| TOTAL (Rs. In Million) | | | | | | 20.364 |

| <p align="center">Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara STREET LIGHTING NETWORK TANK CHOWK TO AKBAR ROAD VIA CANAL DISTRICT OKARA RATE ANALYSIS OF NON- SCHEDULE ITEMS OF ELECTRICAL WORKS</p> | | | | | | | | | | | | | | | | | | | |
|---|-----|------|------------|-----------|---------------------|---------|-----------------------|---------|---------------------|-----------------|--------|-----------------------------|--------|------------|---------------------|------------------|------------|-----------|-----|
| BOQ Item# | Qty | Unit | Unit Price | Cost | Contractor Profit % | | Amount in lieu of Tax | | Total Material Cost | Freight Charges | | Labour / Installation (With | | Income Tax | Total Services Cost | Total Cost /unit | Total Cost | | |
| | | | | | e | f | g | h | | i | o | p | q | | | | | x | y |
| | a | b | c | d | d x e | d x e | d x g | d x g | m | n | o | p | q | x | y | z | cc | dd | |
| | | | | a x c | % | Amount | % | Amount | d + f + h | % | Amount | % | Amount | (o + q) x | o + q + y | dd / a | m + z | | |
| | | | | Pkr | % | Pkr | % | Pkr | Pkr | % | Pkr | % | Pkr | % | Amount | Pkr | Pkr | Pkr | Pkr |
| 2 | 55 | Each | 2,396 | 131,802 | 20% | 26,360 | 17% | 22,406 | 180,569 | 5% | 6,590 | 5% | 6,590 | 7.5% | 989 | 14,169 | 3,541 | 194,737 | |
| 5 | 1 | Each | 11,000 | 11,000 | 20% | 2,200 | 17% | 1,870 | 15,070 | 5% | 550 | 5% | 550 | 7.5% | 83 | 1,183 | 16,253 | 16,253 | |
| 11 | 1 | Job | 62,770 | 62,770 | 20% | 12,554 | 17% | 10,671 | 85,995 | 5% | 3,139 | 5% | 3,139 | 7.5% | 471 | 6,748 | 92,743 | 92,743 | |
| 12 | 55 | Each | 20,240 | 1,113,200 | 20% | 222,640 | 17% | 189,244 | 1,525,084 | 5% | 55,660 | 5% | 55,660 | 7.5% | 8,349 | 119,669 | 29,905 | 1,644,753 | |

**Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab
Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara
Rate Analysis of Raising of Man hole chambers**

Sub - Head B

MEASUREMENT SHEET & ESTIMATE

MRS, 2nd BI-ANNUAL-2022 (01.07.2022 to 31.12.2022) DISTRICT OKARA

| Sr No. | Description of Item | Quantity | Rate | Unit | Amount |
|--------------------|---|-----------|----------|------|-------------------|
| 1 | <p>(Ch.4 item No.19.c) Dismantling cement concrete 1:2:4 plain.</p> <p>1 x 3.142 x 2.58 x 0.75 x 0.50 = 3.0 Cft Total = 3.0 Cft =</p> | 3.04 Cft | 11174.60 | 100 | Rs. 340 |
| 2 | <p>(Ch.7 item No.7i) Pacca brick work other than building upto 10ft. (3 m) height in cement sand mortar ratio 1:3.</p> <p>1 x 3.142 x 2.58 x 0.75 x 0.50 = 3.0 Cft Total = 3.0 Cft =</p> | 3.04 Cft | 33606.10 | 100 | Rs. 1,022 |
| 3 | <p>(Ch.6 item No.5f) Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate):(f) Ratio 1: 2: 4. Arround Manhole Cover</p> <p>1 x 3.142 x 2.58 x 0.75 x 0.50 = 3.04 Total = 3.040 =</p> | 3.04 Cft | 47016.25 | 100 | Rs. 1,429 |
| 4 | <p>(Ch. 11 item No.8b) Cement plaster 1:3 upto 20' (6.00 m) height:-½" (13 mm)</p> <p>2 x 3.142 x 3.33 x 0.75 = 15.69 Sft = 2 x 3.142 x 3.33 x 0.50 = 10.46 Sft = 2 x 3.142 x 3.33 x 0.25 = 5.23 Sft = 2 x 3.142 x 3.33 x 0.50 = 10.46 Sft = Total = 41.85 Sft =</p> | 41.85 Sft | 3424.50 | 100 | Rs. 1,433 |
| 5 | <p>NON MRS RPC Manhole Cover Manufactured with 100% Reinforced Plastic Composite Material, 650 mm dia with clear opening size 600 mm (24" dia) and RPC manhole frame having dia meter 790 mm (Complete) (Certified under ISO 9001-2015)</p> <p>MRS INPUT PRICE = 7,000.00 Installation = 2,000.00 Sub-Total = 9,000.00 Contractor's Overheads and Profit 20% = 1,800.00 Total price for 1 Manhole cover = 10,800.00 =</p> | 1 No. | 10800.00 | 1 | Rs. 10,800 |
| 6 | <p>(Ch. 4 item No.20) Dismantling cement concrete reinforced,separating reinforcement from concrete, cleaning and straightening the same.</p> <p>Dismantling RCC of Existing Man Holes = 1 x 1.60 = 1.60 Cft =</p> | 1.60 Cft | 18285.70 | 100 | Rs. 292.57 |
| TOTAL (A) = | | | | | Rs. 15,316 |

| DEDUCT | | | | | | | | | |
|---------------|--|-----------|--------------|---|------------------|---|------------|-----|-------------------|
| 7 | Deduct Cost of old material available from Manhole covers with 80% depreciated weight & 10% missing Covers i/c dismantling of RCC and separating the steel bars. | | | | | | | | |
| | Old material | | | | | | | | |
| | i) C.I frame | = 1.0 x | 0.90 | x | 37.324 | x | 0.80 | = | 26.9 Kg = |
| | RCC cover | | | | | | | | 26.87 Kg |
| | ii) M.S L-iron frame 2.5"x2.50"x.25" (22" dia) | | | | | | | | 60.00 |
| | Length (each) | = 3.142 x | 26-0.25/12 | x | 1.00 | = | 6.742 | Rft | |
| | Weight (each) | = 6.742 x | 2.5+2.5-0.25 | x | 0.25x480 | = | 12.11 | Kg | |
| | | | | | | | | | 12x12 |
| | wgt.for 1000 | = 1.0 x | 12.11 | x | | = | 12.11 | Kg | |
| | iii) 1/2" M.S bars (Straight bars) | | | | | | | | |
| | | No,s | Length | | Weight/Rft | | Total Wgt. | | |
| | (Straight bars) | = 1.0 x | 2.125 | x | 0.299 | = | 0.636 | Kg | |
| | | = 2.0 x | 2.021 | x | 0.299 | x | 1.210 | Kg | |
| | | = 4.0 x | 1.656 | x | 0.299 | x | 1.984 | Kg | |
| | | | 2.125+0.166+ | | | | | | |
| | (Bent up bars) | = 1.0 x | 0.166 | x | 0.299 | = | 0.736 | Kg | |
| | | = 2.0 x | 2.021+0.166+ | | | | | | |
| | | | 0.166 | x | 0.299 | x | 1.472 | Kg | |
| | | | 2.125+0.138+ | | | | | | |
| | | = 4.0 x | 0.140 | x | 0.299 | x | 2.876 | Kg | |
| | Upper Dit.Rong | = 3.142 x | 1.50 | x | 0.299 | x | 1.411 | Kg | |
| | Lower Dit.Rong | = 3.142 x | 1.25 | x | 0.299 | x | 1.176 | Kg | |
| | Over lap Dit.Ring | = 2.000 x | 0.50 | x | 0.299 | x | 0.299 | Kg | |
| | | | | | Total | | 11.800 | Kg | |
| | wgt.for 811 | = 1.0 x | 0.90 | x | 11.80 | x | 0.800 | = | 8.50 Kg |
| | | | | | Total (ii)+(iii) | | | = | 21 Kg = |
| | Total cost of old material | | | | | | | | 20.61 Kg |
| | | | | | | | | | 90.00 |
| | | | | | | | | | 1 |
| | | | | | | | | | Rs. 1,612 |
| | | | | | | | | | 1 |
| | | | | | | | | | Rs. 1,854 |
| | TOTAL (B) = | | | | | | | | Rs. 3,467 |
| | TOTAL (A-B) = | | | | | | | | Rs. 11,849 |

**Detail Design of Infrastructure Sub - Projects Sectoral Planning &
Resident Supervision in 16 Cities of Punjab**

Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara

MRS, 2nd BI-ANNUAL-2022 (01.07.2022 to 31.12.2022) DISTRICT OKARA

UNIT 100 CFT

| Sr.No | Detail of Item | Unit | | Rate | Amount | |
|---|--|---------|-------|--------|------------------|-----------|
| RATE ANALYSIS FOR SUB - BASE | | | | | | |
| Chapter.18 - Item .3a,ii,b - Page .115 | | | | | | |
| 1 | Providing and laying sub-base course of stone product of approved quality and grade, including placing, mixing, spreading and compaction of sub-base material to required depth, camber, grade to achieve 100% maximum modified AASHO dry density, including carriage of all material to site of work except gravel and aggregate. | | | | | |
| ii) | Crushed stone aggregate. | 100 Cft | | 8,925 | 8,925.00 | |
| Chapter.1 - Item .1 - Page .3 | | | | | | |
| 2 | Carriage of 100 Cft. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by truck or by any other means owned by the contractor. | | | | | |
| Carriage from Kirana Hills Quarry | | | | | | |
| Okara to Pull 11 + Pull 11 to Kirana hills | | | | | | |
| 165 + 1.4 = 166.5 Kms | | | | | | |
| | 1st Km | Km | 1.200 | 299.40 | 359.28 | |
| | 2nd Km | Km | 1.200 | 145.25 | 174.30 | |
| | 3rd Km | Km | 1.200 | 116.85 | 140.22 | |
| | 4th Km | Km | 1.200 | 85.30 | 102.36 | |
| | 5th Km | Km | 1.200 | 80.20 | 96.24 | |
| | 6th Km | Km | 1.200 | 79.00 | 94.80 | |
| | 7th Km | Km | 1.200 | 74.25 | 89.10 | |
| | 8th Km | Km | 1.200 | 73.50 | 88.20 | |
| | 9th Km | Km | 1.200 | 69.55 | 83.46 | |
| | 10th Km | Km | 1.200 | 65.70 | 78.84 | |
| | 10th Kms to 166.4Kms = 156.4Kms | 156.4 | Km | 1.200 | 57.25 | 10,744.68 |
| | Total Carriage | | | | 12,051.48 | |
| | Total Rate for 100 Cft | | | | 20,976.48 | |
| | Rate Per Cft | | | | 209.76 | |

| Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab | | | | | |
|--|---|---------|-------|-----------|------------------|
| Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara | | | | | |
| MRS, 2nd BI-ANNUAL-2022 (01.07.2022 to 31.12.2022) DISTRICT OKARA | | | | UNIT | 100 CFT |
| Sr.No | Detail of Item | Unit | | Rate | Amount |
| RATE ANALYSIS FOR BASE COURSE | | | | | |
| Chapter,18 - Item ,4 (a) page ,116 | | | | | |
| 1 | Providing and laying base course of crushed stone aggregate of approved quality and grade, and supply and spreading of stone screening, including placing, mixing, spreading and compaction of base course material to required depth, camber and grade to achieve 100%maximum modified AASHO dry density, including carriage of all materials to site of work except gravel and aggregate. | | | | |
| ii) | Crushed stone aggregate. | 100 Cft | | 14,002.60 | 14,002.60 |
| Chapter,1 - Item ,1 - Page ,3 | | | | | |
| 2 | Carriage of 100 Cft. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by truck or by any other means owned by the contractor. | | | | |
| Carriage from Kirana Hills Quarry | | | | | |
| Okara to Pull 11 + Pull 11 to Kirana hills | | | | | |
| 165 + 1.4 = 166.5 Kms | | | | | |
| | 1st Km | Km | 1.220 | 299.40 | 365.27 |
| | 2nd Km | Km | 1.220 | 145.25 | 177.21 |
| | 3rd Km | Km | 1.220 | 116.85 | 142.56 |
| | 4th Km | Km | 1.220 | 85.30 | 104.07 |
| | 5th Km | Km | 1.220 | 80.20 | 97.84 |
| | 6th Km | Km | 1.220 | 79.00 | 96.38 |
| | 7th Km | Km | 1.220 | 74.25 | 90.59 |
| | 8th Km | Km | 1.220 | 73.50 | 89.67 |
| | 9th Km | Km | 1.220 | 69.55 | 84.85 |
| | 10th Km | Km | 1.220 | 65.70 | 80.15 |
| | 10th Kms to 166.4Kms = 156.4 | Km | 1.220 | 57.25 | 10,923.76 |
| | Total Carriage | | | | 12,252.34 |
| | Total Rate for 100 Cft | | | | 26,254.94 |
| | Rate Per Cft | | | | 262.55 |

| Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab | | | | | |
|--|--|---------|-------|-----------|------------------|
| Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara | | | | | |
| MRS, 2nd BI-ANNUAL-2022 (01.07.2022 to 31.12.2022) DISTRICT OKARA | | | | UNIT | 100 CFT |
| Sr.No | Detail of Item | Unit | | Rate | Amount |
| | RATE ANALYSIS FOR PCC 1:4:8 Chapter,6 - Item ,5 (i) | | | | |
| 1 | Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate (i) Ratio 1: 4: 8 | | | | |
| ii) | Crushed stone aggregate. | 100 Cft | | 28,986.90 | 28,986.90 |
| | Chapter,1 - Item ,1 - Page ,3 | | | | |
| 2 | Carriage of 100 Cft. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by truck or by any other means owned by the contractor. | | | | |
| | Carriage from Kirana Hills Quarry Okara to Pull 11 + Pull 11 to Kirana hills 165 + 1.4 = 166.5 Kms Consumption Factor = 1.54 x 8 / 13 | | | | |
| | 1st Km | Km | 0.948 | 299.40 | 283.74 |
| | 2nd Km | Km | 0.948 | 145.25 | 137.65 |
| | 3rd Km | Km | 0.948 | 116.85 | 110.74 |
| | 4th Km | Km | 0.948 | 85.30 | 80.84 |
| | 5th Km | Km | 0.948 | 80.20 | 76.00 |
| | 6th Km | Km | 0.948 | 79.00 | 74.87 |
| | 7th Km | Km | 0.948 | 74.25 | 70.37 |
| | 8th Km | Km | 0.948 | 73.50 | 69.66 |
| | 9th Km | Km | 0.948 | 69.55 | 65.91 |
| | 10th Km | Km | 0.948 | 65.70 | 62.26 |
| | 10th Kms to 166.4Kms = 156.4Kms 156.4 | Km | 0.948 | 57.25 | 8,485.54 |
| | Total Carriage | | | | 9,517.58 |
| | Total Rate for 100 Cft | | | | 38,504.48 |
| | Rate Per Cft | | | | 385.04 |

| Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab | | | | | |
|--|--|---------|-------|-----------|------------------|
| Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara | | | | | |
| MRS, 2nd BI-ANNUAL-2022 (01.07.2022 to 31.12.2022) DISTRICT OKARA | | | | UNIT | 100 CFT |
| Sr.No | Detail of Item | Unit | | Rate | Amount |
| | RATE ANALYSIS FOR PCC 1:2:4 Chapter,6 - Item ,5 (f) | | | | |
| 1 | Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate (f) Ratio 1: 2: 4 | | | | |
| ii) | Crushed stone aggregate. | 100 Cft | | 38,178.50 | 38,178.50 |
| | Chapter,1 - Item ,1 - Page .3 | | | | |
| 2 | Carriage of 100 Cft. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by truck or by any other means owned by the contractor. | | | | |
| | Carriage from Kirana Hills Quarry Okara to Pull 11 + Pull 11 to Kirana hills 165 + 1.4 = 166.5 Kms Consumption Factor = 1.54 x 4 / 7 | | | | |
| | 1st Km | Km | 0.880 | 299.40 | 263.47 |
| | 2nd Km | Km | 0.880 | 145.25 | 127.82 |
| | 3rd Km | Km | 0.880 | 116.85 | 102.83 |
| | 4th Km | Km | 0.880 | 85.30 | 75.06 |
| | 5th Km | Km | 0.880 | 80.20 | 70.58 |
| | 6th Km | Km | 0.880 | 79.00 | 69.52 |
| | 7th Km | Km | 0.880 | 74.25 | 65.34 |
| | 8th Km | Km | 0.880 | 73.50 | 64.68 |
| | 9th Km | Km | 0.880 | 69.55 | 61.20 |
| | 10th Km | Km | 0.880 | 65.70 | 57.82 |
| | 10th Kms to 166.4Kms = 156.4Kms 156.4 | Km | 0.880 | 57.25 | 7,879.43 |
| | Total Carriage | | | | 8,837.75 |
| | Total Rate for 100 Cft | | | | 47,016.25 |
| | Rate Per Cft | | | | 470.16 |

| Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab | | | | | |
|--|--|---------|---------|--------|------------------|
| Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara | | | | | |
| MRS, 2nd BI-ANNUAL-2022 (01.07.2022 to 31.12.2022) DISTRICT OKARA | | | | UNIT | 100 CFT |
| Sr.No | Detail of Item | Unit | | Rate | Amount |
| 1 | <p>RATE ANALYSIS FOR RCC 1:2:4 Chapter,6 - Item ,6-a-i-3</p> <p>Providing and laying reinforced cement concrete (including prestressed a) (i) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects:-</p> <p>(3) Type C (nominal mix 1: 2: 4) Crushed stone aggregate.</p> | 100 Cft | 100.000 | 556.50 | 55,650.00 |
| 2 | <p>Chapter,1 - Item ,1 - Page ,3</p> <p>Carriage of 100 Cft. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by truck or by any other means owned by the contractor.</p> <p>Carriage from Kirana Hills Quarry Okara to Pull 11 + Pull 11 to Kirana hills 165 + 1.4 = 166.5 Kms Consumption Factor = 1.54 x 4 / 7</p> | | | | |
| | 1st Km | Km | 0.880 | 299.40 | 263.47 |
| | 2nd Km | Km | 0.880 | 145.25 | 127.82 |
| | 3rd Km | Km | 0.880 | 116.85 | 102.83 |
| | 4th Km | Km | 0.880 | 85.30 | 75.06 |
| | 5th Km | Km | 0.880 | 80.20 | 70.58 |
| | 6th Km | Km | 0.880 | 79.00 | 69.52 |
| | 7th Km | Km | 0.880 | 74.25 | 65.34 |
| | 8th Km | Km | 0.880 | 73.50 | 64.68 |
| | 9th Km | Km | 0.880 | 69.55 | 61.20 |
| | 10th Km | Km | 0.880 | 65.70 | 57.82 |
| | 10th Kms to 166.4Kms = 156.4Kms | 156.4 | Km | 0.880 | 57.25 |
| | Total Carriage | | | | 8,837.75 |
| | Total Rate for 100 Cft | | | | 64,487.75 |
| | Rate Per Cft | | | | 644.88 |

| Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab | | | | | |
|--|---|---------|---------|--------|-----------|
| Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara | | | | | |
| MRS, 2nd BI-ANNUAL-2022 (01.07.2022 to 31.12.2022) DISTRICT OKARA | | | | UNIT | 100 CFT |
| Sr.No | Detail of Item | Unit | | Rate | Amount |
| 1 | <p>RATE ANALYSIS FOR RCC 1:1:2 Chapter,6 - Item ,6-a-i-3</p> <p>Providing and laying reinforced cement concrete (including prestressed a) (i) Reinforced cement concrete in roof slab, beams,columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects:-</p> <p>1) Type A (nominal mix 1:1:2)</p> <p>ii) Crushed stone aggregate.</p> | 100 Cft | 100.000 | 716.30 | 71,630.00 |
| 2 | <p>Chapter,1 - Item ,1 - Page ,3</p> <p>Carriage of 100 Cft. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by truck or by any other means owned by the contractor.</p> <p>Carriage from Kirana Hills Quarry Okara to Pull 11 + Pull 11 to Kirana hills 165 + 1.4 = 166.5 Kms Consumption Factor = 1.54 x 2 / 4</p> <p>1st Km Km 0.770 299.40 230.54 2nd Km Km 0.770 145.25 111.84 3rd Km Km 0.770 116.85 89.97 4th Km Km 0.770 85.30 65.68 5th Km Km 0.770 80.20 61.75 6th Km Km 0.770 79.00 60.83 7th Km Km 0.770 74.25 57.17 8th Km Km 0.770 73.50 56.60 9th Km Km 0.770 69.55 53.55 10th Km Km 0.770 65.70 50.59 10th Kms to 166.4Kms = 156.4Kms 156.4 Km 0.770 57.25 6,894.50</p> <p>Total Carriage 7,733.03 Total Rate for 100 Cft 79,363.03 Rate Per Cft 793.63</p> | | | | |

| Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab | | | | | |
|--|---|------|-----|--------|------------------|
| Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara | | | | | |
| MRS, 2nd BI-ANNUAL-2022 (01.07.2022 to 31.12.2022) DISTRICT OKARA | | | | UNIT | 100 CFT |
| Sr.No | Detail of Item | Unit | | Rate | Amount |
| | RATE ANALYSIS FOR PLANT MIX BITUMEN 2" THICK Chapter,18 - Item ,10a | | | | |
| 1 iv) | Providing and laying plant premixed bituminous 2" thick iv) 4.5% Bitumen | 100 | Sft | 100 | 15,056.50 |
| | Chapter,1 - Item ,1 - Page ,3 | | | | |
| 2 | Carriage of 100 Cft. (2.83 cu.m) of all materials like stone Carriage from Kirana Hills Quarry Okara to Pull 11 + Pull 11 to Kirana hills 165 + 1.4 = 166.5 Kms Consumption Factor = 1.54 x 2 / 4 | | | | |
| | 1st Km | | Km | 0.1400 | 299.40 |
| | 2nd Km | | Km | 0.1400 | 145.25 |
| | 3rd Km | | Km | 0.1400 | 116.85 |
| | 4th Km | | Km | 0.1400 | 85.30 |
| | 5th Km | | Km | 0.1400 | 80.20 |
| | 6th Km | | Km | 0.1400 | 79.00 |
| | 7th Km | | Km | 0.1400 | 74.25 |
| | 8th Km | | Km | 0.1400 | 73.50 |
| | 9th Km | | Km | 0.1400 | 69.55 |
| | 10th Km | | Km | 0.1400 | 65.70 |
| | 10th Kms to 166.4Kms = 156.4Kms | 156 | Km | 0.1400 | 57.25 |
| | Total Carriage | | | | 1,406.01 |
| | Total Rate for 100 Cft | | | | 16,462.51 |
| | Rate Per Cft | | | | 164.63 |

| Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara MRS, 2nd BI-ANNUAL-2022 (01.07.2022 to 31.12.2022) DISTRICT OKARA | | | | | | |
|---|-------|---|----------------------|----------|-----------|-------------|
| Sr.No | Mrs | | Detail of Item | Unit | Rate (Rs) | Amount (Rs) |
| | Chap | Item | | | | |
| 3 | 7 - i | A) <u>EXCAVATION FOR PITS</u> Earthwork excavation in open cutting upto 5'-0" (1.5 m) depth for storm water | 1000 cft | 9,016.70 | 9016.7 | |
| 3 | 17 | i) <u>Ordinary Soil</u> B) <u>EXTRA FOR TRANSPORTATION UPTO 3 KM</u> Transportation of earth all types when the total distance, including the lead covered in the item of work, is more than 1000 ft. (300 m) 2) This rate will be paid in addition to the rate of earthwork, without deducting the a) upto ¼ mile (400 m). b) for every 330 ft. (100 m) additional lead or part thereof, beyond ¼ mile (400 m) upto one mile. (1.6 Km.) $1600 - 400 = 1200 \div 100 = 12 \times 47.5 = 570$ Total 570 c) for every ¼ mile (400 m) additional lead or part thereof, beyond one mile (1.6 Km.) upto 5 mile (8 Km.) $3000 - 1600 = 1400 \div 400 = 3.5 \times 338 = 1184$ Total 1184 S - TOTAL (B) | 1000 Cft | 4248.00 | 4248.00 | |
| | | | | | 1184.40 | |
| | | | | | 6,002.40 | |
| | | | TOTAL (A+B) | 1000 Cft | | 15,019.10 |
| N/S | A) | A) <u>COST OF SWEET SOIL REQUIRED FOR TREE PITS</u> Expected cost taken for estimation | 1000 cft | 3,500.00 | 3,500.00 | |
| 3 | 7 - i | B) <u>EXCAVATION FOR PITS</u> Earthwork excavation in open cutting upto 5'-0" (1.5 m) depth for storm water | 1000 cft | 9,016.70 | 9,016.70 | |
| 3 | 17 | i) <u>Ordinary Soil</u> C) <u>EXTRA FOR TRANSPORTATION UPTO 3 KM</u> Transportation of earth all types when the total distance, including the lead 2) This rate will be paid in addition to the rate of earthwork, without deducting the a) upto ¼ mile (400 m). b) for every 330 ft. (100 m) additional lead or part thereof, beyond ¼ mile (400 m) upto one mile. (1.6 Km.) $1600 - 400 = 1200 \div 100 = 12 \times 47.5 = 570$ Total 570 c) for every ¼ mile (400 m) additional lead or part thereof, beyond one mile (1.6 Km.) upto 5 mile (8 Km.) $3000 - 1600 = 1400 \div 400 = 3.5 \times 338 = 1184$ Total 1184 S - TOTAL (B) | 1000 Cft | 4248.00 | 4248.00 | |
| | | | | | 570.00 | |
| | | | | | 1184.40 | |
| | | | | | 6,002.40 | |
| | | | TOTAL (A+B+C) | 1000 Cft | | 18,519.10 |
| N/S | A) | A) <u>FERTILIZER</u> cow manure fertilizer Cost of Fertilizer | 100 Bag | 10.00 | 1,000.00 | |
| N/S | | B) <u>MIXING WITH SWEET SOIL</u> Mixing with sweet soil | 100 Bag | 2.00 | 200.00 | |
| | | Total | | | - | |
| | | S - TOTAL (B) | | | 1,200.00 | |
| | | | TOTAL (A+B+C) | 1 Bags | | 12.00 |

**Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab
Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara
MRS, 2nd BI-ANNUAL-2022 (01.07.2022 to 31.12.2022) DISTRICT OKARA**

| Sr.No | Mrs | | Detail of Item | Unit | Rate (Rs) | Amount (Rs) |
|-------|------|------|--|--------|-----------|------------------|
| | Chap | Item | | | | |
| | N/S | A) | A) TREES <u>Terminalia Tree</u> Cost of Terminalia Tree | 20 Eac | 3,000.00 | 60,000.00 |
| | N/S | | B) TRANSPORTATION Transportation to site and Plantation (Small Pick-up to be used) | 1 Trip | 1,000.00 | 1,000.00 |
| | | | Total S - TOTAL (B) | | | 61,000.00 |
| | | | TOTAL (A+B+C) | 1 3ags | | 3,050.00 |

| Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab | | | | | | | | | | | |
|--|----------------|-----------------|---|------------------------|-------------------------------|-------------------------------|------------------------------------|---|-----------------------------|----------------------------|--|
| Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara | | | | | | | | | | | |
| Calculation of Quantities | | | | | | | | | | | |
| Basic Data | | | | | | | | | Excavation in Ordinary Soil | | |
| RD | Depth Required | Depth available | Depth available after removing old road | Further depth required | Width of New Carriage Way Rft | Width of Old Carriage Way Rft | Width of Expanded Carriage Way Rft | Excavation under Additional Carriage Way Area = Sft | Further depth required Rft | Quantity of Excavation Cft | |
| 50 | 1.167 | 0.42 | 1.17 | (0.00) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 100 | 1.167 | 0.62 | 1.37 | (0.20) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 150 | 1.167 | 0.58 | 1.33 | (0.16) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 200 | 1.167 | 0.49 | 1.24 | (0.07) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 250 | 1.167 | 0.46 | 1.21 | (0.04) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 300 | 1.167 | 0.35 | 1.10 | 0.07 | 24.00 | 15.5 | 8.50 | 425.00 | 0.07 | 28.48 | |
| 350 | 1.167 | 0.30 | 1.05 | 0.12 | 24.00 | 15.5 | 8.50 | 425.00 | 0.12 | 49.73 | |
| 400 | 1.167 | 0.21 | 0.96 | 0.21 | 24.00 | 15.5 | 8.50 | 425.00 | 0.21 | 87.98 | |
| 450 | 1.167 | 0.34 | 1.09 | 0.08 | 24.00 | 15.5 | 8.50 | 425.00 | 0.08 | 32.73 | |
| 500 | 1.167 | 0.52 | 1.27 | (0.10) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 550 | 1.167 | 0.74 | 1.49 | (0.32) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 600 | 1.167 | 0.79 | 1.54 | (0.37) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 650 | 1.167 | 0.84 | 1.59 | (0.42) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 700 | 1.167 | 0.89 | 1.64 | (0.47) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 750 | 1.167 | 0.93 | 1.68 | (0.51) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 800 | 1.167 | 0.88 | 1.63 | (0.46) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 850 | 1.167 | 0.82 | 1.57 | (0.40) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 900 | 1.167 | 0.94 | 1.69 | (0.52) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 950 | 1.167 | 0.95 | 1.70 | (0.53) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1000 | 1.167 | 0.85 | 1.60 | (0.43) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1050 | 1.167 | 0.81 | 1.56 | (0.39) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1100 | 1.167 | 0.84 | 1.59 | (0.42) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1150 | 1.167 | 0.77 | 1.52 | (0.35) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1200 | 1.167 | 0.70 | 1.45 | (0.28) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1250 | 1.167 | 0.61 | 1.36 | (0.19) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1300 | 1.167 | 0.50 | 1.25 | (0.08) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1350 | 1.167 | 0.47 | 1.22 | (0.05) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1400 | 1.167 | 0.52 | 1.27 | (0.10) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1450 | 1.167 | 0.52 | 1.27 | (0.10) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1500 | 1.167 | 0.54 | 1.29 | (0.12) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1550 | 1.167 | 0.60 | 1.35 | (0.18) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1600 | 1.167 | 0.69 | 1.44 | (0.27) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1650 | 1.167 | 0.71 | 1.46 | (0.29) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1700 | 1.167 | 0.60 | 1.35 | (0.18) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1750 | 1.167 | 0.48 | 1.23 | (0.06) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1800 | 1.167 | 0.53 | 1.28 | (0.11) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1850 | 1.167 | 0.61 | 1.36 | (0.19) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1900 | 1.167 | 0.70 | 1.45 | (0.28) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 1950 | 1.167 | 0.79 | 1.54 | (0.37) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 2000 | 1.167 | 0.89 | 1.64 | (0.47) | 24.00 | 15.5 | 8.50 | 425.00 | | - | |
| 2050 | 1.167 | 0.96 | 1.71 | (0.54) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 2100 | 1.167 | 0.80 | 1.55 | (0.38) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 2150 | 1.167 | 0.64 | 1.39 | (0.22) | 24.00 | 14 | 10.00 | 500.00 | | - | |

| Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab | | | | | | | | | | | |
|---|-------|------|------|--------|-------|----|-------|--------|------------------------------------|-------|--|
| Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara | | | | | | | | | | | |
| Calculation of Quantities | | | | | | | | | | | |
| 3-7-i | | | | | | | | | | | |
| Basic Data | | | | | | | | | Excavation in Ordinary Soil | | |
| 2200 | 1.167 | 0.48 | 1.23 | (0.06) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 2250 | 1.167 | 0.48 | 1.23 | (0.06) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 2300 | 1.167 | 0.42 | 1.17 | (0.00) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 2350 | 1.167 | 0.39 | 1.14 | 0.03 | 24.00 | 14 | 10.00 | 500.00 | 0.03 | 13.50 | |
| 2400 | 1.167 | 0.58 | 1.33 | (0.16) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 2450 | 1.167 | 0.77 | 1.52 | (0.35) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 2500 | 1.167 | 0.91 | 1.66 | (0.49) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 2550 | 1.167 | 0.86 | 1.61 | (0.44) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 2600 | 1.167 | 0.87 | 1.62 | (0.45) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 2650 | 1.167 | 0.91 | 1.66 | (0.49) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 2700 | 1.167 | 0.91 | 1.66 | (0.49) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 2750 | 1.167 | 0.88 | 1.63 | (0.46) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 2800 | 1.167 | 0.88 | 1.63 | (0.46) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 2850 | 1.167 | 0.90 | 1.65 | (0.48) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 2900 | 1.167 | 0.86 | 1.61 | (0.44) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 2950 | 1.167 | 0.86 | 1.61 | (0.44) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3000 | 1.167 | 0.89 | 1.64 | (0.47) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3050 | 1.167 | 0.80 | 1.55 | (0.38) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3100 | 1.167 | 0.77 | 1.52 | (0.35) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3150 | 1.167 | 0.80 | 1.55 | (0.38) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3200 | 1.167 | 0.81 | 1.56 | (0.39) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3250 | 1.167 | 0.79 | 1.54 | (0.37) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3300 | 1.167 | 0.73 | 1.48 | (0.31) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3350 | 1.167 | 0.66 | 1.41 | (0.24) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3400 | 1.167 | 0.63 | 1.38 | (0.21) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3450 | 1.167 | 0.66 | 1.41 | (0.24) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3500 | 1.167 | 0.64 | 1.39 | (0.22) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3550 | 1.167 | 0.53 | 1.28 | (0.11) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3600 | 1.167 | 0.54 | 1.29 | (0.12) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3650 | 1.167 | 0.59 | 1.34 | (0.17) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3700 | 1.167 | 0.77 | 1.52 | (0.35) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3750 | 1.167 | 0.87 | 1.62 | (0.45) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3800 | 1.167 | 0.90 | 1.65 | (0.48) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3850 | 1.167 | 0.88 | 1.63 | (0.46) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3900 | 1.167 | 0.86 | 1.61 | (0.44) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 3950 | 1.167 | 0.78 | 1.53 | (0.36) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 4000 | 1.167 | 0.71 | 1.46 | (0.29) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 4050 | 1.167 | 0.67 | 1.42 | (0.25) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 4100 | 1.167 | 0.72 | 1.47 | (0.30) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 4150 | 1.167 | 0.76 | 1.51 | (0.34) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 4200 | 1.167 | 0.81 | 1.56 | (0.39) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 4250 | 1.167 | 0.82 | 1.57 | (0.40) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 4300 | 1.167 | 0.76 | 1.51 | (0.34) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 4350 | 1.167 | 0.72 | 1.47 | (0.30) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 4400 | 1.167 | 0.69 | 1.44 | (0.27) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 4450 | 1.167 | 0.63 | 1.38 | (0.21) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 4500 | 1.167 | 0.54 | 1.29 | (0.12) | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 4550 | 1.167 | 0.41 | 1.16 | 0.01 | 24.00 | 14 | 10.00 | 500.00 | 0.01 | 3.50 | |
| 4600 | 1.167 | 0.31 | 1.06 | 0.11 | 24.00 | 14 | 10.00 | 500.00 | 0.11 | 53.50 | |
| 4650 | 1.167 | 0.39 | 1.14 | 0.03 | 24.00 | 14 | 10.00 | 500.00 | 0.03 | 13.50 | |

| Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab | | | | | | | | | | | |
|---|-------|------|------|--------|-------|------|-------|--------|------------------------------------|--------|-----------------|
| Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara | | | | | | | | | | | |
| Calculation of Quantities | | | | | | | | | | | |
| Basic Data | | | | | | | | | Excavation in Ordinary Soil | | |
| 4700 | 1.167 | 0.41 | 1.16 | 0.01 | 24.00 | 14 | 10.00 | 500.00 | 0.01 | 3.50 | |
| 4750 | 1.167 | 0.31 | 1.06 | 0.11 | 24.00 | 14.5 | 9.50 | 475.00 | 0.11 | 50.83 | |
| 4800 | 1.167 | 0.25 | 1.00 | 0.17 | 24.00 | 14.5 | 9.50 | 475.00 | 0.17 | 79.33 | |
| 4850 | 1.167 | 0.22 | 0.97 | 0.20 | 24.00 | 14.5 | 9.50 | 475.00 | 0.20 | 93.58 | |
| 4900 | 1.167 | 0.24 | 0.99 | 0.18 | 24.00 | 14.5 | 9.50 | 475.00 | 0.18 | 84.08 | |
| 4950 | 1.167 | 0.30 | 1.05 | 0.12 | 24.00 | 14.5 | 9.50 | 475.00 | 0.12 | 55.58 | |
| 5000 | 1.167 | 0.30 | 1.05 | 0.12 | 24.00 | 14.5 | 9.50 | 475.00 | 0.12 | 55.58 | |
| 5050 | 1.167 | 0.31 | 1.06 | 0.11 | 24.00 | 14.5 | 9.50 | 475.00 | 0.11 | 50.83 | |
| 5100 | 1.167 | 0.39 | 1.14 | 0.03 | 24.00 | 14.5 | 9.50 | 475.00 | 0.03 | 12.83 | |
| 5150 | 1.167 | 0.42 | 1.17 | (0.00) | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5200 | 1.167 | 0.37 | 1.12 | 0.05 | 24.00 | 14.5 | 9.50 | 475.00 | 0.05 | 22.33 | |
| 5250 | 1.167 | 0.37 | 1.12 | 0.05 | 24.00 | 14.5 | 9.50 | 475.00 | 0.05 | 22.33 | |
| 5300 | 1.167 | 0.37 | 1.12 | 0.05 | 24.00 | 14.5 | 9.50 | 475.00 | 0.05 | 22.33 | |
| 5350 | 1.167 | 0.36 | 1.11 | 0.06 | 24.00 | 14.5 | 9.50 | 475.00 | 0.06 | 27.08 | |
| 5400 | 1.167 | 0.38 | 1.13 | 0.04 | 24.00 | 14.5 | 9.50 | 475.00 | 0.04 | 17.58 | |
| 5450 | 1.167 | 0.39 | 1.14 | 0.03 | 24.00 | 14.5 | 9.50 | 475.00 | 0.03 | 12.83 | |
| 5500 | 1.167 | 0.23 | 0.98 | 0.19 | 24.00 | 14.5 | 9.50 | 475.00 | 0.19 | 88.83 | |
| 5550 | 1.167 | 0.09 | 0.84 | 0.33 | 24.00 | 14.5 | 9.50 | 475.00 | 0.33 | 155.33 | |
| 5600 | 1.167 | 0.05 | 0.80 | 0.37 | 24.00 | 14.5 | 9.50 | 475.00 | 0.37 | 174.33 | |
| 5650 | 1.167 | 0.24 | 0.99 | 0.18 | 24.00 | 14.5 | 9.50 | 475.00 | 0.18 | 84.08 | |
| 5700 | 1.167 | 0.42 | 1.17 | (0.00) | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5750 | 1.167 | 0.58 | 1.33 | (0.16) | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5800 | 1.167 | 0.91 | 1.66 | (0.49) | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5850 | 1.167 | 1.34 | 2.09 | (0.92) | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5900 | 1.167 | 1.77 | 2.52 | (1.35) | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5950 | 1.167 | 1.81 | 2.56 | (1.39) | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 6000 | 1.167 | 1.86 | 2.61 | (1.44) | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 6050 | 1.167 | 1.91 | 2.66 | (1.49) | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 6100 | 1.167 | 1.44 | 2.19 | (1.02) | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 6152 | 1.167 | 0.07 | 0.82 | 0.35 | 24.00 | 14.5 | 9.50 | 494.00 | 0.35 | 171.42 | |
| TOTAL QUANTITY | | | | | | | | | | | 1,567.53 |

**Detail Design of Infrastructure Sub - Projects Sectoral Planning &
Resident Supervision in 16 Cities of Punjab
Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along
Calculation of Quantities**

3-5-i

| Basic Data | | | | | | | | | Filling in Carriage Way Area | | |
|------------|----------------|-----------------|---|------------------------|-------------------------------|-------------------------------|------------------------------------|---|------------------------------|--------------------------|--|
| RD | Depth Required | Depth available | Depth available after removing old road | Further depth required | Width of New Carriage Way Rft | Width of Old Carriage Way Rft | Width of Expanded Carriage Way Rft | Excavation under Additional Carriage Way Area = Sft | Filling Depth available Ft | Total Filly Quantity Cft | |
| 50 | 1.167 | 0.42 | 1.17 | (0.00) | 24.00 | 15.5 | 8.50 | 425.00 | 0.00 | 1.27 | |
| 100 | 1.167 | 0.62 | 1.37 | (0.20) | 24.00 | 15.5 | 8.50 | 425.00 | 0.20 | 86.28 | |
| 150 | 1.167 | 0.58 | 1.33 | (0.16) | 24.00 | 15.5 | 8.50 | 425.00 | 0.16 | 69.28 | |
| 200 | 1.167 | 0.49 | 1.24 | (0.07) | 24.00 | 15.5 | 8.50 | 425.00 | 0.07 | 31.03 | |
| 250 | 1.167 | 0.46 | 1.21 | (0.04) | 24.00 | 15.5 | 8.50 | 425.00 | 0.04 | 18.28 | |
| 300 | 1.167 | 0.35 | 1.10 | 0.07 | 24.00 | 15.5 | 8.50 | 425.00 | - | - | |
| 350 | 1.167 | 0.30 | 1.05 | 0.12 | 24.00 | 15.5 | 8.50 | 425.00 | - | - | |
| 400 | 1.167 | 0.21 | 0.96 | 0.21 | 24.00 | 15.5 | 8.50 | 425.00 | - | - | |
| 450 | 1.167 | 0.34 | 1.09 | 0.08 | 24.00 | 15.5 | 8.50 | 425.00 | - | - | |
| 500 | 1.167 | 0.52 | 1.27 | (0.10) | 24.00 | 15.5 | 8.50 | 425.00 | 0.10 | 43.78 | |
| 550 | 1.167 | 0.74 | 1.49 | (0.32) | 24.00 | 15.5 | 8.50 | 425.00 | 0.32 | 137.28 | |
| 600 | 1.167 | 0.79 | 1.54 | (0.37) | 24.00 | 15.5 | 8.50 | 425.00 | 0.37 | 158.53 | |
| 650 | 1.167 | 0.84 | 1.59 | (0.42) | 24.00 | 15.5 | 8.50 | 425.00 | 0.42 | 179.78 | |
| 700 | 1.167 | 0.89 | 1.64 | (0.47) | 24.00 | 15.5 | 8.50 | 425.00 | 0.47 | 201.03 | |
| 750 | 1.167 | 0.93 | 1.68 | (0.51) | 24.00 | 15.5 | 8.50 | 425.00 | 0.51 | 218.03 | |
| 800 | 1.167 | 0.88 | 1.63 | (0.46) | 24.00 | 15.5 | 8.50 | 425.00 | 0.46 | 196.78 | |
| 850 | 1.167 | 0.82 | 1.57 | (0.40) | 24.00 | 15.5 | 8.50 | 425.00 | 0.40 | 171.28 | |
| 900 | 1.167 | 0.94 | 1.69 | (0.52) | 24.00 | 15.5 | 8.50 | 425.00 | 0.52 | 222.28 | |
| 950 | 1.167 | 0.95 | 1.70 | (0.53) | 24.00 | 15.5 | 8.50 | 425.00 | 0.53 | 226.53 | |
| 1000 | 1.167 | 0.85 | 1.60 | (0.43) | 24.00 | 15.5 | 8.50 | 425.00 | 0.43 | 184.03 | |
| 1050 | 1.167 | 0.81 | 1.56 | (0.39) | 24.00 | 15.5 | 8.50 | 425.00 | 0.39 | 167.03 | |
| 1100 | 1.167 | 0.84 | 1.59 | (0.42) | 24.00 | 15.5 | 8.50 | 425.00 | 0.42 | 179.78 | |
| 1150 | 1.167 | 0.77 | 1.52 | (0.35) | 24.00 | 15.5 | 8.50 | 425.00 | 0.35 | 150.03 | |
| 1200 | 1.167 | 0.70 | 1.45 | (0.28) | 24.00 | 15.5 | 8.50 | 425.00 | 0.28 | 120.28 | |
| 1250 | 1.167 | 0.61 | 1.36 | (0.19) | 24.00 | 15.5 | 8.50 | 425.00 | 0.19 | 82.02 | |
| 1300 | 1.167 | 0.50 | 1.25 | (0.08) | 24.00 | 15.5 | 8.50 | 425.00 | 0.08 | 35.28 | |
| 1350 | 1.167 | 0.47 | 1.22 | (0.05) | 24.00 | 15.5 | 8.50 | 425.00 | 0.05 | 22.53 | |
| 1400 | 1.167 | 0.52 | 1.27 | (0.10) | 24.00 | 15.5 | 8.50 | 425.00 | 0.10 | 43.78 | |
| 1450 | 1.167 | 0.52 | 1.27 | (0.10) | 24.00 | 15.5 | 8.50 | 425.00 | 0.10 | 43.78 | |
| 1500 | 1.167 | 0.54 | 1.29 | (0.12) | 24.00 | 15.5 | 8.50 | 425.00 | 0.12 | 52.28 | |
| 1550 | 1.167 | 0.60 | 1.35 | (0.18) | 24.00 | 15.5 | 8.50 | 425.00 | 0.18 | 77.78 | |
| 1600 | 1.167 | 0.69 | 1.44 | (0.27) | 24.00 | 15.5 | 8.50 | 425.00 | 0.27 | 116.03 | |
| 1650 | 1.167 | 0.71 | 1.46 | (0.29) | 24.00 | 15.5 | 8.50 | 425.00 | 0.29 | 124.53 | |
| 1700 | 1.167 | 0.60 | 1.35 | (0.18) | 24.00 | 15.5 | 8.50 | 425.00 | 0.18 | 77.78 | |
| 1750 | 1.167 | 0.48 | 1.23 | (0.06) | 24.00 | 15.5 | 8.50 | 425.00 | 0.06 | 26.78 | |
| 1800 | 1.167 | 0.53 | 1.28 | (0.11) | 24.00 | 15.5 | 8.50 | 425.00 | 0.11 | 48.03 | |
| 1850 | 1.167 | 0.61 | 1.36 | (0.19) | 24.00 | 15.5 | 8.50 | 425.00 | 0.19 | 82.02 | |
| 1900 | 1.167 | 0.70 | 1.45 | (0.28) | 24.00 | 15.5 | 8.50 | 425.00 | 0.28 | 120.28 | |
| 1950 | 1.167 | 0.79 | 1.54 | (0.37) | 24.00 | 15.5 | 8.50 | 425.00 | 0.37 | 158.53 | |
| 2000 | 1.167 | 0.89 | 1.64 | (0.47) | 24.00 | 15.5 | 8.50 | 425.00 | 0.47 | 201.03 | |
| 2050 | 1.167 | 0.96 | 1.71 | (0.54) | 24.00 | 14 | 10.00 | 500.00 | 0.54 | 271.50 | |
| 2100 | 1.167 | 0.80 | 1.55 | (0.38) | 24.00 | 14 | 10.00 | 500.00 | 0.38 | 191.50 | |
| 2150 | 1.167 | 0.64 | 1.39 | (0.22) | 24.00 | 14 | 10.00 | 500.00 | 0.22 | 111.50 | |

**Detail Design of Infrastructure Sub - Projects Sectoral Planning &
Resident Supervision in 16 Cities of Punjab
Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along
Calculation of Quantities**

3-5-i

| Basic Data | | | | | | | | | Filling in Carriage Way Area | | |
|------------|-------|------|------|--------|-------|----|-------|--------|------------------------------|--------|--|
| 2200 | 1.167 | 0.48 | 1.23 | (0.06) | 24.00 | 14 | 10.00 | 500.00 | 0.06 | 31.50 | |
| 2250 | 1.167 | 0.48 | 1.23 | (0.06) | 24.00 | 14 | 10.00 | 500.00 | 0.06 | 31.50 | |
| 2300 | 1.167 | 0.42 | 1.17 | (0.00) | 24.00 | 14 | 10.00 | 500.00 | 0.00 | 1.50 | |
| 2350 | 1.167 | 0.39 | 1.14 | 0.03 | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 2400 | 1.167 | 0.58 | 1.33 | (0.16) | 24.00 | 14 | 10.00 | 500.00 | 0.16 | 81.50 | |
| 2450 | 1.167 | 0.77 | 1.52 | (0.35) | 24.00 | 14 | 10.00 | 500.00 | 0.35 | 176.50 | |
| 2500 | 1.167 | 0.91 | 1.66 | (0.49) | 24.00 | 14 | 10.00 | 500.00 | 0.49 | 246.50 | |
| 2550 | 1.167 | 0.86 | 1.61 | (0.44) | 24.00 | 14 | 10.00 | 500.00 | 0.44 | 221.50 | |
| 2600 | 1.167 | 0.87 | 1.62 | (0.45) | 24.00 | 14 | 10.00 | 500.00 | 0.45 | 226.50 | |
| 2650 | 1.167 | 0.91 | 1.66 | (0.49) | 24.00 | 14 | 10.00 | 500.00 | 0.49 | 246.50 | |
| 2700 | 1.167 | 0.91 | 1.66 | (0.49) | 24.00 | 14 | 10.00 | 500.00 | 0.49 | 246.50 | |
| 2750 | 1.167 | 0.88 | 1.63 | (0.46) | 24.00 | 14 | 10.00 | 500.00 | 0.46 | 231.50 | |
| 2800 | 1.167 | 0.88 | 1.63 | (0.46) | 24.00 | 14 | 10.00 | 500.00 | 0.46 | 231.50 | |
| 2850 | 1.167 | 0.90 | 1.65 | (0.48) | 24.00 | 14 | 10.00 | 500.00 | 0.48 | 241.50 | |
| 2900 | 1.167 | 0.86 | 1.61 | (0.44) | 24.00 | 14 | 10.00 | 500.00 | 0.44 | 221.50 | |
| 2950 | 1.167 | 0.86 | 1.61 | (0.44) | 24.00 | 14 | 10.00 | 500.00 | 0.44 | 221.50 | |
| 3000 | 1.167 | 0.89 | 1.64 | (0.47) | 24.00 | 14 | 10.00 | 500.00 | 0.47 | 236.50 | |
| 3050 | 1.167 | 0.80 | 1.55 | (0.38) | 24.00 | 14 | 10.00 | 500.00 | 0.38 | 191.50 | |
| 3100 | 1.167 | 0.77 | 1.52 | (0.35) | 24.00 | 14 | 10.00 | 500.00 | 0.35 | 176.50 | |
| 3150 | 1.167 | 0.80 | 1.55 | (0.38) | 24.00 | 14 | 10.00 | 500.00 | 0.38 | 191.50 | |
| 3200 | 1.167 | 0.81 | 1.56 | (0.39) | 24.00 | 14 | 10.00 | 500.00 | 0.39 | 196.50 | |
| 3250 | 1.167 | 0.79 | 1.54 | (0.37) | 24.00 | 14 | 10.00 | 500.00 | 0.37 | 186.50 | |
| 3300 | 1.167 | 0.73 | 1.48 | (0.31) | 24.00 | 14 | 10.00 | 500.00 | 0.31 | 156.50 | |
| 3350 | 1.167 | 0.66 | 1.41 | (0.24) | 24.00 | 14 | 10.00 | 500.00 | 0.24 | 121.50 | |
| 3400 | 1.167 | 0.63 | 1.38 | (0.21) | 24.00 | 14 | 10.00 | 500.00 | 0.21 | 106.50 | |
| 3450 | 1.167 | 0.66 | 1.41 | (0.24) | 24.00 | 14 | 10.00 | 500.00 | 0.24 | 121.50 | |
| 3500 | 1.167 | 0.64 | 1.39 | (0.22) | 24.00 | 14 | 10.00 | 500.00 | 0.22 | 111.50 | |
| 3550 | 1.167 | 0.53 | 1.28 | (0.11) | 24.00 | 14 | 10.00 | 500.00 | 0.11 | 56.50 | |
| 3600 | 1.167 | 0.54 | 1.29 | (0.12) | 24.00 | 14 | 10.00 | 500.00 | 0.12 | 61.50 | |
| 3650 | 1.167 | 0.59 | 1.34 | (0.17) | 24.00 | 14 | 10.00 | 500.00 | 0.17 | 86.50 | |
| 3700 | 1.167 | 0.77 | 1.52 | (0.35) | 24.00 | 14 | 10.00 | 500.00 | 0.35 | 176.50 | |
| 3750 | 1.167 | 0.87 | 1.62 | (0.45) | 24.00 | 14 | 10.00 | 500.00 | 0.45 | 226.50 | |
| 3800 | 1.167 | 0.90 | 1.65 | (0.48) | 24.00 | 14 | 10.00 | 500.00 | 0.48 | 241.50 | |
| 3850 | 1.167 | 0.88 | 1.63 | (0.46) | 24.00 | 14 | 10.00 | 500.00 | 0.46 | 231.50 | |
| 3900 | 1.167 | 0.86 | 1.61 | (0.44) | 24.00 | 14 | 10.00 | 500.00 | 0.44 | 221.50 | |
| 3950 | 1.167 | 0.78 | 1.53 | (0.36) | 24.00 | 14 | 10.00 | 500.00 | 0.36 | 181.50 | |
| 4000 | 1.167 | 0.71 | 1.46 | (0.29) | 24.00 | 14 | 10.00 | 500.00 | 0.29 | 146.50 | |
| 4050 | 1.167 | 0.67 | 1.42 | (0.25) | 24.00 | 14 | 10.00 | 500.00 | 0.25 | 126.50 | |
| 4100 | 1.167 | 0.72 | 1.47 | (0.30) | 24.00 | 14 | 10.00 | 500.00 | 0.30 | 151.50 | |
| 4150 | 1.167 | 0.76 | 1.51 | (0.34) | 24.00 | 14 | 10.00 | 500.00 | 0.34 | 171.50 | |
| 4200 | 1.167 | 0.81 | 1.56 | (0.39) | 24.00 | 14 | 10.00 | 500.00 | 0.39 | 196.50 | |
| 4250 | 1.167 | 0.82 | 1.57 | (0.40) | 24.00 | 14 | 10.00 | 500.00 | 0.40 | 201.50 | |
| 4300 | 1.167 | 0.76 | 1.51 | (0.34) | 24.00 | 14 | 10.00 | 500.00 | 0.34 | 171.50 | |
| 4350 | 1.167 | 0.72 | 1.47 | (0.30) | 24.00 | 14 | 10.00 | 500.00 | 0.30 | 151.50 | |
| 4400 | 1.167 | 0.69 | 1.44 | (0.27) | 24.00 | 14 | 10.00 | 500.00 | 0.27 | 136.50 | |
| 4450 | 1.167 | 0.63 | 1.38 | (0.21) | 24.00 | 14 | 10.00 | 500.00 | 0.21 | 106.50 | |
| 4500 | 1.167 | 0.54 | 1.29 | (0.12) | 24.00 | 14 | 10.00 | 500.00 | 0.12 | 61.50 | |
| 4550 | 1.167 | 0.41 | 1.16 | 0.01 | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 4600 | 1.167 | 0.31 | 1.06 | 0.11 | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 4650 | 1.167 | 0.39 | 1.14 | 0.03 | 24.00 | 14 | 10.00 | 500.00 | | - | |

**Detail Design of Infrastructure Sub - Projects Sectoral Planning &
Resident Supervision in 16 Cities of Punjab
Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along
Calculation of Quantities**

3-5-i

| Basic Data | | | | | | | | | Filling in Carriage Way Area | | |
|-----------------------|-------|------|------|--------|-------|------|-------|--------|------------------------------|--------|------------------|
| 4700 | 1.167 | 0.41 | 1.16 | 0.01 | 24.00 | 14 | 10.00 | 500.00 | | - | |
| 4750 | 1.167 | 0.31 | 1.06 | 0.11 | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 4800 | 1.167 | 0.25 | 1.00 | 0.17 | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 4850 | 1.167 | 0.22 | 0.97 | 0.20 | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 4900 | 1.167 | 0.24 | 0.99 | 0.18 | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 4950 | 1.167 | 0.30 | 1.05 | 0.12 | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5000 | 1.167 | 0.30 | 1.05 | 0.12 | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5050 | 1.167 | 0.31 | 1.06 | 0.11 | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5100 | 1.167 | 0.39 | 1.14 | 0.03 | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5150 | 1.167 | 0.42 | 1.17 | (0.00) | 24.00 | 14.5 | 9.50 | 475.00 | 0.00 | 1.42 | |
| 5200 | 1.167 | 0.37 | 1.12 | 0.05 | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5250 | 1.167 | 0.37 | 1.12 | 0.05 | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5300 | 1.167 | 0.37 | 1.12 | 0.05 | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5350 | 1.167 | 0.36 | 1.11 | 0.06 | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5400 | 1.167 | 0.38 | 1.13 | 0.04 | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5450 | 1.167 | 0.39 | 1.14 | 0.03 | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5500 | 1.167 | 0.23 | 0.98 | 0.19 | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5550 | 1.167 | 0.09 | 0.84 | 0.33 | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5600 | 1.167 | 0.05 | 0.80 | 0.37 | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5650 | 1.167 | 0.24 | 0.99 | 0.18 | 24.00 | 14.5 | 9.50 | 475.00 | | - | |
| 5700 | 1.167 | 0.42 | 1.17 | (0.00) | 24.00 | 14.5 | 9.50 | 475.00 | 0.00 | 1.42 | |
| 5750 | 1.167 | 0.58 | 1.33 | (0.16) | 24.00 | 14.5 | 9.50 | 475.00 | 0.16 | 77.43 | |
| 5800 | 1.167 | 0.91 | 1.66 | (0.49) | 24.00 | 14.5 | 9.50 | 475.00 | 0.49 | 234.18 | |
| 5850 | 1.167 | 1.34 | 2.09 | (0.92) | 24.00 | 14.5 | 9.50 | 475.00 | 0.92 | 438.43 | |
| 5900 | 1.167 | 1.77 | 2.52 | (1.35) | 24.00 | 14.5 | 9.50 | 475.00 | 1.35 | 642.68 | |
| 5950 | 1.167 | 1.81 | 2.56 | (1.39) | 24.00 | 14.5 | 9.50 | 475.00 | 1.39 | 661.68 | |
| 6000 | 1.167 | 1.86 | 2.61 | (1.44) | 24.00 | 14.5 | 9.50 | 475.00 | 1.44 | 685.43 | |
| 6050 | 1.167 | 1.91 | 2.66 | (1.49) | 24.00 | 14.5 | 9.50 | 475.00 | 1.49 | 709.18 | |
| 6100 | 1.167 | 1.44 | 2.19 | (1.02) | 24.00 | 14.5 | 9.50 | 475.00 | 1.02 | 485.93 | |
| 6152 | 1.167 | 0.07 | 0.82 | 0.35 | 24.00 | 14.5 | 9.50 | 494.00 | | - | |
| TOTAL QUANTITY | | | | | | | | | | | 16,146.33 |

Detail Design of Infrastructure Sub - Projects Sectoral Planning &

Resident Supervision in 16 Cities of Punjab

Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara

Calculation of Quantities

3-7-ii

| Basic Data | | | | | | | | Excavation in Hard Soil (WBM) | | | |
|------------|----------------|-----------------|---|------------------------|------------------|------------------------------------|--------------------|-------------------------------|---------------------|----------------------------|--|
| RD | Depth Required | Depth available | Depth available after removing old road | Further depth required | Old Carriage Way | Rmoval of 2" thick TPT surface Sft | Removal of WBM Sft | Further depth required | Thickness of WBM Ft | Quantity Removl of WBM Cft | |
| 50 | 1.17 | 0.42 | 1.17 | - | 15.5 | 775.00 | 775 | (0.170) | - | - | |
| 100 | 1.17 | 0.62 | 1.37 | (0.20) | 15.5 | 775.00 | 775 | (0.200) | - | - | |
| 150 | 1.17 | 0.58 | 1.33 | (0.16) | 15.5 | 775.00 | 775 | (0.160) | - | - | |
| 200 | 1.17 | 0.49 | 1.24 | (0.07) | 15.5 | 775.00 | 775 | (0.070) | - | - | |
| 250 | 1.17 | 0.46 | 1.21 | (0.04) | 15.5 | 775.00 | 775 | (0.040) | - | - | |
| 300 | 1.17 | 0.35 | 1.10 | 0.07 | 15.5 | 775.00 | 775 | 0.070 | 0.070 | 54.25 | |
| 350 | 1.17 | 0.30 | 1.05 | 0.12 | 15.5 | 775.00 | 775 | 0.120 | 0.120 | 93.00 | |
| 400 | 1.17 | 0.21 | 0.96 | 0.21 | 15.5 | 775.00 | 775 | 0.210 | 0.210 | 162.75 | |
| 450 | 1.17 | 0.34 | 1.09 | 0.08 | 15.5 | 775.00 | 775 | 0.080 | 0.080 | 62.00 | |
| 500 | 1.17 | 0.52 | 1.27 | (0.10) | 15.5 | 775.00 | 775 | (0.100) | - | - | |
| 550 | 1.17 | 0.74 | 1.49 | (0.32) | 15.5 | 775.00 | 775 | (0.320) | - | - | |
| 600 | 1.17 | 0.79 | 1.54 | (0.37) | 15.5 | 775.00 | 775 | (0.370) | - | - | |
| 650 | 1.17 | 0.84 | 1.59 | (0.42) | 15.5 | 775.00 | 775 | (0.420) | - | - | |
| 700 | 1.17 | 0.89 | 1.64 | (0.47) | 15.5 | 775.00 | 775 | (0.470) | - | - | |
| 750 | 1.17 | 0.93 | 1.68 | (0.51) | 15.5 | 775.00 | 775 | (0.510) | - | - | |
| 800 | 1.17 | 0.88 | 1.63 | (0.46) | 15.5 | 775.00 | 775 | (0.460) | - | - | |
| 850 | 1.17 | 0.82 | 1.57 | (0.40) | 15.5 | 775.00 | 775 | (0.400) | - | - | |
| 900 | 1.17 | 0.94 | 1.69 | (0.52) | 15.5 | 775.00 | 775 | (0.520) | - | - | |
| 950 | 1.17 | 0.95 | 1.70 | (0.53) | 15.5 | 775.00 | 775 | (0.530) | - | - | |
| 1000 | 1.17 | 0.85 | 1.60 | (0.43) | 15.5 | 775.00 | 775 | (0.430) | - | - | |
| 1050 | 1.17 | 0.81 | 1.56 | (0.39) | 15.5 | 775.00 | 775 | (0.390) | - | - | |
| 1100 | 1.17 | 0.84 | 1.59 | (0.42) | 15.5 | 775.00 | 775 | (0.420) | - | - | |
| 1150 | 1.17 | 0.77 | 1.52 | (0.35) | 15.5 | 775.00 | 775 | (0.350) | - | - | |
| 1200 | 1.17 | 0.70 | 1.45 | (0.28) | 15.5 | 775.00 | 775 | (0.280) | - | - | |
| 1250 | 1.17 | 0.61 | 1.36 | (0.19) | 15.5 | 775.00 | 775 | (0.190) | - | - | |
| 1300 | 1.17 | 0.50 | 1.25 | (0.08) | 15.5 | 775.00 | 775 | (0.080) | - | - | |
| 1350 | 1.17 | 0.47 | 1.22 | (0.05) | 15.5 | 775.00 | 775 | (0.050) | - | - | |
| 1400 | 1.17 | 0.52 | 1.27 | (0.10) | 15.5 | 775.00 | 775 | (0.100) | - | - | |
| 1450 | 1.17 | 0.52 | 1.27 | (0.10) | 15.5 | 775.00 | 775 | (0.100) | - | - | |
| 1500 | 1.17 | 0.54 | 1.29 | (0.12) | 15.5 | 775.00 | 775 | (0.120) | - | - | |
| 1550 | 1.17 | 0.60 | 1.35 | (0.18) | 15.5 | 775.00 | 775 | (0.180) | - | - | |
| 1600 | 1.17 | 0.69 | 1.44 | (0.27) | 15.5 | 775.00 | 775 | (0.270) | - | - | |
| 1650 | 1.17 | 0.71 | 1.46 | (0.29) | 15.5 | 775.00 | 775 | (0.290) | - | - | |
| 1700 | 1.17 | 0.60 | 1.35 | (0.18) | 15.5 | 775.00 | 775 | (0.180) | - | - | |
| 1750 | 1.17 | 0.48 | 1.23 | (0.06) | 15.5 | 775.00 | 775 | (0.060) | - | - | |
| 1800 | 1.17 | 0.53 | 1.28 | (0.11) | 15.5 | 775.00 | 775 | (0.110) | - | - | |
| 1850 | 1.17 | 0.61 | 1.36 | (0.19) | 15.5 | 775.00 | 775 | (0.190) | - | - | |
| 1900 | 1.17 | 0.70 | 1.45 | (0.28) | 15.5 | 775.00 | 775 | (0.280) | - | - | |
| 1950 | 1.17 | 0.79 | 1.54 | (0.37) | 15.5 | 775.00 | 775 | (0.370) | - | - | |
| 2000 | 1.17 | 0.89 | 1.64 | (0.47) | 15.5 | 775.00 | 775 | (0.470) | - | - | |
| 2050 | 1.17 | 0.96 | 1.71 | (0.54) | 14 | 700.00 | 700 | (0.540) | - | - | |
| 2100 | 1.17 | 0.80 | 1.55 | (0.38) | 14 | 700.00 | 700 | (0.380) | - | - | |
| 2150 | 1.17 | 0.64 | 1.39 | (0.22) | 14 | 700.00 | 700 | (0.220) | - | - | |

**Detail Design of Infrastructure Sub - Projects Sectoral Planning &
Resident Supervision in 16 Cities of Punjab
Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara
Calculation of Quantities**

| Basic Data | | | | | | | | 3-7-ii Ecavation in Hard Soil (WBM) | | | |
|------------|------|------|------|--------|----|--------|-----|--|-------|-------|--|
| 2200 | 1.17 | 0.48 | 1.23 | (0.06) | 14 | 700.00 | 700 | (0.060) | - | - | |
| 2250 | 1.17 | 0.48 | 1.23 | (0.06) | 14 | 700.00 | 700 | (0.060) | - | - | |
| 2300 | 1.17 | 0.42 | 1.17 | - | 14 | 700.00 | 700 | - | - | - | |
| 2350 | 1.17 | 0.39 | 1.14 | 0.03 | 14 | 700.00 | 700 | 0.030 | 0.030 | 21.00 | |
| 2400 | 1.17 | 0.58 | 1.33 | (0.16) | 14 | 700.00 | 700 | (0.160) | - | - | |
| 2450 | 1.17 | 0.77 | 1.52 | (0.35) | 14 | 700.00 | 700 | (0.350) | - | - | |
| 2500 | 1.17 | 0.91 | 1.66 | (0.49) | 14 | 700.00 | 700 | (0.490) | - | - | |
| 2550 | 1.17 | 0.86 | 1.61 | (0.44) | 14 | 700.00 | 700 | (0.440) | - | - | |
| 2600 | 1.17 | 0.87 | 1.62 | (0.45) | 14 | 700.00 | 700 | (0.450) | - | - | |
| 2650 | 1.17 | 0.91 | 1.66 | (0.49) | 14 | 700.00 | 700 | (0.490) | - | - | |
| 2700 | 1.17 | 0.91 | 1.66 | (0.49) | 14 | 700.00 | 700 | (0.490) | - | - | |
| 2750 | 1.17 | 0.88 | 1.63 | (0.46) | 14 | 700.00 | 700 | (0.460) | - | - | |
| 2800 | 1.17 | 0.88 | 1.63 | (0.46) | 14 | 700.00 | 700 | (0.460) | - | - | |
| 2850 | 1.17 | 0.90 | 1.65 | (0.48) | 14 | 700.00 | 700 | (0.480) | - | - | |
| 2900 | 1.17 | 0.86 | 1.61 | (0.44) | 14 | 700.00 | 700 | (0.440) | - | - | |
| 2950 | 1.17 | 0.86 | 1.61 | (0.44) | 14 | 700.00 | 700 | (0.440) | - | - | |
| 3000 | 1.17 | 0.89 | 1.64 | (0.47) | 14 | 700.00 | 700 | (0.470) | - | - | |
| 3050 | 1.17 | 0.80 | 1.55 | (0.38) | 14 | 700.00 | 700 | (0.380) | - | - | |
| 3100 | 1.17 | 0.77 | 1.52 | (0.35) | 14 | 700.00 | 700 | (0.350) | - | - | |
| 3150 | 1.17 | 0.80 | 1.55 | (0.38) | 14 | 700.00 | 700 | (0.380) | - | - | |
| 3200 | 1.17 | 0.81 | 1.56 | (0.39) | 14 | 700.00 | 700 | (0.390) | - | - | |
| 3250 | 1.17 | 0.79 | 1.54 | (0.37) | 14 | 700.00 | 700 | (0.370) | - | - | |
| 3300 | 1.17 | 0.73 | 1.48 | (0.31) | 14 | 700.00 | 700 | (0.310) | - | - | |
| 3350 | 1.17 | 0.66 | 1.41 | (0.24) | 14 | 700.00 | 700 | (0.240) | - | - | |
| 3400 | 1.17 | 0.63 | 1.38 | (0.21) | 14 | 700.00 | 700 | (0.210) | - | - | |
| 3450 | 1.17 | 0.66 | 1.41 | (0.24) | 14 | 700.00 | 700 | (0.240) | - | - | |
| 3500 | 1.17 | 0.64 | 1.39 | (0.22) | 14 | 700.00 | 700 | (0.220) | - | - | |
| 3550 | 1.17 | 0.53 | 1.28 | (0.11) | 14 | 700.00 | 700 | (0.110) | - | - | |
| 3600 | 1.17 | 0.54 | 1.29 | (0.12) | 14 | 700.00 | 700 | (0.120) | - | - | |
| 3650 | 1.17 | 0.59 | 1.34 | (0.17) | 14 | 700.00 | 700 | (0.170) | - | - | |
| 3700 | 1.17 | 0.77 | 1.52 | (0.35) | 14 | 700.00 | 700 | (0.350) | - | - | |
| 3750 | 1.17 | 0.87 | 1.62 | (0.45) | 14 | 700.00 | 700 | (0.450) | - | - | |
| 3800 | 1.17 | 0.90 | 1.65 | (0.48) | 14 | 700.00 | 700 | (0.480) | - | - | |
| 3850 | 1.17 | 0.88 | 1.63 | (0.46) | 14 | 700.00 | 700 | (0.460) | - | - | |
| 3900 | 1.17 | 0.86 | 1.61 | (0.44) | 14 | 700.00 | 700 | (0.440) | - | - | |
| 3950 | 1.17 | 0.78 | 1.53 | (0.36) | 14 | 700.00 | 700 | (0.360) | - | - | |
| 4000 | 1.17 | 0.71 | 1.46 | (0.29) | 14 | 700.00 | 700 | (0.290) | - | - | |
| 4050 | 1.17 | 0.67 | 1.42 | (0.25) | 14 | 700.00 | 700 | (0.250) | - | - | |
| 4100 | 1.17 | 0.72 | 1.47 | (0.30) | 14 | 700.00 | 700 | (0.300) | - | - | |
| 4150 | 1.17 | 0.76 | 1.51 | (0.34) | 14 | 700.00 | 700 | (0.340) | - | - | |
| 4200 | 1.17 | 0.81 | 1.56 | (0.39) | 14 | 700.00 | 700 | (0.390) | - | - | |
| 4250 | 1.17 | 0.82 | 1.57 | (0.40) | 14 | 700.00 | 700 | (0.400) | - | - | |
| 4300 | 1.17 | 0.76 | 1.51 | (0.34) | 14 | 700.00 | 700 | (0.340) | - | - | |
| 4350 | 1.17 | 0.72 | 1.47 | (0.30) | 14 | 700.00 | 700 | (0.300) | - | - | |
| 4400 | 1.17 | 0.69 | 1.44 | (0.27) | 14 | 700.00 | 700 | (0.270) | - | - | |
| 4450 | 1.17 | 0.63 | 1.38 | (0.21) | 14 | 700.00 | 700 | (0.210) | - | - | |
| 4500 | 1.17 | 0.54 | 1.29 | (0.12) | 14 | 700.00 | 700 | (0.120) | - | - | |
| 4550 | 1.17 | 0.41 | 1.16 | 0.01 | 14 | 700.00 | 700 | 0.010 | 0.010 | 7.00 | |
| 4600 | 1.17 | 0.31 | 1.06 | 0.11 | 14 | 700.00 | 700 | 0.110 | 0.110 | 77.00 | |
| 4650 | 1.17 | 0.39 | 1.14 | 0.03 | 14 | 700.00 | 700 | 0.030 | 0.030 | 21.00 | |

**Detail Design of Infrastructure Sub - Projects Sectoral Planning &
Resident Supervision in 16 Cities of Punjab
Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara
Calculation of Quantities**

3-7-ii

| Basic Data | | | | | | | | Ecavation in Hard Soil (WBM) | | | | |
|------------|-----------------------|------|------|------|--------|------|------------------|------------------------------|---------|-------|--------|-----------------|
| | 4700 | 1.17 | 0.41 | 1.16 | 0.01 | 14 | 700.00 | 700 | 0.010 | 0.010 | 7.00 | |
| | 4750 | 1.17 | 0.31 | 1.06 | 0.11 | 14.5 | 725.00 | 725 | 0.110 | 0.110 | 79.75 | |
| | 4800 | 1.17 | 0.25 | 1.00 | 0.17 | 14.5 | 725.00 | 725 | 0.170 | 0.170 | 123.25 | |
| | 4850 | 1.17 | 0.22 | 0.97 | 0.20 | 14.5 | 725.00 | 725 | 0.200 | 0.200 | 145.00 | |
| | 4900 | 1.17 | 0.24 | 0.99 | 0.18 | 14.5 | 725.00 | 725 | 0.180 | 0.180 | 130.50 | |
| | 4950 | 1.17 | 0.30 | 1.05 | 0.12 | 14.5 | 725.00 | 725 | 0.120 | 0.120 | 87.00 | |
| | 5000 | 1.17 | 0.30 | 1.05 | 0.12 | 14.5 | 725.00 | 725 | 0.120 | 0.120 | 87.00 | |
| | 5050 | 1.17 | 0.31 | 1.06 | 0.11 | 14.5 | 725.00 | 725 | 0.110 | 0.110 | 79.75 | |
| | 5100 | 1.17 | 0.39 | 1.14 | 0.03 | 14.5 | 725.00 | 725 | 0.030 | 0.030 | 21.75 | |
| | 5150 | 1.17 | 0.42 | 1.17 | - | 14.5 | 725.00 | 725 | - | - | - | |
| | 5200 | 1.17 | 0.37 | 1.12 | 0.05 | 14.5 | 725.00 | 725 | 0.050 | 0.050 | 36.25 | |
| | 5250 | 1.17 | 0.37 | 1.12 | 0.05 | 14.5 | 725.00 | 725 | 0.050 | 0.050 | 36.25 | |
| | 5300 | 1.17 | 0.37 | 1.12 | 0.05 | 14.5 | 725.00 | 725 | 0.050 | 0.050 | 36.25 | |
| | 5350 | 1.17 | 0.36 | 1.11 | 0.06 | 14.5 | 725.00 | 725 | 0.060 | 0.060 | 43.50 | |
| | 5400 | 1.17 | 0.38 | 1.13 | 0.04 | 14.5 | 725.00 | 725 | 0.040 | 0.040 | 29.00 | |
| | 5450 | 1.17 | 0.39 | 1.14 | 0.03 | 14.5 | 725.00 | 725 | 0.030 | 0.030 | 21.75 | |
| | 5500 | 1.17 | 0.23 | 0.98 | 0.19 | 14.5 | 725.00 | 725 | 0.190 | 0.190 | 137.75 | |
| | 5550 | 1.17 | 0.09 | 0.84 | 0.33 | 14.5 | 725.00 | 725 | 0.330 | 0.330 | 239.25 | |
| | 5600 | 1.17 | 0.05 | 0.80 | 0.37 | 14.5 | 725.00 | 725 | 0.370 | 0.370 | 268.25 | |
| | 5650 | 1.17 | 0.24 | 0.99 | 0.18 | 14.5 | 725.00 | 725 | 0.180 | 0.180 | 130.50 | |
| | 5700 | 1.17 | 0.42 | 1.17 | - | 14.5 | 725.00 | 725 | - | - | - | |
| | 5750 | 1.17 | 0.58 | 1.33 | (0.16) | 14.5 | 725.00 | 725 | (0.160) | | - | |
| | 5800 | 1.17 | 0.91 | 1.66 | (0.49) | 14.5 | 725.00 | 725 | (0.490) | | - | |
| | 5850 | 1.17 | 1.34 | 2.09 | (0.92) | 14.5 | 725.00 | 725 | (0.920) | | - | |
| | 5900 | 1.17 | 1.77 | 2.52 | (1.35) | 14.5 | 725.00 | 725 | (1.350) | | - | |
| | 5950 | 1.17 | 1.81 | 2.56 | (1.39) | 14.5 | 725.00 | 725 | (1.390) | | - | |
| | 6000 | 1.17 | 1.86 | 2.61 | (1.44) | 14.5 | 725.00 | 725 | (1.440) | | - | |
| | 6050 | 1.17 | 1.91 | 2.66 | (1.49) | 14.5 | 725.00 | 725 | (1.490) | | - | |
| | 6100 | 1.17 | 1.44 | 2.19 | (1.02) | 14.5 | 725.00 | 725 | (1.020) | | - | |
| | 6152 | 1.17 | 0.07 | 0.82 | 0.35 | 14.5 | 754.00 | 754 | 0.350 | 0.350 | 263.90 | |
| | | | | | | | | | - | | | |
| | | | | | | | | | - | | | |
| | TOTAL QUANTITY | | | | | | 89,854.00 | | | | | 2,501.65 |

**Detail Design of Infrastructure Sub - Projects Sectoral Planning &
Resident Supervision in 16 Cities of Punjab
Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk
Calculation of Quantities**

3-5-i

| Basic Data | | | | | | | | Filling in Carriage Way Area | | |
|------------|----------------|-----------------|---|------------------------|------------------|-------------------------------------|--|------------------------------|--------------------------|--|
| RD | Depth Required | Depth available | Depth available after removing old road | Further depth required | Old Carriage Way | Removal of 2" thick TPT surface Sft | Excavation under Old Carriage Way Area = Sft | Filling Depth available Ft | Total Filly Quantity Cft | |
| 50 | 1.17 | 0.42 | 1.17 | - | 15.5 | 775.00 | 775 | - | - | |
| 100 | 1.17 | 0.62 | 1.37 | (0.20) | 15.5 | 775.00 | 775 | 0.20 | 155.00 | |
| 150 | 1.17 | 0.58 | 1.33 | (0.16) | 15.5 | 775.00 | 775 | 0.16 | 124.00 | |
| 200 | 1.17 | 0.49 | 1.24 | (0.07) | 15.5 | 775.00 | 775 | 0.07 | 54.25 | |
| 250 | 1.17 | 0.46 | 1.21 | (0.04) | 15.5 | 775.00 | 775 | 0.04 | 31.00 | |
| 300 | 1.17 | 0.35 | 1.10 | 0.07 | 15.5 | 775.00 | 775 | | - | |
| 350 | 1.17 | 0.30 | 1.05 | 0.12 | 15.5 | 775.00 | 775 | | - | |
| 400 | 1.17 | 0.21 | 0.96 | 0.21 | 15.5 | 775.00 | 775 | | - | |
| 450 | 1.17 | 0.34 | 1.09 | 0.08 | 15.5 | 775.00 | 775 | | - | |
| 500 | 1.17 | 0.52 | 1.27 | (0.10) | 15.5 | 775.00 | 775 | 0.10 | 77.50 | |
| 550 | 1.17 | 0.74 | 1.49 | (0.32) | 15.5 | 775.00 | 775 | 0.32 | 248.00 | |
| 600 | 1.17 | 0.79 | 1.54 | (0.37) | 15.5 | 775.00 | 775 | 0.37 | 286.75 | |
| 650 | 1.17 | 0.84 | 1.59 | (0.42) | 15.5 | 775.00 | 775 | 0.42 | 325.50 | |
| 700 | 1.17 | 0.89 | 1.64 | (0.47) | 15.5 | 775.00 | 775 | 0.47 | 364.25 | |
| 750 | 1.17 | 0.93 | 1.68 | (0.51) | 15.5 | 775.00 | 775 | 0.51 | 395.25 | |
| 800 | 1.17 | 0.88 | 1.63 | (0.46) | 15.5 | 775.00 | 775 | 0.46 | 356.50 | |
| 850 | 1.17 | 0.82 | 1.57 | (0.40) | 15.5 | 775.00 | 775 | 0.40 | 310.00 | |
| 900 | 1.17 | 0.94 | 1.69 | (0.52) | 15.5 | 775.00 | 775 | 0.52 | 403.00 | |
| 950 | 1.17 | 0.95 | 1.70 | (0.53) | 15.5 | 775.00 | 775 | 0.53 | 410.75 | |
| 1000 | 1.17 | 0.85 | 1.60 | (0.43) | 15.5 | 775.00 | 775 | 0.43 | 333.25 | |
| 1050 | 1.17 | 0.81 | 1.56 | (0.39) | 15.5 | 775.00 | 775 | 0.39 | 302.25 | |
| 1100 | 1.17 | 0.84 | 1.59 | (0.42) | 15.5 | 775.00 | 775 | 0.42 | 325.50 | |
| 1150 | 1.17 | 0.77 | 1.52 | (0.35) | 15.5 | 775.00 | 775 | 0.35 | 271.25 | |
| 1200 | 1.17 | 0.70 | 1.45 | (0.28) | 15.5 | 775.00 | 775 | 0.28 | 217.00 | |
| 1250 | 1.17 | 0.61 | 1.36 | (0.19) | 15.5 | 775.00 | 775 | 0.19 | 147.25 | |
| 1300 | 1.17 | 0.50 | 1.25 | (0.08) | 15.5 | 775.00 | 775 | 0.08 | 62.00 | |
| 1350 | 1.17 | 0.47 | 1.22 | (0.05) | 15.5 | 775.00 | 775 | 0.05 | 38.75 | |
| 1400 | 1.17 | 0.52 | 1.27 | (0.10) | 15.5 | 775.00 | 775 | 0.10 | 77.50 | |
| 1450 | 1.17 | 0.52 | 1.27 | (0.10) | 15.5 | 775.00 | 775 | 0.10 | 77.50 | |
| 1500 | 1.17 | 0.54 | 1.29 | (0.12) | 15.5 | 775.00 | 775 | 0.12 | 93.00 | |
| 1550 | 1.17 | 0.60 | 1.35 | (0.18) | 15.5 | 775.00 | 775 | 0.18 | 139.50 | |
| 1600 | 1.17 | 0.69 | 1.44 | (0.27) | 15.5 | 775.00 | 775 | 0.27 | 209.25 | |
| 1650 | 1.17 | 0.71 | 1.46 | (0.29) | 15.5 | 775.00 | 775 | 0.29 | 224.75 | |
| 1700 | 1.17 | 0.60 | 1.35 | (0.18) | 15.5 | 775.00 | 775 | 0.18 | 139.50 | |
| 1750 | 1.17 | 0.48 | 1.23 | (0.06) | 15.5 | 775.00 | 775 | 0.06 | 46.50 | |
| 1800 | 1.17 | 0.53 | 1.28 | (0.11) | 15.5 | 775.00 | 775 | 0.11 | 85.25 | |
| 1850 | 1.17 | 0.61 | 1.36 | (0.19) | 15.5 | 775.00 | 775 | 0.19 | 147.25 | |
| 1900 | 1.17 | 0.70 | 1.45 | (0.28) | 15.5 | 775.00 | 775 | 0.28 | 217.00 | |
| 1950 | 1.17 | 0.79 | 1.54 | (0.37) | 15.5 | 775.00 | 775 | 0.37 | 286.75 | |
| 2000 | 1.17 | 0.89 | 1.64 | (0.47) | 15.5 | 775.00 | 775 | 0.47 | 364.25 | |
| 2050 | 1.17 | 0.96 | 1.71 | (0.54) | 14 | 700.00 | 700 | 0.54 | 378.00 | |
| 2100 | 1.17 | 0.80 | 1.55 | (0.38) | 14 | 700.00 | 700 | 0.38 | 266.00 | |
| 2150 | 1.17 | 0.64 | 1.39 | (0.22) | 14 | 700.00 | 700 | 0.22 | 154.00 | |

| Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab | | | | | | | | | | |
|---|------|------|------|------|--------|----|-------------------------------------|-----|------|--------|
| Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chow | | | | | | | | | | |
| Calculation of Quantities | | | | | | | | | | |
| Basic Data | | | | | | | Filling in Carriage Way Area | | | |
| | 2200 | 1.17 | 0.48 | 1.23 | (0.06) | 14 | 700.00 | 700 | 0.06 | 42.00 |
| | 2250 | 1.17 | 0.48 | 1.23 | (0.06) | 14 | 700.00 | 700 | 0.06 | 42.00 |
| | 2300 | 1.17 | 0.42 | 1.17 | - | 14 | 700.00 | 700 | - | - |
| | 2350 | 1.17 | 0.39 | 1.14 | 0.03 | 14 | 700.00 | 700 | - | - |
| | 2400 | 1.17 | 0.58 | 1.33 | (0.16) | 14 | 700.00 | 700 | 0.16 | 112.00 |
| | 2450 | 1.17 | 0.77 | 1.52 | (0.35) | 14 | 700.00 | 700 | 0.35 | 245.00 |
| | 2500 | 1.17 | 0.91 | 1.66 | (0.49) | 14 | 700.00 | 700 | 0.49 | 343.00 |
| | 2550 | 1.17 | 0.86 | 1.61 | (0.44) | 14 | 700.00 | 700 | 0.44 | 308.00 |
| | 2600 | 1.17 | 0.87 | 1.62 | (0.45) | 14 | 700.00 | 700 | 0.45 | 315.00 |
| | 2650 | 1.17 | 0.91 | 1.66 | (0.49) | 14 | 700.00 | 700 | 0.49 | 343.00 |
| | 2700 | 1.17 | 0.91 | 1.66 | (0.49) | 14 | 700.00 | 700 | 0.49 | 343.00 |
| | 2750 | 1.17 | 0.88 | 1.63 | (0.46) | 14 | 700.00 | 700 | 0.46 | 322.00 |
| | 2800 | 1.17 | 0.88 | 1.63 | (0.46) | 14 | 700.00 | 700 | 0.46 | 322.00 |
| | 2850 | 1.17 | 0.90 | 1.65 | (0.48) | 14 | 700.00 | 700 | 0.48 | 336.00 |
| | 2900 | 1.17 | 0.86 | 1.61 | (0.44) | 14 | 700.00 | 700 | 0.44 | 308.00 |
| | 2950 | 1.17 | 0.86 | 1.61 | (0.44) | 14 | 700.00 | 700 | 0.44 | 308.00 |
| | 3000 | 1.17 | 0.89 | 1.64 | (0.47) | 14 | 700.00 | 700 | 0.47 | 329.00 |
| | 3050 | 1.17 | 0.80 | 1.55 | (0.38) | 14 | 700.00 | 700 | 0.38 | 266.00 |
| | 3100 | 1.17 | 0.77 | 1.52 | (0.35) | 14 | 700.00 | 700 | 0.35 | 245.00 |
| | 3150 | 1.17 | 0.80 | 1.55 | (0.38) | 14 | 700.00 | 700 | 0.38 | 266.00 |
| | 3200 | 1.17 | 0.81 | 1.56 | (0.39) | 14 | 700.00 | 700 | 0.39 | 273.00 |
| | 3250 | 1.17 | 0.79 | 1.54 | (0.37) | 14 | 700.00 | 700 | 0.37 | 259.00 |
| | 3300 | 1.17 | 0.73 | 1.48 | (0.31) | 14 | 700.00 | 700 | 0.31 | 217.00 |
| | 3350 | 1.17 | 0.66 | 1.41 | (0.24) | 14 | 700.00 | 700 | 0.24 | 168.00 |
| | 3400 | 1.17 | 0.63 | 1.38 | (0.21) | 14 | 700.00 | 700 | 0.21 | 147.00 |
| | 3450 | 1.17 | 0.66 | 1.41 | (0.24) | 14 | 700.00 | 700 | 0.24 | 168.00 |
| | 3500 | 1.17 | 0.64 | 1.39 | (0.22) | 14 | 700.00 | 700 | 0.22 | 154.00 |
| | 3550 | 1.17 | 0.53 | 1.28 | (0.11) | 14 | 700.00 | 700 | 0.11 | 77.00 |
| | 3600 | 1.17 | 0.54 | 1.29 | (0.12) | 14 | 700.00 | 700 | 0.12 | 84.00 |
| | 3650 | 1.17 | 0.59 | 1.34 | (0.17) | 14 | 700.00 | 700 | 0.17 | 119.00 |
| | 3700 | 1.17 | 0.77 | 1.52 | (0.35) | 14 | 700.00 | 700 | 0.35 | 245.00 |
| | 3750 | 1.17 | 0.87 | 1.62 | (0.45) | 14 | 700.00 | 700 | 0.45 | 315.00 |
| | 3800 | 1.17 | 0.90 | 1.65 | (0.48) | 14 | 700.00 | 700 | 0.48 | 336.00 |
| | 3850 | 1.17 | 0.88 | 1.63 | (0.46) | 14 | 700.00 | 700 | 0.46 | 322.00 |
| | 3900 | 1.17 | 0.86 | 1.61 | (0.44) | 14 | 700.00 | 700 | 0.44 | 308.00 |
| | 3950 | 1.17 | 0.78 | 1.53 | (0.36) | 14 | 700.00 | 700 | 0.36 | 252.00 |
| | 4000 | 1.17 | 0.71 | 1.46 | (0.29) | 14 | 700.00 | 700 | 0.29 | 203.00 |
| | 4050 | 1.17 | 0.67 | 1.42 | (0.25) | 14 | 700.00 | 700 | 0.25 | 175.00 |
| | 4100 | 1.17 | 0.72 | 1.47 | (0.30) | 14 | 700.00 | 700 | 0.30 | 210.00 |
| | 4150 | 1.17 | 0.76 | 1.51 | (0.34) | 14 | 700.00 | 700 | 0.34 | 238.00 |
| | 4200 | 1.17 | 0.81 | 1.56 | (0.39) | 14 | 700.00 | 700 | 0.39 | 273.00 |
| | 4250 | 1.17 | 0.82 | 1.57 | (0.40) | 14 | 700.00 | 700 | 0.40 | 280.00 |
| | 4300 | 1.17 | 0.76 | 1.51 | (0.34) | 14 | 700.00 | 700 | 0.34 | 238.00 |
| | 4350 | 1.17 | 0.72 | 1.47 | (0.30) | 14 | 700.00 | 700 | 0.30 | 210.00 |
| | 4400 | 1.17 | 0.69 | 1.44 | (0.27) | 14 | 700.00 | 700 | 0.27 | 189.00 |
| | 4450 | 1.17 | 0.63 | 1.38 | (0.21) | 14 | 700.00 | 700 | 0.21 | 147.00 |
| | 4500 | 1.17 | 0.54 | 1.29 | (0.12) | 14 | 700.00 | 700 | 0.12 | 84.00 |
| | 4550 | 1.17 | 0.41 | 1.16 | 0.01 | 14 | 700.00 | 700 | - | - |
| | 4600 | 1.17 | 0.31 | 1.06 | 0.11 | 14 | 700.00 | 700 | - | - |
| | 4650 | 1.17 | 0.39 | 1.14 | 0.03 | 14 | 700.00 | 700 | - | - |

| Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab | | | | | | | | | | |
|---|------|------|------|--------|------|------------------|-----|-------------------------------------|------------------|--|
| Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk | | | | | | | | | | |
| Calculation of Quantities | | | | | | | | 3-5-i | | |
| Basic Data | | | | | | | | Filling in Carriage Way Area | | |
| 4700 | 1.17 | 0.41 | 1.16 | 0.01 | 14 | 700.00 | 700 | - | - | |
| 4750 | 1.17 | 0.31 | 1.06 | 0.11 | 14.5 | 725.00 | 725 | - | - | |
| 4800 | 1.17 | 0.25 | 1.00 | 0.17 | 14.5 | 725.00 | 725 | - | - | |
| 4850 | 1.17 | 0.22 | 0.97 | 0.20 | 14.5 | 725.00 | 725 | - | - | |
| 4900 | 1.17 | 0.24 | 0.99 | 0.18 | 14.5 | 725.00 | 725 | - | - | |
| 4950 | 1.17 | 0.30 | 1.05 | 0.12 | 14.5 | 725.00 | 725 | - | - | |
| 5000 | 1.17 | 0.30 | 1.05 | 0.12 | 14.5 | 725.00 | 725 | - | - | |
| 5050 | 1.17 | 0.31 | 1.06 | 0.11 | 14.5 | 725.00 | 725 | - | - | |
| 5100 | 1.17 | 0.39 | 1.14 | 0.03 | 14.5 | 725.00 | 725 | - | - | |
| 5150 | 1.17 | 0.42 | 1.17 | - | 14.5 | 725.00 | 725 | - | - | |
| 5200 | 1.17 | 0.37 | 1.12 | 0.05 | 14.5 | 725.00 | 725 | - | - | |
| 5250 | 1.17 | 0.37 | 1.12 | 0.05 | 14.5 | 725.00 | 725 | - | - | |
| 5300 | 1.17 | 0.37 | 1.12 | 0.05 | 14.5 | 725.00 | 725 | - | - | |
| 5350 | 1.17 | 0.36 | 1.11 | 0.06 | 14.5 | 725.00 | 725 | - | - | |
| 5400 | 1.17 | 0.38 | 1.13 | 0.04 | 14.5 | 725.00 | 725 | - | - | |
| 5450 | 1.17 | 0.39 | 1.14 | 0.03 | 14.5 | 725.00 | 725 | - | - | |
| 5500 | 1.17 | 0.23 | 0.98 | 0.19 | 14.5 | 725.00 | 725 | - | - | |
| 5550 | 1.17 | 0.09 | 0.84 | 0.33 | 14.5 | 725.00 | 725 | - | - | |
| 5600 | 1.17 | 0.05 | 0.80 | 0.37 | 14.5 | 725.00 | 725 | - | - | |
| 5650 | 1.17 | 0.24 | 0.99 | 0.18 | 14.5 | 725.00 | 725 | - | - | |
| 5700 | 1.17 | 0.42 | 1.17 | - | 14.5 | 725.00 | 725 | - | - | |
| 5750 | 1.17 | 0.58 | 1.33 | (0.16) | 14.5 | 725.00 | 725 | 0.16 | 116.00 | |
| 5800 | 1.17 | 0.91 | 1.66 | (0.49) | 14.5 | 725.00 | 725 | 0.49 | 355.25 | |
| 5850 | 1.17 | 1.34 | 2.09 | (0.92) | 14.5 | 725.00 | 725 | 0.92 | 667.00 | |
| 5900 | 1.17 | 1.77 | 2.52 | (1.35) | 14.5 | 725.00 | 725 | 1.35 | 978.75 | |
| 5950 | 1.17 | 1.81 | 2.56 | (1.39) | 14.5 | 725.00 | 725 | 1.39 | 1,007.75 | |
| 6000 | 1.17 | 1.86 | 2.61 | (1.44) | 14.5 | 725.00 | 725 | 1.44 | 1,044.00 | |
| 6050 | 1.17 | 1.91 | 2.66 | (1.49) | 14.5 | 725.00 | 725 | 1.49 | 1,080.25 | |
| 6100 | 1.17 | 1.44 | 2.19 | (1.02) | 14.5 | 725.00 | 725 | 1.02 | 739.50 | |
| 6152 | 1.17 | 0.07 | 0.82 | 0.35 | 14.5 | 754.00 | 754 | - | - | |
| TOTAL QUANTITY | | | | | | 89,854.00 | | | 24,619.50 | |

Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab
Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara
Calculation of Earth Work Quantities

| Basic Data | | | | | | | | 3-7-i Excavation in Ordinary Soil | | |
|------------|----------------|-----------------|------------------------|--------------------|-----------------------|-----------------------------|---------------------------------------|--------------------------------------|----------------------------|--|
| RD | Depth Required | Depth available | Further depth required | No of Shoulders Ft | Width of Shoulders Ft | Total Width of Shoulders Ft | Excavation under Shoulders Area = Sft | Further depth required Rft | Quantity of Excavation Cft | |
| 50 | 0.917 | 0.42 | 0.50 | 2.00 | 3.5 | 7.00 | 350.00 | 0.50 | 173.95 | |
| 100 | 0.917 | 0.62 | 0.30 | 2.00 | 3.5 | 7.00 | 350.00 | 0.30 | 103.95 | |
| 150 | 0.917 | 0.58 | 0.34 | 2.00 | 3.5 | 7.00 | 350.00 | 0.34 | 117.95 | |
| 200 | 0.917 | 0.49 | 0.43 | 2.00 | 3.5 | 7.00 | 350.00 | 0.43 | 149.45 | |
| 250 | 0.917 | 0.46 | 0.46 | 2.00 | 3.5 | 7.00 | 350.00 | 0.46 | 159.95 | |
| 300 | 0.917 | 0.35 | 0.57 | 2.00 | 3.5 | 7.00 | 350.00 | 0.57 | 198.45 | |
| 350 | 0.917 | 0.30 | 0.62 | 2.00 | 3.5 | 7.00 | 350.00 | 0.62 | 215.95 | |
| 400 | 0.917 | 0.21 | 0.71 | 2.00 | 3.5 | 7.00 | 350.00 | 0.71 | 247.45 | |
| 450 | 0.917 | 0.34 | 0.58 | 2.00 | 3.5 | 7.00 | 350.00 | 0.58 | 201.95 | |
| 500 | 0.917 | 0.52 | 0.40 | 2.00 | 3.5 | 7.00 | 350.00 | 0.40 | 138.95 | |
| 550 | 0.917 | 0.74 | 0.18 | 2.00 | 3.5 | 7.00 | 350.00 | 0.18 | 61.95 | |
| 600 | 0.917 | 0.79 | 0.13 | 2.00 | 3.5 | 7.00 | 350.00 | 0.13 | 44.45 | |
| 650 | 0.917 | 0.84 | 0.08 | 2.00 | 3.5 | 7.00 | 350.00 | 0.08 | 26.95 | |
| 700 | 0.917 | 0.89 | 0.03 | 2.00 | 3.5 | 7.00 | 350.00 | 0.03 | 9.45 | |
| 750 | 0.917 | 0.93 | (0.01) | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 800 | 0.917 | 0.88 | 0.04 | 2.00 | 3.5 | 7.00 | 350.00 | 0.04 | 12.95 | |
| 850 | 0.917 | 0.82 | 0.10 | 2.00 | 3.5 | 7.00 | 350.00 | 0.10 | 33.95 | |
| 900 | 0.917 | 0.94 | (0.02) | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 950 | 0.917 | 0.95 | (0.03) | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 1000 | 0.917 | 0.85 | 0.07 | 2.00 | 3.5 | 7.00 | 350.00 | 0.07 | 23.45 | |
| 1050 | 0.917 | 0.81 | 0.11 | 2.00 | 3.5 | 7.00 | 350.00 | 0.11 | 37.45 | |
| 1100 | 0.917 | 0.84 | 0.08 | 2.00 | 3.5 | 7.00 | 350.00 | 0.08 | 26.95 | |
| 1150 | 0.917 | 0.77 | 0.15 | 2.00 | 3.5 | 7.00 | 350.00 | 0.15 | 51.45 | |
| 1200 | 0.917 | 0.70 | 0.22 | 2.00 | 3.5 | 7.00 | 350.00 | 0.22 | 75.95 | |
| 1250 | 0.917 | 0.61 | 0.31 | 2.00 | 3.5 | 7.00 | 350.00 | 0.31 | 107.45 | |
| 1300 | 0.917 | 0.50 | 0.42 | 2.00 | 3.5 | 7.00 | 350.00 | 0.42 | 145.95 | |
| 1350 | 0.917 | 0.47 | 0.45 | 2.00 | 3.5 | 7.00 | 350.00 | 0.45 | 156.45 | |
| 1400 | 0.917 | 0.52 | 0.40 | 2.00 | 3.5 | 7.00 | 350.00 | 0.40 | 138.95 | |
| 1450 | 0.917 | 0.52 | 0.40 | 2.00 | 3.5 | 7.00 | 350.00 | 0.40 | 138.95 | |
| 1500 | 0.917 | 0.54 | 0.38 | 2.00 | 3.5 | 7.00 | 350.00 | 0.38 | 131.95 | |
| 1550 | 0.917 | 0.60 | 0.32 | 2.00 | 3.5 | 7.00 | 350.00 | 0.32 | 110.95 | |
| 1600 | 0.917 | 0.69 | 0.23 | 2.00 | 3.5 | 7.00 | 350.00 | 0.23 | 79.45 | |
| 1650 | 0.917 | 0.71 | 0.21 | 2.00 | 3.5 | 7.00 | 350.00 | 0.21 | 72.45 | |
| 1700 | 0.917 | 0.60 | 0.32 | 2.00 | 3.5 | 7.00 | 350.00 | 0.32 | 110.95 | |
| 1750 | 0.917 | 0.48 | 0.44 | 2.00 | 3.5 | 7.00 | 350.00 | 0.44 | 152.95 | |
| 1800 | 0.917 | 0.53 | 0.39 | 2.00 | 3.5 | 7.00 | 350.00 | 0.39 | 135.45 | |
| 1850 | 0.917 | 0.61 | 0.31 | 2.00 | 3.5 | 7.00 | 350.00 | 0.31 | 107.45 | |
| 1900 | 0.917 | 0.70 | 0.22 | 2.00 | 3.5 | 7.00 | 350.00 | 0.22 | 75.95 | |
| 1950 | 0.917 | 0.79 | 0.13 | 2.00 | 3.5 | 7.00 | 350.00 | 0.13 | 44.45 | |
| 2000 | 0.917 | 0.89 | 0.03 | 2.00 | 3.5 | 7.00 | 350.00 | 0.03 | 9.45 | |
| 2050 | 0.917 | 0.96 | (0.04) | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 2100 | 0.917 | 0.80 | 0.12 | 2.00 | 3.5 | 7.00 | 350.00 | 0.12 | 40.95 | |
| 2150 | 0.917 | 0.64 | 0.28 | 2.00 | 3.5 | 7.00 | 350.00 | 0.28 | 96.95 | |

**Detail Design of Infrastructure Sub - Projects Sectoral Planning &
Resident Supervision in 16 Cities of Punjab
Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara
Calculation of Earth Work Quantities**

| Basic Data | | | | | | | 3-7-i Excavation in Ordinary Soil | | |
|------------|-------|------|------|------|-----|------|--------------------------------------|------|--------|
| 2200 | 0.917 | 0.48 | 0.44 | 2.00 | 3.5 | 7.00 | 350.00 | 0.44 | 152.95 |
| 2250 | 0.917 | 0.48 | 0.44 | 2.00 | 3.5 | 7.00 | 350.00 | 0.44 | 152.95 |
| 2300 | 0.917 | 0.42 | 0.50 | 2.00 | 3.5 | 7.00 | 350.00 | 0.50 | 173.95 |
| 2350 | 0.917 | 0.39 | 0.53 | 2.00 | 3.5 | 7.00 | 350.00 | 0.53 | 184.45 |
| 2400 | 0.917 | 0.58 | 0.34 | 2.00 | 3.5 | 7.00 | 350.00 | 0.34 | 117.95 |
| 2450 | 0.917 | 0.77 | 0.15 | 2.00 | 3.5 | 7.00 | 350.00 | 0.15 | 51.45 |
| 2500 | 0.917 | 0.91 | 0.01 | 2.00 | 3.5 | 7.00 | 350.00 | 0.01 | 2.45 |
| 2550 | 0.917 | 0.86 | 0.06 | 2.00 | 3.5 | 7.00 | 350.00 | 0.06 | 19.95 |
| 2600 | 0.917 | 0.87 | 0.05 | 2.00 | 3.5 | 7.00 | 350.00 | 0.05 | 16.45 |
| 2650 | 0.917 | 0.91 | 0.01 | 2.00 | 3.5 | 7.00 | 350.00 | 0.01 | 2.45 |
| 2700 | 0.917 | 0.91 | 0.01 | 2.00 | 3.5 | 7.00 | 350.00 | 0.01 | 2.45 |
| 2750 | 0.917 | 0.88 | 0.04 | 2.00 | 3.5 | 7.00 | 350.00 | 0.04 | 12.95 |
| 2800 | 0.917 | 0.88 | 0.04 | 2.00 | 3.5 | 7.00 | 350.00 | 0.04 | 12.95 |
| 2850 | 0.917 | 0.90 | 0.02 | 2.00 | 3.5 | 7.00 | 350.00 | 0.02 | 5.95 |
| 2900 | 0.917 | 0.86 | 0.06 | 2.00 | 3.5 | 7.00 | 350.00 | 0.06 | 19.95 |
| 2950 | 0.917 | 0.86 | 0.06 | 2.00 | 3.5 | 7.00 | 350.00 | 0.06 | 19.95 |
| 3000 | 0.917 | 0.89 | 0.03 | 2.00 | 3.5 | 7.00 | 350.00 | 0.03 | 9.45 |
| 3050 | 0.917 | 0.80 | 0.12 | 2.00 | 3.5 | 7.00 | 350.00 | 0.12 | 40.95 |
| 3100 | 0.917 | 0.77 | 0.15 | 2.00 | 3.5 | 7.00 | 350.00 | 0.15 | 51.45 |
| 3150 | 0.917 | 0.80 | 0.12 | 2.00 | 3.5 | 7.00 | 350.00 | 0.12 | 40.95 |
| 3200 | 0.917 | 0.81 | 0.11 | 2.00 | 3.5 | 7.00 | 350.00 | 0.11 | 37.45 |
| 3250 | 0.917 | 0.79 | 0.13 | 2.00 | 3.5 | 7.00 | 350.00 | 0.13 | 44.45 |
| 3300 | 0.917 | 0.73 | 0.19 | 2.00 | 3.5 | 7.00 | 350.00 | 0.19 | 65.45 |
| 3350 | 0.917 | 0.66 | 0.26 | 2.00 | 3.5 | 7.00 | 350.00 | 0.26 | 89.95 |
| 3400 | 0.917 | 0.63 | 0.29 | 2.00 | 3.5 | 7.00 | 350.00 | 0.29 | 100.45 |
| 3450 | 0.917 | 0.66 | 0.26 | 2.00 | 3.5 | 7.00 | 350.00 | 0.26 | 89.95 |
| 3500 | 0.917 | 0.64 | 0.28 | 2.00 | 3.5 | 7.00 | 350.00 | 0.28 | 96.95 |
| 3550 | 0.917 | 0.53 | 0.39 | 2.00 | 3.5 | 7.00 | 350.00 | 0.39 | 135.45 |
| 3600 | 0.917 | 0.54 | 0.38 | 2.00 | 3.5 | 7.00 | 350.00 | 0.38 | 131.95 |
| 3650 | 0.917 | 0.59 | 0.33 | 2.00 | 3.5 | 7.00 | 350.00 | 0.33 | 114.45 |
| 3700 | 0.917 | 0.77 | 0.15 | 2.00 | 3.5 | 7.00 | 350.00 | 0.15 | 51.45 |
| 3750 | 0.917 | 0.87 | 0.05 | 2.00 | 3.5 | 7.00 | 350.00 | 0.05 | 16.45 |
| 3800 | 0.917 | 0.90 | 0.02 | 2.00 | 3.5 | 7.00 | 350.00 | 0.02 | 5.95 |
| 3850 | 0.917 | 0.88 | 0.04 | 2.00 | 3.5 | 7.00 | 350.00 | 0.04 | 12.95 |
| 3900 | 0.917 | 0.86 | 0.06 | 2.00 | 3.5 | 7.00 | 350.00 | 0.06 | 19.95 |
| 3950 | 0.917 | 0.78 | 0.14 | 2.00 | 3.5 | 7.00 | 350.00 | 0.14 | 47.95 |
| 4000 | 0.917 | 0.71 | 0.21 | 2.00 | 3.5 | 7.00 | 350.00 | 0.21 | 72.45 |
| 4050 | 0.917 | 0.67 | 0.25 | 2.00 | 3.5 | 7.00 | 350.00 | 0.25 | 86.45 |
| 4100 | 0.917 | 0.72 | 0.20 | 2.00 | 3.5 | 7.00 | 350.00 | 0.20 | 68.95 |
| 4150 | 0.917 | 0.76 | 0.16 | 2.00 | 3.5 | 7.00 | 350.00 | 0.16 | 54.95 |
| 4200 | 0.917 | 0.81 | 0.11 | 2.00 | 3.5 | 7.00 | 350.00 | 0.11 | 37.45 |
| 4250 | 0.917 | 0.82 | 0.10 | 2.00 | 3.5 | 7.00 | 350.00 | 0.10 | 33.95 |
| 4300 | 0.917 | 0.76 | 0.16 | 2.00 | 3.5 | 7.00 | 350.00 | 0.16 | 54.95 |
| 4350 | 0.917 | 0.72 | 0.20 | 2.00 | 3.5 | 7.00 | 350.00 | 0.20 | 68.95 |
| 4400 | 0.917 | 0.69 | 0.23 | 2.00 | 3.5 | 7.00 | 350.00 | 0.23 | 79.45 |
| 4450 | 0.917 | 0.63 | 0.29 | 2.00 | 3.5 | 7.00 | 350.00 | 0.29 | 100.45 |
| 4500 | 0.917 | 0.54 | 0.38 | 2.00 | 3.5 | 7.00 | 350.00 | 0.38 | 131.95 |
| 4550 | 0.917 | 0.41 | 0.51 | 2.00 | 3.5 | 7.00 | 350.00 | 0.51 | 177.45 |
| 4600 | 0.917 | 0.31 | 0.61 | 2.00 | 3.5 | 7.00 | 350.00 | 0.61 | 212.45 |
| 4650 | 0.917 | 0.39 | 0.53 | 2.00 | 3.5 | 7.00 | 350.00 | 0.53 | 184.45 |

| Detail Design of Infrastructure Sub - Projects Sectoral Planning & Resident Supervision in 16 Cities of Punjab | | | | | | | | | |
|--|-------|------|------|------|-----|------|------------------|-----------------------------|------------------|
| Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road, Okara | | | | | | | | | |
| Calculation of Earth Work Quantities | | | | | | | | | |
| Basic Data | | | | | | | | 3-7-i | |
| | | | | | | | | Excavation in Ordinary Soil | |
| 4700 | 0.917 | 0.41 | 0.51 | 2.00 | 3.5 | 7.00 | 350.00 | 0.51 | 177.45 |
| 4750 | 0.917 | 0.31 | 0.61 | 2.00 | 3.5 | 7.00 | 350.00 | 0.61 | 212.45 |
| 4800 | 0.917 | 0.25 | 0.67 | 2.00 | 3.5 | 7.00 | 350.00 | 0.67 | 233.45 |
| 4850 | 0.917 | 0.22 | 0.70 | 2.00 | 3.5 | 7.00 | 350.00 | 0.70 | 243.95 |
| 4900 | 0.917 | 0.24 | 0.68 | 2.00 | 3.5 | 7.00 | 350.00 | 0.68 | 236.95 |
| 4950 | 0.917 | 0.30 | 0.62 | 2.00 | 3.5 | 7.00 | 350.00 | 0.62 | 215.95 |
| 5000 | 0.917 | 0.30 | 0.62 | 2.00 | 3.5 | 7.00 | 350.00 | 0.62 | 215.95 |
| 5050 | 0.917 | 0.31 | 0.61 | 2.00 | 3.5 | 7.00 | 350.00 | 0.61 | 212.45 |
| 5100 | 0.917 | 0.39 | 0.53 | 2.00 | 3.5 | 7.00 | 350.00 | 0.53 | 184.45 |
| 5150 | 0.917 | 0.42 | 0.50 | 2.00 | 3.5 | 7.00 | 350.00 | 0.50 | 173.95 |
| 5200 | 0.917 | 0.37 | 0.55 | 2.00 | 3.5 | 7.00 | 350.00 | 0.55 | 191.45 |
| 5250 | 0.917 | 0.37 | 0.55 | 2.00 | 3.5 | 7.00 | 350.00 | 0.55 | 191.45 |
| 5300 | 0.917 | 0.37 | 0.55 | 2.00 | 3.5 | 7.00 | 350.00 | 0.55 | 191.45 |
| 5350 | 0.917 | 0.36 | 0.56 | 2.00 | 3.5 | 7.00 | 350.00 | 0.56 | 194.95 |
| 5400 | 0.917 | 0.38 | 0.54 | 2.00 | 3.5 | 7.00 | 350.00 | 0.54 | 187.95 |
| 5450 | 0.917 | 0.39 | 0.53 | 2.00 | 3.5 | 7.00 | 350.00 | 0.53 | 184.45 |
| 5500 | 0.917 | 0.23 | 0.69 | 2.00 | 3.5 | 7.00 | 350.00 | 0.69 | 240.45 |
| 5550 | 0.917 | 0.09 | 0.83 | 2.00 | 3.5 | 7.00 | 350.00 | 0.83 | 289.45 |
| 5600 | 0.917 | 0.05 | 0.87 | 2.00 | 3.5 | 7.00 | 350.00 | 0.87 | 303.45 |
| 5650 | 0.917 | 0.24 | 0.68 | 2.00 | 3.5 | 7.00 | 350.00 | 0.68 | 236.95 |
| 5700 | 0.917 | 0.42 | 0.50 | 2.00 | 3.5 | 7.00 | 350.00 | 0.50 | 173.95 |
| 5750 | 0.917 | 0.58 | 0.34 | 2.00 | 3.5 | 7.00 | 350.00 | 0.34 | 117.95 |
| 5800 | 0.917 | 0.91 | 0.01 | 2.00 | 3.5 | 7.00 | 350.00 | 0.01 | 2.45 |
| 5850 | 0.917 | 1.34 | | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| 5900 | 0.917 | 1.77 | | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| 5950 | 0.917 | 1.81 | | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| 6000 | 0.917 | 1.86 | | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| 6050 | 0.917 | 1.91 | | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| 6100 | 0.917 | 1.44 | | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| 6152 | 0.917 | 0.07 | 0.85 | 2.00 | 3.5 | 7.00 | 364.00 | 0.85 | 308.31 |
| TOTAL QUANTITY | | | | | | | 43,064.00 | | 12,409.21 |

**Detail Design of Infrastructure Sub - Projects Sectoral Planning &
Resident Supervision in 16 Cities of Punjab
Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk
Calculation of Earth Work Quantities**

3-5-i

| Basic Data | | | | | | | | Filling in Carriage Way Area | | |
|------------|------|----------------|-----------------|------------------------|--------------------|-----------------------|-----------------------------|--|----------------------------|--------------------------|
| | RD | Depth Required | Depth available | Further depth required | No of Shoulders Ft | Width of Shoulders Ft | Total Width of Shoulders Ft | Excavation under Old Carriage Way Area = Sft | Filling Depth available Ft | Total Filly Quantity Cft |
| | 50 | 0.917 | 0.42 | 0.50 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 100 | 0.917 | 0.62 | 0.30 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 150 | 0.917 | 0.58 | 0.34 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 200 | 0.917 | 0.49 | 0.43 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 250 | 0.917 | 0.46 | 0.46 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 300 | 0.917 | 0.35 | 0.57 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 350 | 0.917 | 0.30 | 0.62 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 400 | 0.917 | 0.21 | 0.71 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 450 | 0.917 | 0.34 | 0.58 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 500 | 0.917 | 0.52 | 0.40 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 550 | 0.917 | 0.74 | 0.18 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 600 | 0.917 | 0.79 | 0.13 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 650 | 0.917 | 0.84 | 0.08 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 700 | 0.917 | 0.89 | 0.03 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 750 | 0.917 | 0.93 | (0.01) | 2.00 | 3.5 | 7.00 | 350.00 | 0.01 | 4.55 |
| | 800 | 0.917 | 0.88 | 0.04 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 850 | 0.917 | 0.82 | 0.10 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 900 | 0.917 | 0.94 | (0.02) | 2.00 | 3.5 | 7.00 | 350.00 | 0.02 | 8.05 |
| | 950 | 0.917 | 0.95 | (0.03) | 2.00 | 3.5 | 7.00 | 350.00 | 0.03 | 11.55 |
| | 1000 | 0.917 | 0.85 | 0.07 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 1050 | 0.917 | 0.81 | 0.11 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 1100 | 0.917 | 0.84 | 0.08 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 1150 | 0.917 | 0.77 | 0.15 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 1200 | 0.917 | 0.70 | 0.22 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 1250 | 0.917 | 0.61 | 0.31 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 1300 | 0.917 | 0.50 | 0.42 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 1350 | 0.917 | 0.47 | 0.45 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 1400 | 0.917 | 0.52 | 0.40 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 1450 | 0.917 | 0.52 | 0.40 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 1500 | 0.917 | 0.54 | 0.38 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 1550 | 0.917 | 0.60 | 0.32 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 1600 | 0.917 | 0.69 | 0.23 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 1650 | 0.917 | 0.71 | 0.21 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 1700 | 0.917 | 0.60 | 0.32 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 1750 | 0.917 | 0.48 | 0.44 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 1800 | 0.917 | 0.53 | 0.39 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 1850 | 0.917 | 0.61 | 0.31 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 1900 | 0.917 | 0.70 | 0.22 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 1950 | 0.917 | 0.79 | 0.13 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 2000 | 0.917 | 0.89 | 0.03 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 2050 | 0.917 | 0.96 | (0.04) | 2.00 | 3.5 | 7.00 | 350.00 | 0.04 | 15.05 |
| | 2100 | 0.917 | 0.80 | 0.12 | 2.00 | 3.5 | 7.00 | 350.00 | | - |
| | 2150 | 0.917 | 0.64 | 0.28 | 2.00 | 3.5 | 7.00 | 350.00 | | - |

**Detail Design of Infrastructure Sub - Projects Sectoral Planning &
Resident Supervision in 16 Cities of Punjab
Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk
Calculation of Earth Work Quantities**

3-5-i

| Basic Data | | | | | | | | Filling in Carriage Way Area | | |
|------------|-------|------|------|------|-----|------|--------|------------------------------|---|--|
| 2200 | 0.917 | 0.48 | 0.44 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 2250 | 0.917 | 0.48 | 0.44 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 2300 | 0.917 | 0.42 | 0.50 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 2350 | 0.917 | 0.39 | 0.53 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 2400 | 0.917 | 0.58 | 0.34 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 2450 | 0.917 | 0.77 | 0.15 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 2500 | 0.917 | 0.91 | 0.01 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 2550 | 0.917 | 0.86 | 0.06 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 2600 | 0.917 | 0.87 | 0.05 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 2650 | 0.917 | 0.91 | 0.01 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 2700 | 0.917 | 0.91 | 0.01 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 2750 | 0.917 | 0.88 | 0.04 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 2800 | 0.917 | 0.88 | 0.04 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 2850 | 0.917 | 0.90 | 0.02 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 2900 | 0.917 | 0.86 | 0.06 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 2950 | 0.917 | 0.86 | 0.06 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3000 | 0.917 | 0.89 | 0.03 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3050 | 0.917 | 0.80 | 0.12 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3100 | 0.917 | 0.77 | 0.15 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3150 | 0.917 | 0.80 | 0.12 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3200 | 0.917 | 0.81 | 0.11 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3250 | 0.917 | 0.79 | 0.13 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3300 | 0.917 | 0.73 | 0.19 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3350 | 0.917 | 0.66 | 0.26 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3400 | 0.917 | 0.63 | 0.29 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3450 | 0.917 | 0.66 | 0.26 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3500 | 0.917 | 0.64 | 0.28 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3550 | 0.917 | 0.53 | 0.39 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3600 | 0.917 | 0.54 | 0.38 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3650 | 0.917 | 0.59 | 0.33 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3700 | 0.917 | 0.77 | 0.15 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3750 | 0.917 | 0.87 | 0.05 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3800 | 0.917 | 0.90 | 0.02 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3850 | 0.917 | 0.88 | 0.04 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3900 | 0.917 | 0.86 | 0.06 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 3950 | 0.917 | 0.78 | 0.14 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 4000 | 0.917 | 0.71 | 0.21 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 4050 | 0.917 | 0.67 | 0.25 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 4100 | 0.917 | 0.72 | 0.20 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 4150 | 0.917 | 0.76 | 0.16 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 4200 | 0.917 | 0.81 | 0.11 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 4250 | 0.917 | 0.82 | 0.10 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 4300 | 0.917 | 0.76 | 0.16 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 4350 | 0.917 | 0.72 | 0.20 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 4400 | 0.917 | 0.69 | 0.23 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 4450 | 0.917 | 0.63 | 0.29 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 4500 | 0.917 | 0.54 | 0.38 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 4550 | 0.917 | 0.41 | 0.51 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 4600 | 0.917 | 0.31 | 0.61 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |
| 4650 | 0.917 | 0.39 | 0.53 | 2.00 | 3.5 | 7.00 | 350.00 | - | - | |


**Detail Design of Infrastructure Sub - Projects Sectoral Planning &
Resident Supervision in 16 Cities of Punjab
Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk
Calculation of Earth Work Quantities**

3-5-i

| Basic Data | | | | | | | | Filling in Carriage Way Area | | |
|-----------------------|-------|------|------|------|-----|------|--------|------------------------------|--------|-----------------|
| 4700 | 0.917 | 0.41 | 0.51 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 4750 | 0.917 | 0.31 | 0.61 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 4800 | 0.917 | 0.25 | 0.67 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 4850 | 0.917 | 0.22 | 0.70 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 4900 | 0.917 | 0.24 | 0.68 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 4950 | 0.917 | 0.30 | 0.62 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 5000 | 0.917 | 0.30 | 0.62 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 5050 | 0.917 | 0.31 | 0.61 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 5100 | 0.917 | 0.39 | 0.53 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 5150 | 0.917 | 0.42 | 0.50 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 5200 | 0.917 | 0.37 | 0.55 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 5250 | 0.917 | 0.37 | 0.55 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 5300 | 0.917 | 0.37 | 0.55 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 5350 | 0.917 | 0.36 | 0.56 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 5400 | 0.917 | 0.38 | 0.54 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 5450 | 0.917 | 0.39 | 0.53 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 5500 | 0.917 | 0.23 | 0.69 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 5550 | 0.917 | 0.09 | 0.83 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 5600 | 0.917 | 0.05 | 0.87 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 5650 | 0.917 | 0.24 | 0.68 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 5700 | 0.917 | 0.42 | 0.50 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 5750 | 0.917 | 0.58 | 0.34 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 5800 | 0.917 | 0.91 | 0.01 | 2.00 | 3.5 | 7.00 | 350.00 | | - | |
| 5850 | 0.917 | 1.34 | | 2.00 | 3.5 | 7.00 | 350.00 | 0.42 | 148.05 | |
| 5900 | 0.917 | 1.77 | | 2.00 | 3.5 | 7.00 | 350.00 | 0.85 | 298.55 | |
| 5950 | 0.917 | 1.81 | | 2.00 | 3.5 | 7.00 | 350.00 | 0.89 | 312.55 | |
| 6000 | 0.917 | 1.86 | | 2.00 | 3.5 | 7.00 | 350.00 | 0.94 | 330.05 | |
| 6050 | 0.917 | 1.91 | | 2.00 | 3.5 | 7.00 | 350.00 | 0.99 | 347.55 | |
| 6100 | 0.917 | 1.44 | | 2.00 | 3.5 | 7.00 | 350.00 | 0.52 | 183.05 | |
| 6152 | 0.917 | 0.07 | 0.85 | 2.00 | 3.5 | 7.00 | 364.00 | | - | |
| TOTAL QUANTITY | | | | | | | | | | 1,659.00 |

Improvement, Widening and Raising of Road from Tank Chowk to Akbar

Chowk along Canal Road



ANNEXURE – C

**Economic Analysis, Sensitivity
Analysis & Cost Benefit Ratio**

Punjab Cities Program (PCP)

Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road. Okara City

Annexure C for PC-I

Project Benefits and Analysis

Construction, widening and improving roads of any country are the backbone of social and economic development, enabling the provision of transport and logistics services to passengers & cargo and providing accessibility, which in turn induces mobility.

This project will address the following gaps in the road sector of Okara:-

- Limited access to road infrastructure
- Low quality / poor infrastructure
- High transportation cost

1). Project Economic and Financial Analysis

Economic analyses compares the benefits, costs, and return to the economy as a whole. While, the financial analyses of the project compare direct benefits/revenues, costs and return to the individual investor / enterprise OR operating authority.

1.1. Economics

Effective and efficient road network provides economic benefits that result in multiplier effects such as providing infrastructure results in improving (physical) accessibility that will enhance mobility of people and goods, resulting in improving overall economic welfare.

The proposed study relates to Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road in Okara City

Length, proposed tasks and traffic type on the subject road is as detailed below:

| Sr. No | City Road Names | Length (Km) | Proposed Works | | Traffic Type |
|--------|--|-------------|------------------------------------|---|---------------------------|
| | | | Road Work | Street Lights Works | |
| 1 | Road from Tank Chowk to Akbar Chowk along Canal Road | 1.0214 | Widening / Raising and Improvement | Street Lights - Electrical and Civil Work | Mostly Light city traffic |

Above listed existing road/track under study in Okara City was constructed in past as a good / paved road, however, due to various activities for installation of utilities in these areas, the condition of the road has been deteriorated and needed immediate attention to be improved and widened and ease out the vehicles/ pedestrian traffic at large in the area. Traffic on this road is light city traffic. With the completion of proposed works, a large number of people of the city would be benefitted.

1.1.1. Project Economic Costs

Financial (market) estimates of project Investment (Capital) Costs are estimated as Rs.85.55 Million. These are converted in to Economic Costs by applying Standard Conversion Factor (SCF) of 0.87.

| Sr. No. | Description | Financial Costs | Economic Costs @ 0.87 SCF |
|---------|---|-----------------|------------------------------|
| | | Rs. | |
| 1) | Project Investment Costs | | |
| i. | Road Widening / Improvement / Works | Rs 67,349,609 | Rs 58,594,160 |
| ii. | Street Lights Electrical and Civil Works | Rs 23,298,395 | Rs 20,269,604 |
| iii. | <u>Contingency, taxes, Environment. costs</u> | Rs 7,678,360 | Rs 6,680,173 |
| | <u>Total Investment Costs</u> | Rs 98,326,364 | Rs 85,543,937 |

1.1.2. O&M Costs

The roads are already being repaired and maintained by the District Council Unit Okara out of its own financial resources. No additional cost will be required after completion of the improvement and upgradation of the roads, rather the repair cost will be reduced for the initial years.

1.1.3. Project Economic Benefits

Theoretically, the project involves the provision of a public good so it is set to a number of 'wider' economic benefits to the entire population of the concerned area.

1.1.3.1. Direct Benefits

The major economic direct benefits from the project works include:

- **Road User Benefits**
 - a) Vehicle operating cost savings
 - These include fuel and lubricant costs, spare part cost, tyre cost, maintenance cost and depreciation cost among others
 - b) Travel time saving OR travel delay reductions
- **Other benefits**
 - c) Increase in land values / assets / properties along the project roads

1.1.3.2. Indirect Benefits

Some indirect economic benefits may include:

- a) Reduced traffic congestion
- b) Accident reduction, if any. (Cost of human fatal accident, injury, or hospitalization)
- c) Induced travel, including new trips and changes in mode, route, and time of travel
- d) Better and improved connectivity to further infrastructure.
- e) Reduced fuel consumption due to reduction in stopped vehicular delays (idling fuel consumption)

Benefits of purely socio-economic nature may include:

- a) Increased household income and appreciation in value of land adjacent to project roads, resulting in higher aggregate economic output

- b) The project is expected to generate skilled and non-skilled jobs especially during construction period and onwards for roads maintenance works.
- c) Development of commercial activities along improved / widened proposed project roads, resulting in income generation of project area people.
- d) Overall Social and economic uplift of the project roads area.
- e) Easy / comfortable travelling (made possible due to project works) provides a state of complete physical, mental, and social well-being to the people of the area.

For a project of a relatively mega scale involving main roads or other transport infrastructure, it is possible to quantify some of these benefits such as land appreciation, vehicle operating costs, travel time costs with necessary data inputs such as

- Sizeable average daily traffic data by vehicle type (existing and projected),
- Road geometry, pavement structure, road condition, and vehicle operating cost parameters, using the highway Development Model 4 (HDM-4).
- Vehicle operating cost data
- Travel time cost data etc.

1.1.4. Analysis

However, the proposed works are for the city road, are very small (in length) and do not have sizeable motorized traffic, thereby sizeable economic benefits not expected to accrue and thereby are not quantified and B/C Ratio, NPV and EIRR not calculated.

1.2. Financial Aspects

Provision of efficient / good roads facility is a public good and thereby responsibility of the Government. City road users will not thereby be tolled for using the improved project road. No revenues (public or private) are anticipated to be directly generated. Hence, a financial analysis is not required as there is no positive cash flow or direct revenue stream that contributes to the calculation of an internal rate of return (IRR) or payback period or cost-benefit ratio. There is no land acquisition or resettlement requirement (in case of road's improvement / widening) as the road is owned by the government. Consequently, the capital cost of the project will not be recovered by the public. Any other realized costs after completion will be borne by the government from some other income source, such as municipal budgetary or other earmarked resources.

1.3. Social Benefits with Indicators

With the ease of transportation that comes with the construction of project roads, women will have greater enablement and access to economic opportunities and services. An overall change/uplift in livelihood of people around project site is expected due to increase in employment opportunities, raise in incomes, and raise in commercial activities (shops) along road (if any) etc. The road works would decrease transport costs, ease / increase access to jobs, schools, stores / markets, recreation and other community services and amenities, , foster economic integration, stimulate competition, generate agglomeration economies, encourage citizen satisfaction and build trust with the government. These effects can be reflected in increased land values.

1.4. Employment Generation (direct and indirect)

Increased access to the economy from the improvement of the subject road will increase employment in and across project site. It will also create a positive effect on employees, working in various institutions/offices along project road, in terms of their performance and productivity and, hence wages. During construction, employment for the local people of the project area will be available. There will be indirect employment resulting from easier and greater access to opportunities across local geographies. Expected construction of commercial activities / shops (if any) along proposed road will also result in increased employment generation.

1.5. Environmental Impact and Clean Development Mechanism Assessment

Air emission and greenhouse gas reduction will result from the construction/improvement of project roads. During the construction phase, however, issues may arise from the generation of dust, emission of air pollution, noise, and traffic congestion due to traffic lane reduction and redirection.

Paved / improved road would reduce dust element and hence elimination of challenges to human health.

Positive change in the aesthetic/visual scene of the area would occur due to construction of paved and clean roads and expected plantation / greenery along roadsides (if space available).

1.6. Impact of delays on project cost and viability

Delays in the project will cause the total cost of the project to go up due to ever increasing inflationary pressures.

ANNEXURE – D

Implementation Period (Gant Chart)


Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road

Project Implementation Period Chart

| Sr No | Activity | Month 1 | Month 2 | Month 3 | Month 4 | Month 5 | Month 6 |
|-------|------------------------------------|--|---------|---------|---------|---------|---------|
| 1 | Scarifying and dismantling of Road | ██ | | | | | |
| 2 | Preparation of Sub - Grade | ██ | | | | | |
| 3 | Laying of Sub - Base | ██ | | | | | |
| 4 | Laying of Base Course | ██ | | | | | |
| 5 | Asphalt Wearing- Course | ██ | | | | | |
| 6 | Installation of Street lights | ██ | | | | | |

ANNEXURE – E

Environment Impact Assessment



**Environmental and Social Management Plan (ESMP)
Improvement, Widening and Raising of Road from Tank
Chowk to Akbar Chowk (Canal Road)
MC Okara
November 2022**

Table of Contents

| | |
|--|-----------|
| Executive Summary | 1 |
| Section-1 Introduction | 38 |
| 1.1. Punjab Cities Program (PCP) | 38 |
| 1.2. Environment & Social Management Framework (ESMF) | 38 |
| 1.3. Environment & Social Assessment Categories | 39 |
| 1.3.1. Environmental Categories:..... | 39 |
| 1.3.2. Social Categories:..... | 39 |
| 1.3.3. Environment & Social Assessment Category of the Sub-project | 39 |
| 1.4. Environment & Social Management Plan (ESMP)..... | 40 |
| 1.5. Objectives of ESMP | 40 |
| 1.6. Sub-Project Team | 40 |
| Section-2 Sub-Project Description..... | 41 |
| 2.1. Area Description | 41 |
| 2.2. Problem Statement | 41 |
| 2.3. Description of Work Activities | 42 |
| 2.4. Environmental Management Cost | 42 |
| 2.5. Duration of the Sub-project..... | 42 |
| 2.6. Sub-project Alternatives..... | 42 |
| 2.6.1. Do Nothing Scenario..... | 42 |
| 2.6.2. Site Alternative..... | 43 |
| Section-3 Legal & Policy Framework..... | 44 |
| 3.1. Introduction..... | 44 |
| 3.2. National and Provincial Laws, Regulations, Procedures and Guidelines dealing with the Environmental & Social Aspects | 44 |
| 3.3. World Bank Policy Core Principles and Applicability on Sub-project | 45 |
| 3.4. World Bank Environmental, Health and Social Guidelines | 46 |
| 3.5. PMDFC Environment Health and Safety SOPs for labor/workers (including Women)..... | 46 |
| 3.6. COVID-19 SOPs..... | 46 |
| Section-4 Environment & Social Baseline..... | 47 |
| 4.1. City profile | 47 |
| 4.2. Climate..... | 47 |
| 4.3. Demographic Status | 47 |
| 4.4. Water Resources..... | 47 |
| 4.4.1. Water Quality | 48 |
| 4.5. Solid Waste Management..... | 48 |
| 4.6. Sewerage Facility..... | 48 |
| 4.7. Seismologic Zone | 49 |

| | |
|--|-----------|
| 4.8. Natural Disasters Data | 50 |
| 4.8.1. Potential hazards of the District Okara | 50 |
| 4.9. Environmentally and Socially Sensitive Receptors | 50 |
| 4.10. Flora & Fauna | 50 |
| 4.11. Right of Way and Corridor of Impact | 51 |
| 4.12. Socio - Economic Baseline | 51 |
| 4.12.1. Demographic Characteristics | 51 |
| 4.12.2. Educational institutions | 51 |
| 4.12.3. Housing | 51 |
| 4.12.4. Archaeological, Historical, and Cultural Resources | 51 |
| 4.12.5. Identification of Project Affected Persons (PAP) | 52 |
| Section-5 Stakeholder Consultation | 54 |
| 5.1. General | 54 |
| 5.2. Public Consultation | 54 |
| Section-6 Grievance Redress Mechanism | 59 |
| 6.1. Grievance Redress Mechanism at Sub-Project Site | 59 |
| 6.2. GRM at Regional Level | 60 |
| 6.3. Types of Grievances | 60 |
| Section-7 Environmental and Social Management and Monitoring Plan | 62 |
| 7.1. Objective | 62 |
| 7.2. Institutional Arrangements | 62 |
| 7.2.1. MC Okara | 62 |
| 7.2.2. PMDFC ESM Wing | 62 |
| 7.2.3. The Contractor..... | 63 |
| 7.2.4. Supervisory Consultant..... | 64 |
| 7.3. Monitoring Mechanism | 64 |
| 7.4. Reports | 64 |
| 7.5. Inclusion of ESMP in Bidding/ Contract Documents | 65 |
| 7.6. Environmental and Social Non-Compliance | 65 |
| 7.7. Environmental and Social Management and Monitoring Plan | 65 |
| 7.8. Environmental and Social Management Plan Implementation Budget | 47 |
| Section-8 Capacity Building | 48 |
| 8.1. General | 48 |

List of Figures

| | |
|---|----|
| Figure 2-1: Canal Road Okara | 41 |
| Figure 4-1: Project Area Seismic Zone Location | 49 |
| Figure 4-2: Few Photographs of assets to be partially removed and pole to be relocated | 53 |
| Figure 5-1: Pictorial view of Institutional Consultations..... | 57 |
| Figure 5-2: Pictorial view of Public Consultation..... | 58 |

List of Tables

| | |
|---|----|
| Table 1-1: Composition of Sub-project Team | 40 |
| Table 3-1: National and Provincial Laws, Regulations, Procedures and Guidelines dealing with the Environmental & Social Aspects | 44 |
| Table 4-1: Seismic Zones of Tehsils of Pakistan | 49 |
| Table 4-2: Risk Analysis of Potential Hazards of District Okara..... | 50 |
| Table 7-1: Environmental & Social Management & Monitoring Plan..... | 38 |
| Table 7-2: Environmental Implementation Budget..... | 47 |
| Table 8-1: Training/ Awareness and Sensitization Plan..... | 48 |

List of Annexures

| | |
|---|-----------|
| Annexure i: Environment & Social Screening Checklist..... | 50 |
| Annexure ii: IFC EHS Guidelines for Construction and Decommissioning | 47 |
| Annexure iii: COVID-19 Pandemic and Health Safety Measures | 54 |
| Annexure iv: List of Persons Consulted | 56 |
| Annexure v: Personal Protective Equipment According to Hazard..... | 58 |
| Annexure vi: Chance Find Procedures..... | 0 |

ACRONYMS

| | | | |
|------------------|--|--------------|---|
| AHs | Affected Households | LESCO | Lahore Electric Supply Company |
| BOD | Biological Oxygen Demand | MC | Municipal Corporation/Committee |
| DPO | Deputy Program Officer | MO-I | Municipal Officer Infrastructure |
| CO | Chief Officer | MO-P | Municipal Officer Planning |
| CPMT | Central Program Management Team | NEQS | National Environmental Quality Standards |
| CTS | Complaints Tracking System | NOC | No Objection Certificate |
| DPO | Deputy Program Officer | OHS | Occupational Health & Safety |
| EHS | Environment Health & Safety | OPs | Operational Policies |
| EIA | Environmental Impact Assessment | PAPs | Project Affected Persons |
| EMMP | Environmental Management and Monitoring Plan | PC-I | Planning Commission Form-I |
| EPA | Environment Protection Agency | PCP | Punjab Cities Program |
| EPD | Environment Protection Department | PCRs | Physical Cultural Resources |
| ESFPs | Environmental & Social Focal Persons | PD | Project Director |
| ESM | Environmental & Social Management | PDO | Program Development Objectives |
| ESMF | Environmental & Social Management Framework | PEPA | Punjab Environment Protection Act |
| ESMP | Environmental & Social Management Plan | PHED | Public Health Engineering Department |
| ESMMP | Environmental & Social Management and Monitoring Plan | PMDFC | Punjab Municipal Development Fund Company |
| ESSs | Environmental & Social Safeguards | PMU | Project Management Unit |
| GoP | Government of the Punjab | PPEs | Personal Protective Equipment |
| GRC | Grievance Redress Committee | PO | Program Officer |
| GRM | Grievance Redress Mechanism | RoW | Right of Way |
| HIV/AIDS | Human Immunodeficiency Virus / Acquired Immune Deficiency Syndrome | RPF | Resettlement Policy Framework |
| HSE | Health Safety & Environment | SMP | Social Management Plan |
| IEE | Initial Environmental Examination | SOPs | Standard Operating Procedures |
| LG&CD | Local Government & Community Development | SPOs | Senior Program Officer |
| | | STIs | Site Transmission Infections |
| | | TORs | Terms of References |
| | | WB | World Bank |

Executive Summary

Government of Punjab (Govt. of Punjab) sought support from the World Bank for the economic growth of urban sectors in Punjab and launched Punjab Cities Program (PCP). Program is expected to achieve overarching goals of ending poverty and promoting shared prosperity by delivering improved urban infrastructure inclusively and in ways that enhance economic growth and development in the participating cities. The Project has a number of financial, social, economic and environmental benefits, including institutional development, widening and improvement of municipal services, capital investments, better quality of life and employment generation. In addition, a large number of secondary benefits are also likely to accrue in the medium to long term such as institutional reforms at the local level. Environmental and social management under the program will be largely based on the existing legal, regulatory and institutional systems in Pakistan and in the Punjab province. PCP-IPF Window (technical assistance component) supports the strengthening of social and environmental risk management systems in the participating cities. It will finance the strengthening of:

- a) Social and environmental focal points in each city;
- b) The creation of social and environmental management system at the city level; and
- c) Rolling out a training program by PMDFC for city officials.

This Environmental and Social Management Plan (ESMP) is prepared according to the World Bank Core Principles for PforR financing modality and Environmental and Social laws of Government of Punjab (GoPb). It will be used to identify and mitigate the environmental and social impacts that may emerge during implementation of proposed sub-project “Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road” which will be executed by MC Okara from the financial grant of PCP. This ESMP follows the social and environmental appraisal and compliance as mentioned in the Environmental and Social Management Framework (ESMF) of PCP.

Sub-project Summary:

| | |
|---------------------------------|--|
| Scope of Work | Sub-Project Involves Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road. |
| Location | The alignment of Canal Road exists in between Tank Chowk to Akbar Chowk in Okara City. |
| Sub-project Cost | PKR 100.53 /- Million |
| ESMP Implementation Cost | PKR /-1,333,000 |

| | |
|--------------------------------|---|
| Sub-project Duration | Six months approx. 30/35 workers/labor will be engaged |
| Major Work Activities | <ul style="list-style-type: none"> i. Scarifying and dismantling of road ii. Preparation of sub-grade iii. Laying of sub-base iv. Laying of base course v. Asphalt wearing course vi. Installation of street lights |
| Executing Agency | MC Okara |
| Monitoring Agency | Punjab Municipal Development Fund Company (PMDFC) |
| Sub-project Financed By | World Bank under Punjab Cities Program (PCP) |
| Environmental Category | E-2 |
| Social Category | S-2 |

Environment & Social Management:

This ESMP report presents the sub-project site-specific baseline data, identification, assessment and evaluation of sub-project impacts and environmental management and monitoring plan for mitigation of adverse impacts that may arise due to the proposed sub-project interventions.

Screening of Impacts:

Environment and social screening checklist included in the ESMF to screen the sub-projects has been used to screen the impacts of “Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk (Canal Road)” and filled as per the environmental and social survey conducted in the sub-project area during 31st October to 3rd November 2022. The screening checklist (Annex-i) revealed that environmental and social impacts of the sub-project are minor to moderate and temporary and can be mitigated and managed with prevailing good civil construction measures.

Impact Assessment:

Overall, the subproject will be beneficial. However, during construction phase, there will be some negative environmental and social impacts including construction waste generation during dismantling of road, noise pollution, obstruction in vehicular and pedestrian movement, and temporary disturbance in the accessibility of residents due to road closure. There will be

no impact on PCRs as project interventions are outside of the PCR boundaries. There are 05 schools along the entire stretch of road, where educational activities may be affected due to project interventions. Ramps of three schools will be partially dismantled during widening of Canal road and one electric pole needs to be relocated. It will be advised to implement traffic management plan during construction and ensure safety of children by applying SOPs related to construction safety while executing activities near schools. Further it will be required to monitor noise levels of machinery and equipment to keep them within safe limits. There are community safety and occupational safety prospects envisaged. Land acquisition is not required in the sub-project.

Mitigation Measures:

These impacts require appropriate mitigation and management measures to curtail them. The sub-project specific measures suggested are;

- a) ESFPs will conduct regular visit to the construction sites and fortnightly by DPO-ESM to monitor the compliance of E & S aspects
- (b) Dismantling material will be disposed of simultaneously to designated site approved by the construction supervision engineer
- (c) It will be ensured to execute the work in portions to minimize the temporary disturbance in accessibility of the people
- (d) Public safety will be ensured
- (e) Workforce will be provided with the PPEs
- (f) Corona SOPs will be followed
- (g) Contractor will use efficient machinery and equipment to reduce noise and air pollution impacts
- (h) Contractor will ensure public convenience during the course of sub-project.

Grievance Redress Mechanism (GRM):

GRM for subproject implementation will cater to all sub-project beneficiaries. The GRM mechanism is based on two-tier grievance redress committees at MC Okara, and PMDFC/ LG & CDD level. At construction site contact numbers of GRC members will be displayed.

Stakeholder Consultations:

Stakeholder consultations were carried out during preparation of ESMP. Interviews were undertaken with primary and secondary stakeholders to discuss present working condition of road and improvements recommended. Meetings were held with MC Okara Officials and key environmental and social issues were discussed. Consultations revealed that overwhelming majority of the respondents were not satisfied with the current condition of road as presently the road taken for improvement in the sub-project is narrow and shows traffic problems, surface drainage and aesthetics. All the respondents were in favor of widening and improvement of the road.

Section-1 Introduction

1.1. Punjab Cities Program (PCP)

Punjab Cities Program (PCP) Program-for-Results (PforR) will support participating MC Okara to improve their urban management and service delivery performance. The operation will provide capacity-building and institutional support to 16 secondary cities in Punjab, with an estimated total population of 4.1 million, half of whom are female.

Program Development Objectives (PDO) *is to strengthen the performance of participating urban local governments in urban management and service delivery.*

By achieving the Program Development Objective (PDO), the execution of the sub-project is expected to contribute to the overarching goals of ending extreme poverty and promoting shared prosperity by delivering improved urban infrastructure on an inclusive basis and in ways that enhance economic growth and development in the participating cities. Achievement of the PDO will also make a significant contribution to attaining Sustainable Development Goal-11 (sustainable cities and communities).

1.2. Environment & Social Management Framework (ESMF)

Environmental and Social Management Framework (ESMF) has been prepared for Punjab Cities Program (PCP). ESMF will facilitate and technically assist the MC Okara in better understanding and compliance of social and environmental management processes and procedures as per the World Bank Core Principles under PforR financing modality, local policies and legal framework. Under ESMF procedures, each sub-project will be screened for the severity and extent of environmental and social impacts. All the sub-projects will be screened through an environmental and social screening checklist and those having negligible environmental and or social impacts will require no further assessment. sub-projects having some negative but localized environmental and or social impacts will require a generic Environmental and Social Management Plan (ESMP) or SMP, while those having environmental impacts of significant nature or they come under Schedule I or II of PEPA Review of IEE/EIA Regulation 2000 will require to conduct the detailed studies (IEE/EIA) and further submission of reports to PEPA for review and to obtain NOC/ environmental approval.

1.3. Environment & Social Assessment Categories

1.3.1. Environmental Categories:

Depending on size, cost, location and the nature, scheme will have varying impacts on city environment. The rigorousness of environmental assessment requires identifying and mitigating the impacts, largely dependent upon the complexities of scheme. To facilitate effective screening, ESMF categorized schemes into three categories viz. E-1, E-2 and E-3.

| | |
|-----|---|
| E-1 | schemes are those wherein major environmental impacts are foreseen; |
| E-2 | schemes are expected to have only moderate environmental impacts; and |
| E-3 | schemes are the schemes with negligible environmental impacts and hence, these can be termed as “environmentally benign”. |

1.3.2. Social Categories:

Based on the number of households that may be affected by the scheme, i.e., Affected Households (AHs) and magnitude of impacts, schemes are categorized as S-1, S-2 and S-3.

| | |
|-----|--|
| S-1 | schemes are those that will impact more than 40 households, and are expected to have significant negative social consequences; |
| S-2 | schemes are those which will impact less than 40 households and are expected to have significant social consequences affecting local inhabitants |
| S-3 | schemes are not expected to have any significant adverse social impacts. |

1.3.3. Environment & Social Assessment Category of the Sub-project

Sub-project has been screened to assess the environment and social impacts anticipated as per scope of work. As per findings of the site visit conducted during 31-10-2022 to 01.11.2022, discussion with officials and stakeholder consultations, sub-project area does not fall in any of the wildlife habitat or reserve area/ environmental sensitive areas; therefore, it will not cause any harmful environmental impact directly or indirectly during or after execution of civil works. sub-project will have no irreversible environmental and social impacts. There are some moderate environmental impacts (minor excavations and civil works) as per scope of work which will be minimized by providing mitigation measures mentioned in Table 7-1. sub-project is categorized as E-2 and ESMP is prepared under this category.

Involuntary land acquisition is not required, and therefore there will be no physical displacement or impacts on livelihoods nor restrictions on access of the local community. Anyhow, sub-project may have temporary social impacts related to community health and safety and accessibility. Therefore,

sub-project is categorized as S-2, as there is no negative impact in terms of livelihood, business loss and any other economic loss is anticipated. Ramps of three schools i.e. Allied School, The Knowledge School and Dar-e-Arqam School will be partially affected due to widening of road and one electric pole will have to be relocated.

1.4. Environment & Social Management Plan (ESMP)

The Environmental and Social Management Plan (ESMP) is prepared for the following sub-project in compliance with the guidelines provided in the Environmental and Social Management Framework (ESMF) for the PCP-project

“Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk (Canal Road)”

1.5. Objectives of ESMP

The primary objectives of the ESMP are as follows:

- To facilitate the implementation of the identified mitigation measures.
- To define responsibilities of the project proponents, Contractor, and other members of the project team.
- To define a monitoring mechanism and identify monitoring parameters in order to ensure complete implementation of all mitigation measures and ensure effectiveness of the mitigation measures.

1.6. Sub-Project Team

Following team members (Table-1-1) participated during the preparation of ESMP.

Table 1-1: Composition of Sub-project Team

| Sr. No. | Name | Designation | Department |
|---------|---------------------------|--------------------------|-------------|
| 1 | Mr. Asif Gilani | DPO-ESS | PMDFC |
| 2 | Mr. Ali Raza | Sub-Engineer | MC Okara |
| 3 | Dr. Muhammad Ashraf Bodla | Environmental Specialist | MM-Pakistan |
| 4 | Mr. Moazzam Ali | Environmentalist | MM-Pakistan |
| 5 | Mr. Saqib Sadiq | Sociologist | MM-Pakistan |

Section-2 Sub-Project Description

2.1. Area Description

The alignment of Canal Road exists in between Tank Chowk and Akbar Chowk in Okara city. The present physical conditions of Canal road is presented in the Figure 2-1.



Figure 2-1: Canal Road Okara

2.2. Problem Statement

This sub-project has been formulated on the basis of demand from communities residing along with the alignment of the sub-Project. The road proposed for widening and improvement have been damaged because of poor maintenance. Due to various activities for installation of utilities in these areas the condition of the areas highlighted by district council, Okara is narrow and needed immediate attention to improve the vehicles/ pedestrian traffic to ease out the public at large in the area. The road is damaged at various places and needs widening and improvement. Therefore, MC Okara also decided to construct road under this sub-project.

2.3. Description of Work Activities

The subproject is Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk (Canal Road)

The sub-project has the following interventions:

- Scarifying and dismantling of road
- Preparation of sub-grade
- Laying of sub-base
- Laying of base course
- Asphalt wearing course
- Installation of street lights.

2.4. Environmental Management Cost

Total cost of the scheme: 100.93 Million/- PKR

ESMP implementation cost: 1.33/- Million. PKR (Break-up of this cost described in Table 7-2).

2.5. Duration of the Sub-project

Implementation Schedule/Duration: 06 month maximum.

No. of workers/labor involved: 30-35 approx.

2.6. Sub-project Alternatives

Sub-project involves Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road.

2.6.1. Do Nothing Scenario

The no-build alternative involves letting the current situation continue without addressing the on-going deterioration of the air quality, level of service and other environmental and social impacts occurring in the subproject area. If the project is not carried out the expected consequences are:

- Deterioration in air quality, and increase in noise levels due to traffic jam.

- An increase in the severity of socio-economic impacts in the surrounding area.
- The project shall eventually have to be undertaken as the demand from the communities shall soon reach its peak levels.
- The cost of the proposed design shall increase in future due to inflation, social issues, environmental impacts etc.

2.6.2. Site Alternative

Sub-project involves Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk (Canal Road), so there is no site alternative envisaged because no other site available to serve this purpose.

Section-3 Legal & Policy Framework

3.1. Introduction

The Government of Pakistan and Government of Punjab (GOP) have enacted a range of laws, regulations, policies and procedures for management and mitigation of social and environmental impacts for infrastructure development projects. This chapter discusses the relevant and applicable laws and WB Core Principles for PforR financing modality applicable for PCP to deal with the environmental and social issues.

3.2. National and Provincial Laws, Regulations, Procedures and Guidelines dealing with the Environmental & Social Aspects

Table 3-1: National and Provincial Laws, Regulations, Procedures and Guidelines dealing with the Environmental & Social Aspects

| Sr. No. | Applicable laws, regulations, Guidelines | Relevancy/Applicability |
|---------|--|--|
| I. | Punjab Environmental Protection Act 2012 | PEPA does not require IEE or EIA of widening projects |
| II. | PEPA Review of IEE/EIA Regulations, 2000 | IEE/EIA regulations do not require IEE or EIA of widening projects. |
| III. | Notification No.SO (Tech)/EPD/1-26/2004 issued by Government of the Punjab, Environment Protection Department "Delegation of Powers for Environmental Approvals Rules 2017 | ESMP do not require review and subsequent NOC from the relevant authority |
| IV. | Punjab Local Government Act, 2019 | Follows the environmental and social assessment procedures stated in PEPA 2012 |
| V. | Punjab Environmental Quality Standards for Motor Vehicle Exhaust and Noise | Applied to vehicles used by the contractor |
| VI. | Punjab Environmental Quality Standards for Ambient Air (2016) | Compliance required during construction activities |
| VII. | Punjab Environmental Quality Standards for Noise (2016) | Compliance required during construction activities |
| VIII. | Punjab Environmental Quality Standards for Drinking Water | Compliance required during construction activities |

| | | |
|-----|---|--|
| IX. | Punjab Restriction of Employment of Children Act 2016 | Compliance required during construction activities |
| X. | Protection Against Harassment of Women at the Workplace Act, 2010 | Compliance required during construction activities |

3.3. World Bank Policy Core Principles and Applicability on Sub-project

| Core Principles | Applicability |
|---|---|
| <p>Core Principle 1 Environmental and social management procedures and processes are designed to (a) Avoid, minimize, or mitigate against adverse impacts; (b) Promote environmental and social sustainability in program design; and (c) Promote informed decision making relating to a program’s environmental and social effects.</p> | ESMP prepared under the light of this Principle in order to mitigate negative impacts envisaged in this sub-project. ESMP implementation will help in achieving environmental and social sustainability |
| <p>Core Principle 2 Environmental and social management procedures and processes are designed to avoid, minimize, and mitigate against adverse effects on natural habitats and physical cultural resources resulting from the program</p> | All the mitigation measures have been incorporated in the Table 7-1. |
| <p>Core Principle 3 Program procedures ensure adequate measures to protect public and worker safety against the potential risks associated with (a) construction and/or operations of facilities or other operational practices developed or promoted under the Program and (b) exposure to toxic chemicals, hazardous wastes, and otherwise dangerous materials</p> | All the mitigation measures have been incorporated in the Table 7-1 to address risks associated with workers and community health and safety. Contractor will ensure compliance with these attributes. |
| <p>Core Principle 4 Land acquisition and loss of access to natural resources are managed in a way that avoids or minimizes displacement, and affected people are assisted in improving, or at least restoring, their livelihoods and living standards</p> | This core principle doesn’t trigger in this sub-project as no land acquisition is required during the replacement of existing sewer-line. |
| <p>Core Principle 5 Due consideration is given to cultural appropriateness of, and equitable access to, program benefits, giving special attention to rights and interests of indigenous peoples and to the needs or concerns of vulnerable groups.</p> | No indigenous/ Vulnerable groups exist in the sub-project sites. |

| Core Principles | Applicability |
|--|---|
| <p>Core Principle 6 Avoid exacerbating social conflict, especially in fragile states, post-conflict areas, or areas subject to territorial disputes.</p> | <p>This principle is not relevant for this Sub-project.</p> |

3.4. World Bank Environmental, Health and Social Guidelines

The principal World Bank publications that contain environmental and social guidelines are listed below.

- Environment, Health, and Safety (EHS) Guidelines prepared by International Finance Corporation and World Bank in 2007
- Pollution Prevention and Abatement Handbook 1998: Towards Cleaner Production
- Environmental Assessment Sourcebook, Volume I: Policies, Procedures, and Cross-Sectoral Issues.
- Social Analysis Sourcebook
- WB Group Gender Strategy

Details of related EHSG can be found in Annexure ii.

3.5. PMDFC Environment Health and Safety SOPs for labor/workers (including Women)

EHS SOPs for labor/ workers (including women workers) will be applicable during the labor work and made part of the contractual agreement of the contractor

3.6. COVID-19 SOPs

During the construction and implementation of the Sub-project, the Standard Operating Procedures (SOPs) will be strictly followed during construction activities, stakeholder consultations or applicable in any other relevant aspect. The SOPs attached as Annexure iii.

Section-4 Environment & Social Baseline

4.1. City profile

Okara district is composed of three sub-divisions Okara, Renala Khurd and Depalpur. Okara, the District Headquarters is about 127 Kilometers to the southwest of Lahore, on the National Highway and on the main Lahore-Karachi Railway track. Okara district spreads between latitudes of 30° -18' to 31°-08' North, and the longitudes of 73°-14' to 74°-09' East. The city coordinates are 30° -49' North latitude, and 73° -27' East longitude.

4.2. Climate

Climate of the district varies from hot to very hot in summer and cold in winter especially in December and January. During the months of July and August, the weather is humid whereas spring is pleasant. Summer season starts in April and continues till September. June is the hottest month with mean maximum and minimum temperature of about 45 and 27 degree Celsius respectively. Winter season starts from November and lasts till February. Mean maximum and minimum temperature recorded during the month of January is about 20 and 6 degree Celsius respectively. Light rainfalls during winter season especially in the months of January and February is succeeded by a spell of pleasant spring weather. Monsoon starts in the first week of July. The average annual rainfall is about 625 millimeters.

4.3. Demographic Status

The population census report of year 2017 has not been published by Government of Pakistan. However the provisional data available for this census shows the population of 357,935 persons for the city within municipal limits. A land scan process was done to estimate the population of entire inhabited areas of city in close approximation which was found to be 443,396 persons in the year 2017 with an annual growth rate of 2.32 % and it is expected to rise to 557,695 persons in the year 2027. A large and thick inhabitation has developed outside the municipal limits of the city and the municipal limits need to be extended.

4.4. Water Resources

The city is divided into two zones by Lahore-Karachi railway track and is called North & South Zones. Originally 19 tube wells for north zone were installed on the bank of Lower Bari Doab Canal (LBDC) between the LBDC and 4-L distributary whereas the tube wells for south zone were installed on the bank of 4-L distributary. Both the irrigation channels diverge away from each other at the south-western end of the city.

The discharge of 4-L distributary is 260 cusecs only and after some time the water quality of the tube wells installed on the banks of this channel, deteriorated because of excessive withdrawals as compared to the recharge and became unfit for human consumption. In this way acute water shortage was experienced in the south zone.

4.4.1. Water Quality

No specific primary and secondary data available in context of Okara City. MC Okara has not sampled/analyzed any drinking water since PHED handed over whole water supply infrastructure to MC.

4.5. Solid Waste Management

Some portion of the city is either un-served or partially served because of shortage of sanitary staff and machinery & equipment whereas the existing machinery and equipment is inefficient having costly operation and maintenance and need repairs. The solid waste is being dumped at two different points along the LBDC because no proper landfill site is available which is creating hazards like obnoxious smell, sub soil water pollution and breeding of vectors causing water borne and vector diseases. Apart from that this is also creating insanitary conditions resulting in frustration in the citizens. MC has a piece of land measuring 13 acres for the development of Landfill site but it could not be developed due to financial constraints.

4.6. Sewerage Facility

The city is equipped with sewerage system in 71% area. The city has been divided in to three areas called as Zones with respect to the drainage. In zone-1 the outfall sewer line of 48" diameter was choked and has been subsequently got replaced by a 54" diameter sewer. The Disposal works of this system is located in Chack No-2/4L and the waste water from this disposal works is being pumped into a seepage/storm water drain through a force main up to LBDC and sullage carrier up to drain. The section of the sullage carrier is not adequate to carry the entire quantity of water and hence it overflows in private lands. To eliminate the overflow, the farmers divert the water to LBDC thus polluting this channel.

The disposal works of zone-2 is located in Chack No-1/4L. No problem in this zone is experienced as the sewers are relatively of much lesser age than the rest of the systems and not posing any problem of flooding of streets and roads. However the ultimate disposal of waste water is broad irrigation in the private lands across LBDC. When water is not required by the farmers, they divert this water into LBDC thus polluting the canal. The sullage carrier needs to be extended up to the seepage drain to eliminate pollution of the canal.

Zone-3 is relatively much bigger systems and covers most of the area lying in the south-east of railway track. The waste water is being discharged by gravity into a seepage/storm water drain flowing in the south eastern side of Okara city at a distance 6 Km through the outfall sewer of 66 inches diameter converting into a sullage carrier from its mid length to the end.

4.7. Seismologic Zone




Figure 4-1: Project Area Seismic Zone Location¹

Table 4-1: Seismic Zones of Tehsils of Pakistan

| Tehsil | Seismic Zone | Tehsil | Seismic Zone | Tehsil | Seismic Zone |
|---------------|--------------|--------------|--------------|-------------------|--------------|
| Punjab | | | | | |
| Bhakkar | 2A | Kasur | 2A | Kot Addu | 2A |
| Kalur Kot | 2B | Chunian | 2A | Bahawalpur | 2A |
| Mankera | 2A | Pattoki | 2A | Hasilpur | 2A |
| Darya Khan | 2A | Okara | 2A | Yazman | 2A |
| Khushab | 2B | Depalpur | 2A | Ahmadpur East | 2A |
| Nurpur | 2A | Renala Khurd | 2A | Khairpur Tamawali | 2A |

According to the Seismic data of Pakistan; Okara lies in 2A zone with minimum risks to any earthquakes².

¹ Source: Geological Survey of Pakistan

² Source: Geological Survey of Pakistan

4.8. Natural Disasters Data

Geographically Okara lies at a distance of 32 Km and 111 Km from River Ravi and Satluj respectively and is therefore historically not affected by floods.

4.8.1. Potential hazards of the District Okara

Table 4-2: Risk Analysis of Potential Hazards of District Okara

| Hazards Risk | Likelihood Score (1-5) | Impact Score (1-5) | |
|--|------------------------|--------------------|----|
| Floods | 5 | 5 | 25 |
| Urban Flooding | 1 | 1 | 1 |
| Flash Floods | 1 | 1 | 1 |
| Hill Torrent | 1 | 1 | |
| Glacial Lake Outburst Flood (GLOF) | 1 | 1 | 1 |
| Landslide | 1 | 1 | 1 |
| Tornado | 1 | 1 | 1 |
| Earthquake | 5 | 5 | 25 |
| Drought | 1 | 1 | 1 |
| Epidemic | 2 | 4 | 8 |
| Fire Incidents | 1 | 1 | 1 |
| Other Major Accidents (Building Collapse, road traffic accidents, train accident, Stampede, plane crash) | 1 | 1 | 1 |
| Environmental Hazards (industrial accidents, severe pollution etc.) | 1 | 1 | 1 |
| Risk = Impact x Likelihood Low: 1-7 Medium: 8-14 High: 15-25 | | | |

Source: District Disaster Management Plan 2020 (District Okara)

4.9. Environmentally and Socially Sensitive Receptors

Environmental sensitive areas are more prone towards human disturbance. For this sub-project, no wetland, estuarine, river, protected areas lie within scope of work of scheme area and no significant environmental impacts have been envisaged. 05 schools are located within 100m of Canal road. There will only be impediment in the movement of local community during school timings. The ramps of three schools will be partially affected during construction works and one electric pole will have to be relocated due to widening of road.

4.10. Flora & Fauna

18 trees of Jaman, Datepalm, Neem, Toot and Sufaida are growing along the footpath where tuff paver are proposed, however, these trees are outside of the paver boundary and will not be cut/uprooted. Similarly, 35 trees of same species are growing on the other side of the road but

outside of RoW. No tree cutting is involved during the execution of the project. No wild animal/ endangered species is found in the area.

4.11. Right of Way and Corridor of Impact

The existing Right of Way (RoW) of Canal Road is 30-33 ft. The existing carriage way is 14.5 to 15.5ft and proposed carriage way is 24ft which is the Corridor of Impact (COI) where the widening/ improvement works of roads will be confined.

4.12. Socio - Economic Baseline

The socio-economic characteristics are a comprehensive review of the current conditions of the project area. It is based on a literature review, site visits, and consultations with institutional and community stakeholders. The baseline provides a glance of the conditions of the community of the project area. It includes provision of social infrastructure facilities available in the area. Moreover, the existing conditions of utilities and the presence of cultural and religious sites are also discussed. Most of residents along the road fall under the high income category and are engaged with politics, education and business.

4.12.1. Demographic Characteristics

The population of Okara is 357,935 as recorded in 2017. The project lies in the urban area. Birth, Death, fertility, mortality, fecundity, Crude and net birth rate and migration are the most important demographic factors.

4.12.2. Educational institutions

05 schools are present in the vicinity of project location, where temporary impediment in the movement of school children is anticipated. Construction works in front of these schools will be done after school hours or civil activities will be executed in sections to avoid any blockage in the movement of students or any interference in educational activities during working hours.

4.12.3. Housing

Majority of the houses are made of material such as bricks and cement-concrete. Basic utilities, which are included gas, water supply and sewerage system, are also available at the proposed project site.

4.12.4. Archaeological, Historical, and Cultural Resources

There is no identified archaeological, historical, and cultural resources along the sub-project route that will be impacted by the road construction except 05 schools that are located outside of

subproject Corridor of Impact (COI). There will be no impact on the structures. However, temporary impediment in the movement of people during the school timings might happen. This impact would be mitigated by keeping the passageway clear during study timings.

4.12.5. Identification of Project Affected Persons (PAP)

The residential and commercial structures adjacent to the road will not be affected as no land acquisition is required. The ramps of Allied School, The Knowledge School and Dar-e- Arqam School will be partially affected and one electric pole owned by LESCO will have to be relocated (Figure 4.2). The details are as under:

| Sr. No. | Name of PAP | Type of Asset | Size in Sq. Feet | Name of Institution | Contact No. |
|--|---------------------------|---------------|------------------|----------------------|-------------|
| 1. | Irshad Ali (Principal) | Tough Paver | 91 | Allied School | 04427067256 |
| 2. | Muhammad Idrees (Teacher) | Tough Paver | 200 | The Knowledge School | 03136962254 |
| 3. | Prinipal | Tough Paver | 400 | Dar-e- Arqam School | 0404400672 |
| Total Cost | | | | 144,720 Pkr | |
| Cost for Relocation of 1 Electric pole | | | | 10,00,000 Pkr | |



Figure 4-2: Photographs of assets to be partially removed and pole to be relocated

Section-5 Stakeholder Consultation

Timely and broad-based stakeholder involvement is an essential element for an effective environmental and social assessment. Stakeholder engagement and consultation during environmental & social assessment contributes in the improvement of the project design, environmental compliance and social acceptability.

5.1. General

This section describes the outcomes of the public consultation sessions held within MC Okara about the proposed sub-project area. The objectives of this process were to:

- Share information with stakeholders on the widening of the proposed project and expected impacts on the physical, biological and socio-economic environment of the project;
- Understand stakeholder's concerns regarding various aspects of the project and the likely impacts of construction related activities and operation of the project;
- Understand the perceptions, assessment of social impacts and concerns of the affected people/ MC Okara of the proposed project;
- Provide an opportunity to the public regarding their valuable suggestions in a positive manner; and
- Reduce the chances of conflict through the early identification of controversial issues, and consult them to find acceptable solutions.

In preparation for the ESMP, two major groups of stakeholders were identified:

- (i) Local communities who are the direct beneficiaries of the project interventions and therefore identified as the primary stakeholders
- (ii) Institutions who have an important role in enabling the realization of the project interventions and therefore identified as the secondary stakeholders.

5.2. Public Consultation

For public information/ consultation, visits were made in the proposed sub-project areas to record the concerns of communities regarding sub-project activities. Methodology used for selection of interviewee was Random Sampling/ Focus Group Discussion. Table 5.1 depicts the concerns of the Institutional and community representatives and the replies from the consultant team. The

pictorial record of Institutional and community consultations are given in Figure 5-1 & 5-2 respectively.

Table 5.1 Stakeholders Consultation

| Sr. No. | Institutional Concerns | Consultant Responses |
|---------|--|---|
| 1 | Mr. Zahid Iqbal, Additional Deputy Commissioner (General) asked about any broacher on the sub-project prepared? If so send a copy | Project brief has been prepared by Punjab Municipal Development Finance Company (PMDFC) and may be provided to the stakeholders in due course |
| 2 | Mr. Zaheer Liaqat Baig, Administrator MC Okara asked about the removal of electric poles and transformers from the roads. He also enquired about the cutting of trees. An alternate plantation of tree cutting should be made prior to subproject execution. He commented that the green belts of roads should not be decreased. He was fully agreed with the construction of roundabout and U-Turn at Multan Road. He said, it is a dire need to take urgent initiatives accordance with the available space. | It was informed that the electric poles will be removed by Lahore Electric Supply Company (LESCO) for which Demand Notice has been received. About tree cutting, he was informed that 1o trees will be planted for every cut/uprooted tree. |
| 3 | Mr. Muhammad Nasim Chief Officer has positive response to the subproject. He commented that the sub-project may be executed at the earliest as per need of the citizens. | Well appreciated his views. |
| 4 | Ahsan Bilal, Circle Head Draftsman was briefed about the shifting of electricity poles. He enquired about the shifting cost of the electric poles as per their Demand Notice. | He was informant that demand notice has been received and payment to LESCO being arranged. |
| 5 | Mr. Sarfraz Ali Sub Divisional Officer Irrigation has no issue about the roads but has concern about disposal of untreated sewage in to Lower Bari Doab Canal and 4.L Distributary. | He was informed that the sewage will not be disposed of in to the water bodies. |
| 6 | Mr. Javaid Suleman Assistant Forest asked that whether any forest tree will be cut/uprooted. In doing so replenishment cost has to be paid to the Forest Department prior to execution of the subproject. He provided copy of SOP for cutting of forest trees. | He was informed that No forest tree will be cut/uprooted |
| 7 | Mr. Muhammad Tufail Principal Savvy School, and Mr. Arshad Ali Principal Allied School supported the subproject. | Appreciated their support |

| Sr. No. | Community Concerns | Consultant Responses |
|---------|---|---|
| 1 | The residents showed their concern about the existing bad and narrow condition of road and asked for urgent widening. | The project team said that this project would be completed on an urgent basis. |
| 2 | There is dire need to establish a supervision committee to monitor the construction works of road to ensure quality at site | The team briefed that all construction works will be monitored by MC itself as well as PMDFC representative and team of supervision consultants. Quality will be ensured at every stage. |
| 3 | The provision of speed breakers should be added particularly near schools while designing road to avoid over speeding and ensure safety of school children | The team answered that this provision of speed breakers close to schools will be considered while designing road. |
| 4 | Fence and foot path must be added in the scope of work towards canal side | The team answered that this suggestion will be communicated to design team. |
| 5 | The local people suggested that there should be lease involvement of political leaders in this project and should only focus need of local residents and common user of road. | Acknowledged by the consultants and replied they recognize the dire need of the local people and will fulfill the needs accordingly. |
| 6 | School owners, showed their concern about impediment in movement of students coming to school. | Sociologist of MMP responded, this impact is already in our mind and shall not only be addressed properly in environment management plan but also strictly implemented during construction to avoid impediment in the movement of pedestrians. |
| 7 | There is a heavy load of traffic on this road, how it will be managed during construction? | Acknowledged, The contractor will prepare Traffic Management Plan before the start of construction activities and shall implement during execution. Consultant and PMDFC staff will monitor its implementation throughout the project duration. |
| 8 | Speed breakers should be designed according to prescribed standards to avoid damage to vehicles and unnecessary speed breakers should be avoided. | Acknowledged, all speed breakers will be designed as per specifications and need based. |
| 9. | The road along the right bank of canal should also be improved along with this project | This project is for the improvement of left bank of canal road, but this suggestion will be communicated to concerned authorities as a prospect for future development needs. |
| 10. | The trees on this road should not be cut while widening of road | The team ensured to the community that no tree will be cut or uprooted. |



Figure 5-1: Pictorial view of Institutional Consultations



Figure 5-2: Pictorial view of Public Consultation

Section-6 Grievance Redress Mechanism

In order to receive and facilitate the resolution of affected people concerns, compliments, and grievance about the project's environmental and social performance an Environmental Grievance Redress Mechanism (GRM) has been established. The GRM will address affected people's concerns and complaints proactively and promptly, using an understandable and transparent process that is gender responsive, culturally appropriate and readily accessible to all segments of the affected people at no costs and without retribution.

The GRM will be accessible to diverse members of the communities, including women, senior citizens, and people with disabilities, laborers/workers, and other vulnerable groups. Culturally appropriate communication mechanisms will be used at all sub-project sites both to spread awareness regarding the GRM process as well as complaints management. *ESMF GRM will be integrated with the PCP's overall program GRM hotline to be developed by the Consultants under the scope of PCP.*

GRM has been designed which will utilize the web platform and also android app.

6.1. Grievance Redress Mechanism at Sub-Project Site

Grievance Redress Mechanism (GRM) is to provide a robust system of procedures and processes that provides for transparent and rapid resolution of concerns and complaints identified at the local level. For integration of GRM into existing Complaint Tracking System (CTS), Grievance Redress Committee (GRC) - MC will be notified under umbrella of Punjab Cities Program (PCP) comprising of the following members and TORs.

| | |
|--|-------------|
| Chief Officer MC | Chairperson |
| Municipal Officer (Infrastructure Development) | Convener |
| Municipal Officer (Planning) | Member |
| Municipal Officer (Regulation) | Member |

TORs of GRC-MC are as follows:

- ESFPs designated by the MCs for environmental and social management will be responsible to manage the GRM effectively. The ESFPs with the support of DPO-ESM will play an instrumental role in steering the GRC functions both at city and regional level.

- CO MC will be responsible to share monthly recorded grievances data with regional GRC.

6.2. GRM at Regional Level

Grievance Redress Committee at Regional level will also be notified under umbrella of Punjab Cities Program (PCP) comprising of the following members and TORs:

| | |
|--|------------------------|
| Deputy Program Officer (Environmental & Social Management) | Chairperson & Convener |
| Deputy Program Officer (Infrastructure Development) | Member |
| Deputy Program Officer (Institutional Strengthening) | Member |

TORs of GRC-Regional are as follows:

- Committee will be responsible to manage the GRM effectively as per data provided by MC GRC.
- DPO-ESM will support ESFPs in steering the GRC functions both at city and regional level.
- DPO ESM will maintain monthly complaint records from ESFPs.

A Grievance Redress Committee (GRC- PMDFC/LG & CDD) will be responsible to oversee the overall functions of the GRM at a strategic level including monthly reviews. It will be headed by the Secretary LG &CDD.

6.3. Types of Grievances

The following are some of the environmental and social issues that could be subject for grievance from the affected people:

| Environmental Issues | Social Issues | EHS Issues |
|--|--|--|
| <ul style="list-style-type: none"> • Noise Pollution • Air Pollution • Fugitive Dust • Water Pollution • Solid Waste Management • House Keeping • Cutting of Trees • Borrow Areas Management | <ul style="list-style-type: none"> • Accidental Insurance for labor • Non-Provision of PPEs to labor as per nature of their jobs • Loss of any public infrastructure • Protection of sensitive receptors | <ul style="list-style-type: none"> • First Aid • Fire Safety • Workplace Safety • Tools Box Talks • Provision of PPEs • Work at Height Safety • Excavation Safety • Heavy Machinery Issues |

| | | |
|---|---|--|
| <ul style="list-style-type: none"> • Protection of Wildlife • Campsite Management | <ul style="list-style-type: none"> • Compensation for any economic losses • Traffic Management • Labor grievance redressal • Gender discrimination • Security Arrangements • Impacts on livelihood • Irregular Traffic Movement • Obstruction in access • Intensive schedule of construction activities • Child Labor • Unsafe conditions for the community (Community Health and Safety, CHS) | |
|---|---|--|

Section-7 Environmental and Social Management and Monitoring Plan

7.1. Objective

The purpose of Environmental and Social Management and Monitoring Plan (ESMMP) for widening and improvement of road is to ensure that all necessary identified measures have been adopted in order to protect the environment and social situations and to comply with country environmental legislation and applicable World Bank Core Principles for PforR financing modality. After the preparation of ESMF, PMDFC ESM Wing outlined site-specific ESMMP for the Contractors and executing agency. Environmental and social checklist was prepared by PMDFC ESM Wing with the help of the field teams and was used to assess the potential impacts of sub-project on the basis of its scale/ size, nature and significant negative impacts.

7.2. Institutional Arrangements

The specific responsibilities of the institutions involved in the ESMP implementation are described below:

7.2.1. MC Okara

MC Okara will be responsible for implementation, monitoring and reporting of ESMP with the technical assistance of ESM Wing PMDFC throughout the project period.

Notification of ESFPs in MC Okara under PCP has been done.

MOI has been nominated for Environment Focal Person, he is responsible for implementation & monitoring of environmental aspects. MOP has been nominated for Social Focal Person he is responsible for implementation & Monitoring of social Aspects

7.2.2. PMDFC ESM Wing

ESM Wing will provide support to ESFPs (MOI for Environment focal person and MOP for Social focal person) for managing environment and social aspects of the subproject and implementation of the present ESMP. ESM Wing would also support communities' participation, consultations and other social activities from the sub-project identification to completion stage. PMDFC ESM wing will also monitor the subproject activities to ensure the project remains complaint as per World Bank and national/provincial policies and regulations. Therefore, regular reports will be submitted to the Word Bank accordingly.

7.2.3. The Contractor

The Contractor will be responsible for on-field implementation of the ESMP and environmental protection liabilities under the Punjab Environmental Protection Act (Amendment 2012) and World Bank's Environmental and Social Core Principles for PforR financing. He will also be responsible for compliance of ESMP provisions keeping in view his contract with the MC Okara. The Contractor will train his crews in all aspects for implementation of the ESMP.

Contractors have to comply with the following responsibilities:

- Observation of timings and make a schedule that the surrounding communities should not affect from noise pollution, air emissions and disturbances in their routine work
- Sage of machinery/equipment's producing negligible/low noise.
- Ensure health, safety and protective measures including safety equipment, safe drinking water, first aid boxes etc. to the workforce as per nature of their jobs.
- Water sprinkling to avoid air pollution.
- Indicate alternate routes and provide indicators on suitable places during work timings.
- Local labor should be preferred to work.
- Child labor is strictly prohibited as per labor law. All labor should be more than 14 year of age individually.
- Minimize livelihood disturbance of hawkers and shopkeepers
- Proper disposal of wastes and garbage.
- Health, safety and protective measures for the labor.
- Notice board of emergency numbers should be placed on proper place
- Contractors shall also provide safety equipment's i.e., PPEs, safe drinking water, first aid boxes etc. to the workforce as per nature of their jobs. By ensuring all these mitigation measures; not only their company profile shall boost up but also enable them to qualify and win the future sub-projects.

7.2.4. Supervisory Consultant

Compliance of ESMP's all attributes will be ensured by Resident Supervision Consultant.

7.3. Monitoring Mechanism

The ESFPs will carry out the monitoring at the field level on a continuous basis. The DPO ESSs will perform periodic monitoring during their site visits. Two complementary methodology approaches are being applied to monitor the proposed actions under the ESMP:

- Compliance monitoring; which checks whether the actions proposed by the ESMP have been carried out by visual observation, photographic documentation and the use of checklists prepared for the ESMP;
- Effects monitoring; which records the consequences of program activities on the biophysical and social environment; as applicable, these effects are repeatedly measured by applying selected indicators.

The plan also defines the monitoring mechanism and identifies a set of verifiable monitoring parameters to ensure that all proposed mitigation measures laid down in the ESMP are completely and effectively implemented.

Monitoring will be carried out to ensure that the mitigation plans are regularly and effectively implemented. It will be performed at two levels. At the PMDFC, the environmental team will do ESMP compliance monitoring to ensure that the mitigation plans are being effectively implemented. At Contractor's level, the Environmental & Social Monitoring Checklist (Annexure i) will be filled on weekly basis by their Environmental Manager.

7.4. Reports

The Contractor will submit weekly compliance monitoring checklist and PMDFC ESM Wing will submit quarterly and annual monitoring reports as well as a final report of the sub-project based on safeguard implementation status. The monitoring reports will also include process and outcome of consultations with the Project Affected Persons. The distribution of periodic reports is given below:

| Distribution of Periodic Reports Report | Prepared by | Reviewed by | Distribution |
|---|----------------|----------------|-------------------------------------|
| Weekly | Contractor | PMDFC DPO ESSs | PD, The Engineer |
| Quarterly | PMDFC DPO ESSs | PMDFC SPO ESSs | PD, The Engineer, The World Bank |

| | | | |
|---------------|----------------|----------------|-------------------------------------|
| Annual | PMDFC DPO ESSs | PMDFC SPO ESSs | PD, The Engineer, The World Bank |
| Final | PMDFC DPO ESSs | PMDFC SPO ESSs | PD, The Engineer, The World Bank |

7.5. Inclusion of ESMP in Bidding/ Contract Documents

The present ESMP has been included in the bidding/ contract documents and their implementation will be a contractual binding for the Contractors. In addition, the Contractor's guidelines prepared by PMDFC/ safeguards procedures will also be made part of contracts.

7.6. Environmental and Social Non-Compliance

Any environmental and social non-compliance during first half of the reporting month will be considered as a "minor deviation". In case the non-compliance attains the status of "non-mitigation" during the second half of the reporting month, it would be considered a "moderate non-compliance". In case non-compliance continues in the second month, it will fall in the category of "undone" and as such would be considered as a major non-compliance and eventually leading to serious action including the suspension of Contractor's payment or any other penalty as may be considered appropriate with the recommendation of the DPO ESSs/Engineer. No payment will be made to Contractor against non-compliance and no arrears will be paid thereof.

7.7. Environmental and Social Management and Monitoring Plan

The impacts, mitigation measures, monitoring indicators, frequency and responsibility has been discussed in Environmental and Social Management and Monitoring Plan (ESMMP).

Table 7-1: Environmental & Social Management & Monitoring Plan

Sub-project: Widening and Improvement of Roads and Streetlights in Okara City

| Proposed Sub-project activities | Potential Env./Soc. Impacts | Magnitude of Impact | Mitigation Measures | Mitigation Implementation Responsibility | Monitoring Indicators | Monitoring Frequency | Monitoring Responsibility |
|--|---|---------------------|--|--|---|---|--|
| Design Phase | | | | | | | |
| | Conflict on design | Negligible | To avoid conflicts at design phase public consultations was conducted, in this subproject no conflict was raised during public consultation | MC ESFPs | Minutes of meeting records, attendance sheets and pictures | Design E&S Consultants | ESM team of PMDFC |
| Construction Phase | | | | | | | |
| Dismantling, Excavation fine aggregate, base coarse and cleaning & grabbing) | <p>a) Land Use:</p> <ul style="list-style-type: none"> The current land use is residential cum commercial with shops, houses and commercial structures including schools on one side and canal on other side of the road. | High | <ul style="list-style-type: none"> Excavated material will be disposed within 24 hours at the designated place of MC Okara. Updated and tuned machinery will be used to control noise. Water sprinkling will be carried out | Contractor | Visual/ Photographic record, Public consultation, Environment Quality Analysis reports, GRM Complaints record | <ul style="list-style-type: none"> Daily site visit during construction phase Fortnightly/ Weekly Once during the construction phase | <ul style="list-style-type: none"> ESFPs DPO ESM Supervision Consultants E&S team |

| Proposed Sub-project activities | Potential Env./Soc. Impacts | Magnitude of Impact | Mitigation Measures | Mitigation Implementation Responsibility | Monitoring Indicators | Monitoring Frequency | Monitoring Responsibility |
|---------------------------------|---|---------------------|---|--|-----------------------|----------------------|---------------------------|
| | <p>b) Environmental Issues:</p> <ul style="list-style-type: none"> • Dust which may affect visibility, community and labor health • Noise from machineries/ equipment • Waste may be generated due these activities • Safety hazards to labor and nearby resident population. • Worse House Keeping <p>c) Social Issues:</p> <ul style="list-style-type: none"> • Excavated material may cause disturbance in mobility • Temporary blockage of | | <p>at consecutive intervals as per instructions</p> <ul style="list-style-type: none"> ○ Avoiding construction activities during nights. ○ Removal of excess matter/ debris from the site within 24 hours. ○ Provide PPEs (See Annexure v). ○ Provide appropriate signage near the construction activities to sensitize the communities and minimize accidents. ○ Public must be informed about project major activities, duration of scheme, time | | | | |

| Proposed Sub-project activities | Potential Env./Soc. Impacts | Magnitude of Impact | Mitigation Measures | Mitigation Implementation Responsibility | Monitoring Indicators | Monitoring Frequency | Monitoring Responsibility |
|---------------------------------|---|---------------------|--|--|-----------------------|----------------------|---------------------------|
| | road may restrict mobility <ul style="list-style-type: none"> • Conflict with public and public complaints • Economic losses • Livelihood's loss. • Temporary loss of structures and private property • Economic loss of permanent and mobile vendors due to obstruction of passage • Presence of Physical Cultural Resources (PCRs) of Archeological importance • Air and dust pollution • Noise pollution | | and schedule, anticipated impacts and their proposed Mitigation Measures. <ul style="list-style-type: none"> ○ The contact Nos. of focal person of Grievance Redress Committee will be displayed at different locations and residents will also be informed about it. ○ Traffic controllers will be placed at strategic locations to control traffic and ensure safety of pedestrians ○ Safety/ caution sign boards and | | | | |

| Proposed Sub-project activities | Potential Env./Soc. Impacts | Magnitude of Impact | Mitigation Measures | Mitigation Implementation Responsibility | Monitoring Indicators | Monitoring Frequency | Monitoring Responsibility |
|---------------------------------|-----------------------------|---------------------|---|--|-----------------------|----------------------|---------------------------|
| | | | <p>reflective tape will be installed at site during work.</p> <ul style="list-style-type: none"> ○ Construction work will be scheduled in such a way that business of the shopkeepers and schools located along the roads will not be affected. ○ Temporary hindrance in mobility for which contractor will be instructed to execute that work by providing the alternate route for community mobility. ○ Contractor will ensure that work should be executed in | | | | |

| Proposed Sub-project activities | Potential Env./Soc. Impacts | Magnitude of Impact | Mitigation Measures | Mitigation Implementation Responsibility | Monitoring Indicators | Monitoring Frequency | Monitoring Responsibility |
|---------------------------------|-----------------------------|---------------------|--|--|-----------------------|----------------------|---------------------------|
| | | | <p>portions to avoid the temporary disturbances in the accessibility and placement of the temporary vendors</p> <ul style="list-style-type: none"> ○ Contractor will make sure that labor must not damage the property and structures of the communities (tough paver ramps of three schools will be partially affected which will be compensated as per market rate and one electric pole will be relocated) and in case of damage | | | | |

| Proposed Sub-project activities | Potential Env./Soc. Impacts | Magnitude of Impact | Mitigation Measures | Mitigation Implementation Responsibility | Monitoring Indicators | Monitoring Frequency | Monitoring Responsibility |
|---------------------------------|-----------------------------|---------------------|---|--|-----------------------|----------------------|---------------------------|
| | | | compensation will be provided as per entitlements. <ul style="list-style-type: none"> ○ If there will be any PCR found during excavation; Contractor will follow guidelines (Annexure vi) of chance find procedure. ○ Air quality will be analyzed by the contractor from EPD certified Lab at pre, during and after execution stage of the work. ○ Noise quality will be analyzed by the contractor from EPD certified Lab at pre, during and after | | | | |

| Proposed Sub-project activities | Potential Env./Soc. Impacts | Magnitude of Impact | Mitigation Measures | Mitigation Implementation Responsibility | Monitoring Indicators | Monitoring Frequency | Monitoring Responsibility |
|---|---|----------------------|--|--|-----------------------|---|--|
| Construction material storage, handling and use | <p>Environmental Issues:</p> <ul style="list-style-type: none"> ○ Ground water may be contaminated due to the any oil spillages from machinery. ○ Health risk to workers and local inhabitants. ○ Poor Housekeeping <p>Social Issues:</p> <ul style="list-style-type: none"> ○ Land acquisition for storage of construction material ○ Accidents/Injuries expected if neglected ○ Blockage of passage for pedestrians ○ Haphazard arrangement of construction material | Medium to negligible | <p>execution of the work</p> <ul style="list-style-type: none"> • Construction material will be covered to ensure safe passage between the destinations during transportation. • Materials will not be loaded to a higher level than the side and tail boards and shall be covered with a good quality tarpaulin; • Sufficient space is available within the RoW of roads for storage of construction material. Anyhow, if land may need to be acquired for | Contractor | Visual/ Pictures | <ul style="list-style-type: none"> • Daily site visit during construction phase • Fortnightly/ Weekly • Once during the construction phase | <ul style="list-style-type: none"> • ESFPs • DPO ESM • Supervision Consultants E&S team |

| Proposed Sub-project activities | Potential Env./Soc. Impacts | Magnitude of Impact | Mitigation Measures | Mitigation Implementation Responsibility | Monitoring Indicators | Monitoring Frequency | Monitoring Responsibility |
|---------------------------------|-----------------------------|---------------------|--|--|-----------------------|----------------------|---------------------------|
| | | | temporary storage of machinery & materials contractor will be liable to compensate the land owner accordingly through agreement/ negotiations/voluntarily. Contractor will submit satisfactory handing over certificate from land owner verified by DPO-ESS to the supervision consultant <ul style="list-style-type: none"> • Contractor will lay/ utilize construction materials as per work requirement | | | | |

| Proposed Sub-project activities | Potential Env./Soc. Impacts | Magnitude of Impact | Mitigation Measures | Mitigation Implementation Responsibility | Monitoring Indicators | Monitoring Frequency | Monitoring Responsibility |
|---|---|---------------------|--|--|-----------------------|--|--|
| | | | from his storage site. <ul style="list-style-type: none"> Contractor will use night vision reflective signboards/ reflective tapes to cordon off the area during construction activities. | | | | |
| Labor Camp (if established by Contractor) | <ul style="list-style-type: none"> Health impacts due to absence of housing and sanitation facilities in labor camp. Security of labor Unhygienic conditions | Medium | <ul style="list-style-type: none"> Contractor will prepare Occupational Health and Safety Plan and get approval from DPO-ESSs before the execution of work. For the execution of this sub-project, 30/35 number of workers/ laborers will be required to work for almost 06 months and | Contractor | Visual/ Pictures | <ul style="list-style-type: none"> Daily site visit during construction phase Fortnightly/Weekly Once during the construction phase | <ul style="list-style-type: none"> ESFPs DPO ESM Supervision Consultants E&S team |

| Proposed Sub-project activities | Potential Env./Soc. Impacts | Magnitude of Impact | Mitigation Measures | Mitigation Implementation Responsibility | Monitoring Indicators | Monitoring Frequency | Monitoring Responsibility |
|---------------------------------|-----------------------------|---------------------|---|--|-----------------------|----------------------|---------------------------|
| | | | <p>contractor will be instructed (will be included in his term of reference and in the form of EHS SOPs, implementation) , to prefer the local labor to be engaged, for which labor camp will not be required to be established. Anyhow, for temporary labor site, following mitigation measures will be provided</p> <ul style="list-style-type: none"> • Contractor will ensure provision of appropriate housing, water supply, and sanitation facilities to | | | | |

| Proposed Sub-project activities | Potential Env./Soc. Impacts | Magnitude of Impact | Mitigation Measures | Mitigation Implementation Responsibility | Monitoring Indicators | Monitoring Frequency | Monitoring Responsibility |
|---------------------------------|-----------------------------|---------------------|---|--|-----------------------|----------------------|---------------------------|
| | | | construction labor. <ul style="list-style-type: none"> • Good housekeeping will be ensured inside campsite • Labor will be provided with quality food. • During winter hot water will be provided for bathing and likewise as per the weather condition. • Accommodation will be ensured by the Contractor. • It's better to accommodate labor in Containers Camps/houses with all amenities. • Contractor will submit Campsite | | | | |

| Proposed Sub-project activities | Potential Env./Soc. Impacts | Magnitude of Impact | Mitigation Measures | Mitigation Implementation Responsibility | Monitoring Indicators | Monitoring Frequency | Monitoring Responsibility |
|---------------------------------|--|---------------------|--|--|---|--|--|
| | | | Management Plan and get approval from DPO-ESSs before the execution of work. | | | | |
| Vehicle Movements | <ul style="list-style-type: none"> Traffic congestion Conflicts Vehicle emissions | High | <ul style="list-style-type: none"> Contractor will prepare Traffic management plan and get approval from DPO-ESSs before the execution of work. Sign boards and posters will also be displayed at sub-project site and adjacent areas as well. Inform the residents about timing, schedule and construction work duration. | Contractor | Visual/ Pictures, Vehicle emission tests reports, GRM Complaints record | <ul style="list-style-type: none"> Daily site visit during construction phase Fortnightly/Weekly Once during the construction phase | <ul style="list-style-type: none"> ESFPs DPO ESM Supervision Consultants E&S team |

| Proposed Sub-project activities | Potential Env./Soc. Impacts | Magnitude of Impact | Mitigation Measures | Mitigation Implementation Responsibility | Monitoring Indicators | Monitoring Frequency | Monitoring Responsibility |
|---------------------------------|---|---------------------|---|--|-----------------------|--|--|
| | | | <ul style="list-style-type: none"> ○ Work will be done in portions so that the half portion of road may be used safely and vehicles movement will not be disturbed. ○ Vehicle emissions testing will be ensured (Hand platter, Compactor) once during execution of work | | | | |
| Site Safety Issues | <ul style="list-style-type: none"> • Accidents | High | Contractor will ensure site safety using safety cautions (night vision), boards, flagmen, cordon tapes for smooth flow of traffic and pedestrians during the construction | Contractor | Visual/ Pictures | <ul style="list-style-type: none"> • Daily site visit during construction phase • Fortnightly/Weekly • Once during the construction phase | <ul style="list-style-type: none"> • ESFPs • DPO ESM • Supervision Consultants E&S team |

| Proposed Sub-project activities | Potential Env./Soc. Impacts | Magnitude of Impact | Mitigation Measures | Mitigation Implementation Responsibility | Monitoring Indicators | Monitoring Frequency | Monitoring Responsibility |
|---------------------------------|--|---------------------|---|--|--|--|--|
| | | | phase of the sub-Project. | | | | |
| Public access | Problems for pedestrians. Normal mode of transport may be disturbed during sub-project execution. 05 schools exist within 100m of the Canal road. There will be impediment in the movement of local community during school working hours. | Medium | <ul style="list-style-type: none"> If it required to provide an alternated access route, contractor will ensure that the alternate access route must consider the safety aspects for all kind of pedestrian i.e. women, children, disabled. Cordon off the construction zone. Ensure to work at night for major part of work in which heavy machinery may hinder the public accessibility Implement a proper traffic management plan. | Contractor | No hindrance in the community movement. Visual/ Pictures | <ul style="list-style-type: none"> Daily site visit during construction phase Fortnightly/Weekly Once during the construction phase | <ul style="list-style-type: none"> ESFPs DPO ESM Supervision Consultants E&S team |

| Proposed Sub-project activities | Potential Env./Soc. Impacts | Magnitude of Impact | Mitigation Measures | Mitigation Implementation Responsibility | Monitoring Indicators | Monitoring Frequency | Monitoring Responsibility |
|---------------------------------|---|---------------------|---|--|-----------------------|--|--|
| Occupational Health & Safety | <ul style="list-style-type: none"> Injuries to workers/LTI | High | <ul style="list-style-type: none"> Contractor will follow PMDFC designed Environment, Health and Safety SOPs for Labor/ Workers for all activities on the site and these SOPs will be the part of his term of reference and contractual agreement. Workers will be trained by the PMDFC ESM team and guided to follow SOPs and will be provided with necessary PPEs (Safety Helmets, Safety Shoes, Gloves, Chemical Masks etc.) wherever required. First aid will be provided onsite | Contractor | Visual/ Pictures | <ul style="list-style-type: none"> Daily site visit during construction phase Fortnightly/Weekly Once during the construction phase | <ul style="list-style-type: none"> ESFPs DPO ESM Supervision Consultants E&S team |

| Proposed Sub-project activities | Potential Env./Soc. Impacts | Magnitude of Impact | Mitigation Measures | Mitigation Implementation Responsibility | Monitoring Indicators | Monitoring Frequency | Monitoring Responsibility |
|--|---|---------------------|---|--|--|--|--|
| | | | <ul style="list-style-type: none"> Careful monitoring will also be carried out. | | | | |
| Laying of coarse base, gravel, sub base | <ul style="list-style-type: none"> Injuries to workers | High | <ul style="list-style-type: none"> Contractor will provide Safety Shoes, Hand Gloves, Safety Helmet, and Reflective Vest to all the labor. | Contractor | Visual/ Pictures | <ul style="list-style-type: none"> Daily site visit during construction phase Fortnightly/Weekly Once during the construction phase | <ul style="list-style-type: none"> ESFPs DPO ESM Supervision Consultants E&S team |
| Damage to Public Infrastructure/ utilities | <ul style="list-style-type: none"> Accidents/Incidents/ Injuries Structural loss: Social Conflicts | High | <ul style="list-style-type: none"> Contractor will ensure no damage to public utilities or structures. Contractor will provide compensation for the damages to entitles accordingly | Contractor | Visual/ Pictures/payment record | <ul style="list-style-type: none"> Daily site visit during construction phase Fortnightly/Weekly Once during the construction phase | <ul style="list-style-type: none"> ESFPs DPO ESM Supervision Consultants E&S team |
| Sexual Harassment-Labor Influx-Child Labor | <ul style="list-style-type: none"> Social Conflicts | Low | <ul style="list-style-type: none"> Contractor will give behavioral training to the workforce. | Contractor | Visual/ Pictures/Reported/Complains by public during visit | <ul style="list-style-type: none"> Daily site visit during construction phase | <ul style="list-style-type: none"> ESFPs DPO ESM Supervision Consultants E&S team |

| Proposed Sub-project activities | Potential Env./Soc. Impacts | Magnitude of Impact | Mitigation Measures | Mitigation Implementation Responsibility | Monitoring Indicators | Monitoring Frequency | Monitoring Responsibility |
|---------------------------------|--|---------------------|--|--|-----------------------|--|--|
| | | | <ul style="list-style-type: none"> Contractor will hire local labor for un-skilled works. No child labor is allowed onsite below 14 years. GRM at site level will be ensured to report in case of any such incident | | | <ul style="list-style-type: none"> Fortnightly/Weekly Once during the construction phase | |
| CoViD-19 SOPs implementation | <ul style="list-style-type: none"> Spread of Corona among the labor | Low | <ul style="list-style-type: none"> Contractor will provide face masks to the labor on daily basis to reduce Corona impact. Contractor will follow CoViD-19 guidelines during construction works (Annexure iii) | Contractor | Visual/Pictures | <ul style="list-style-type: none"> Daily site visit during construction phase Fortnightly/Weekly Once during the construction phase | <ul style="list-style-type: none"> ESFPs DPO ESM Supervision Consultants E&S team |
| Operational Phase | | | | | | | |
| Road Maintenance-Road Furniture | <ul style="list-style-type: none"> Accidents Complains | Low | <ul style="list-style-type: none"> MC will maintain road lighting system for night vision. Road surface will be | Contractor | Visual/Pictures | <ul style="list-style-type: none"> | <ul style="list-style-type: none"> MC Officials |

| Proposed Sub-project activities | Potential Env./Soc. Impacts | Magnitude of Impact | Mitigation Measures | Mitigation Implementation Responsibility | Monitoring Indicators | Monitoring Frequency | Monitoring Responsibility |
|---------------------------------|-----------------------------|---------------------|----------------------------|--|-----------------------|----------------------|---------------------------|
| | | | repaired/maintained by MC. | | | | |

7.8. Environmental and Social Management Plan Implementation Budget

Table 7-2: Environmental Implementation Budget

| Sr. No. | Description | Quantity | Per Unit Cost (PKR) | Total Cost (PKR) |
|---|---|----------------|------------------------|------------------|
| 1. Environmental Monitoring | | | | |
| 1.1 | Drinking Water Quality Testing | 2 sample | 15,000 | 30,000 |
| 1.2 | Air quality monitoring covering CO, SO ₂ , O ₂ , NO ₂ , NO, NO _x , CO ₂ , PM2.5, and PM2.10, Smoke | 2 | 25,000 | 50,000 |
| 1.3 | Noise level Monitoring | 2 | 1000 | 2,000 |
| | | | Subtotal (1) | 82,000 |
| 2. Implementation of OHS Requirements | | | | |
| 2.1 | Remuneration of Environmental Manager | 1 for 6 Months | 70,000 | 420,000 |
| 2.2 | Remuneration of Health and Safety Officer (2 months) | 1 for 6 Months | 50,000 | 300,000 |
| 2.3 | Purchase of PPEs | | | |
| a. | Safety Shoes Pairs | 25 | 4,000 | 100,000 |
| b. | P. Caps | 50 | 200 | 10,000 |
| c. | Hard Hats | 30 | 500 | 15,000 |
| d. | Glowing Jackets | 60 | 300 | 18,000 |
| e. | Pairs of Gloves | 100 | 110 | 11,000 |
| f. | Face Masks | 1,000 | 10 | 10,000 |
| g. | Sanitizers | 60 | 300 | 18,000 |
| 2.4 | Establishment of dispensary (Salary of Dispenser) | 1 for 6 months | 25,000 | 150,000 |
| 2.5 | Medicines (LS) | Lump Sum | 50,000 | 50,000 |
| 2.6 | First Aid Box | 12 | 2000 | 24,000 |
| 2.7 | Misc. | Lump Sum | 10,000 | 10,000 |
| | | | Subtotal (2) | 1,136,000 |
| 3. Training sessions with contractor labour force and with local communities at site on code of ethics and GRM | | | | |
| 3.1 | Boarding and Lodging | Lump Sum | 25,000 | 25,000 |
| 3.2 | Transportation | Lump Sum | 25,000 | 25,000 |
| 3.3 | Training Material | Lump Sum | 15,000 | 15,000 |
| 3.4 | Entertainment | Lump Sum | 30,000 | 40,000 |
| 3.5 | Misc. | Lump Sum | 10,000 | 10,000 |
| | | | Subtotal (3) | 115,000 |
| | | | Total (1+2+3+4) | 1,333,000 |

Section-8 Capacity Building

8.1. General

A comprehensive program will be followed to strengthen the technical and institutional capacities of the executing agency (MC Okara), contractors, and laborers.

Table 8-1: Training/ Awareness and Sensitization Plan

| Components | Audience | Level | Modality | Frequency | Responsibility |
|--|---|--|--|---|----------------|
| ESMF Site Specific requirements and E&S Management and Mitigation Plan | MO-1 MC field staff ³ MO-P and field staff ³ | Training | Briefing Presentations Mock Activities | Before execution of sub-project and time to time instructions | PMDFC ESM team |
| ESMP Implementation and Monitoring Plan | MO-1 MC field staff | Training | Briefing Presentations Mock Activities | | |
| | Contractor | Awareness and sensitization | Briefing | At the time of Contract signing and before execution | DPO-ESM ESFPs |
| | Labor | Awareness and sensitization | Briefing | Before execution and time to time during execution | DPO-ESM ESFPs |
| EHS SOPs for Labor/Workers (including women workers) | Contractor | Awareness and sensitization | Briefing and Illustrations | Before execution and time to time during execution | DPO-ESM ESFPs |
| | Labor/workers | Awareness and sensitization on SOPs Training on Use of PPEs | Presentations Illustrations Mock activities Resource material | Before execution and time to time during execution | DPO-ESM ESFPs |
| GRM | Contractor | Awareness and sensitization | Briefing | Before execution and time to time during execution | DPO-ESM ESFPs |

³ For ESFPs and MC field staff, PMDFC will organize time to time trainings and a training/ capacity building program has been designed in this regard

| Components | Audience | Level | Modality | Frequency | Responsibility |
|-------------------|------------------------|-----------------------------------|---|--|-----------------------|
| | Labor/ workers | Awareness and sensitization | Briefing and resource material | Before execution and time to time during execution | DPO-ESM ESFPs |
| | Public/ communities | Awareness | Briefing during public consultation Resource material | Before and during execution | DPO-ESM ESFPs |

Annexure i: Environment & Social Screening Checklist

Instructions:

Environmental and Social Focal Persons (ESFPs)¹ nominated by the MCs for PCP environmental and social management, will use this checklist in field for environmental and social screening and categorization of each and every sub-project proposed to be executed under the Program.

Deputy Program Officers-Environmental and Social Management deputed by PMDFC in regional offices will technically assist and support the ESFPs/MCs in filling in of this Checklist

It is to be attached with the main document² of sub-projects at planning stage and will be duly signed by the relevant ESFP and endorsed by the respective DPO-ESM

This checklist focuses on environmental issues and social concerns. To ensure that social dimensions are adequately considered, Involuntary Resettlement Screening Checklist will also be used

(iii) The purpose of this E&S Screening Checklists is to identify potential “Negative” impacts of environmental and social attributes or to enhance the existing environmental & social benefits. Use the “remarks” section to discuss any anticipated mitigation measures.

Name of ESFP: Mushtaq Manda

Name of MC: Okara

Sub-Project Sector: Roads

Sub-Project Title: Improvement, Widening and Raising of Road from Tank Chowk to Akbar Chowk along Canal Road

Sub- Project Categorization: E-2 S-2

Date of Screening: 01.11.2022

Anticipated Project Activities:

- Scarifying and dismantling of road
- Preparation of Sub- Grade
- Laying of Sub- Base
- Laying of Base Course
- Asphalt wearing course
- Installation of street lights

Estimated Cost of Subproject: 100.93 Million

Tentative Completion Time/ Duration:6 Months

Estimated Labor for Subproject: 20-30

¹ In all MCs, ESFPs are notified by Local government; MO (I&S) are focal persons for environmental sector and MO (P) are focal persons for social sectors.

² It is meant as PC-I and/or engineering estimates of sub-project

| Screening Questions | Yes | No | Remarks |
|--|-----|----|---|
| A. Project Siting | | | |
| Is the Sub-Project area adjacent to or within any of the following: | | | |
| Environmentally sensitive areas? | | | |
| Legally protected Area | | ✓ | No legally protected area i.e. wildlife sanctuary, national park or game reserve exist within or near the project area |
| Any surface water body (river, canal, stream, lake, wetland) within 250 meter of the proposed sub project ³ | ✓ | | A canal is flowing at right side along the road and surface water may be affected due to project activities |
| Estuarine | | ✓ | No estuarine within or near the project area |
| Special area for protecting biodiversity | | ✓ | No ecological significant habitat exists within or near the project area |
| Buffer zone of protected area | | ✓ | No protected area exists in the vicinity of the subproject area |
| Mangroves Forest | | ✓ | No mangrove forest is located near the project area |
| Man-made forest /game reserve, orchid/ crops or any other area of environmental importance | ✓ | | There are 53 mature trees on both sides of canal road but no tree will be required to cut or uprooted. |
| Socially sensitive /important areas/communities/ people? | | | |
| PCRs and or any site of cultural/ religious importance (Graveyard, Shrine, Mosque, Church, <i>Gordwarah</i> , Temple, Fort, archeological/ historical site) within 100 m of the proposed subproject ⁴ | | ✓ | No PCR was noted within or near the subproject area |
| Sensitive receptors (Schools, colleges, hospitals and clinics) within 100 meter of the proposed sub project ⁵ | ✓ | | There are 05 schools along the entire stretch of road, where educational activities may be affected due to project interventions. Ramps of three schools (Allied School, The Knowledge school and Dar-e-Arqam) will be partially affected due to widening of road. It will be advised to implement traffic management plan during construction and ensure safety of children by applying SOPs related to construction safety while executing activities near schools. Further it will be required to monitor noise levels of machinery and equipment to keep them within safe limits. |
| Any graveyard of local community (Muslims or Christians) | | ✓ | No graveyard |

| | | | |
|---|---|---|---|
| Any demographic or socio-economic aspects of the sub-project area that are already vulnerable (e.g., high incidence of marginalized populations, rural-urban migrants, illegal settlements, squatters, ethnic minorities, people with disabilities, people in old age, socially isolated segments ⁶ of the society and women or children)? | | ✓ | No vulnerable group exists within the sub-project area |
| Already existing infrastructure ⁷ (including public amenities) which may be required to dismantle or may be affected temporarily by any means? | ✓ | | The ramps, tough paver ramps of 03 schools will have to be dismantled and reconstructed after the widening of road from 14 to 24 feet. Further 01 electric pole will also have to be relocated. |

B. Potential Environmental Impacts

Will the Sub-Project cause...

| | | | |
|---|---|---|--|
| 1. Disturbance to habitats/ biodiversity of environmentally sensitive or protected areas? | | ✓ | No sensitive habitats or protected area exist in the subproject area |
| 2. Cutting of trees? | ✓ | | There are 53 mature trees on both sides of canal road but no tree will be required to cut or uprooted. |
| 3. Disruption to habitats/ biodiversity of surrounding ecosystem/ environment? | ✓ | | Cutting of trees can disturb the associated fauna. |
| 4. Generation of wastewater during construction or operation? | | ✓ | No separate establishment of contractor's camp is anticipated so no waste water would be generated during construction |
| 5. Pollution of surface water/ground water due to wastewater discharge from construction site or due to direct/indirect disposal of waste water? | | ✓ | No waste water will be generated due to subproject interventions |
| 6. Alteration of surface water hydrology of waterways resulting in increased sediment in streams/ rivers or due to increased soil erosion at construction site? | | ✓ | No alteration of surface water hydrology due to subproject interventions |
| 7. Deterioration of surface water quality due to silt runoff and sanitary wastes from worker-based camps and chemicals used in construction? | | ✓ | No deterioration of surface water quality due to subproject interventions |
| 8. Over pumping of ground water, leading to salinization and ground subsidence? | | ✓ | No over pumping of groundwater will be required for the subproject |
| 9. Serious contamination of soil due to construction works? | ✓ | | Due to use of chemicals (asphalt, oil/ fuel) and movement of project machinery there are chances of soil contamination which will be mitigated by avoiding spill of oil/ fuel and safe use of coal tar to avoid soil contamination |

| | | | |
|---|---|---|--|
| 10. Aggravation of solid waste problems in the area? | ✓ | | Due to widening of existing road there are chances of aggravation of construction waste in the project area, which may cause hindrance in the movement of local people. All generated waste will be required to be removed daily to an environmentally safe waste dumping site immediately |
| 11. Generation of hazardous waste? | | ✓ | Bitumen mixed solid waste will be generated as a result of dismantling of road that would be harmful if not properly disposed of. The excavated materials would be disposed of as per approval of the supervision engineer |
| 12. Increased air pollution due to sub-project construction and operation? | ✓ | | Due to project interventions it is anticipated that ambient air of the project area may be temporarily affected due to dust emissions and smoke generated from project vehicles and machinery. Water sprinkling will be required to be done periodically on daily basis and contractor will have to keep his machinery and equipment well-tuned to avoid smoke emissions |
| 13. Noise and vibration due to sub-project construction or operation? | ✓ | | Noise produced from machinery operating at project site may cause disturbance to residents and workers. Contractor will be required to use new machinery to avoid noise emissions. Contractor will provide ear plugs/ muffs to workers near noise producing machinery and shall monitor noise levels periodically throughout the day during construction works. |
| 14. Creation of temporary breeding habitats for diseases such as those transmitted by mosquitoes and rodents due to solid/liquid? | | ✓ | No temporary breeding habitats will be developed due to sub project interventions |
| 15. Use of chemicals during construction? | ✓ | | Due to use of chemicals (asphalt, oil/ fuel) and movement of project machinery there are chances of soil contamination which will be mitigated by avoiding spill of oil/ fuel and safe use of coal tar to avoid soil contamination |
| C: Potential Social Impacts Will the Sub-Project cause... | | | |
| 1. Impairment of historical/ cultural areas; disfiguration of landscape or potential loss/ damage to Physical Cultural Resources (PCRs)? | | ✓ | There will be no damages to Physical Cultural Resources (PCRs) |

Environment & Social Management Plan (ESMP), Canal Road Okara

| | | |
|---|----------|---|
| <p>2. Displacement or involuntary resettlement of people? (physical displacement and/ or economic displacement) (If “Yes”, please also fill Involuntary Resettlement Screening Checklist)</p> | <p>✓</p> | <p>The tough paver ramps of 03 schools will have to be dismantled and reconstructed after the widening of road from 14 to 24 feet. Further 01 electric pole will also have to be relocated.</p> |
| <p>3. Disproportionate impacts on the poor, women and children and or other vulnerable groups ⁸(mentioned above)?</p> | <p>✓</p> | <p>There will be no disproportionate impacts on the poor, women and children and or other vulnerable groups due to subproject interventions</p> |
| <p>4. Temporary impediments in movements of people/ transport and animals?</p> | <p>✓</p> | <p>Due to project interventions there will be temporary impediment in the movement of local people which will be managed by working in patches so as to provide alternate passage way on other side and dump construction in a way that does not interfere with the commutation of local community and passersby.</p> |
| <p>5. Large population influx during sub-project construction and operation that causes increased burden on social infrastructure and services (such as water supply and sanitation systems)?</p> | <p>✓</p> | <p>There will be no population influx during sub-project execution</p> |
| <p>6. Social conflicts if workers from other areas are</p> | <p>✓</p> | <p>Mostly local workers will be hired.</p> |
| <p>7. Risks and vulnerabilities related to occupational health and safety due to physical, chemical, biological, and radiological hazards during project construction and operation?</p> | <p>✓</p> | <p>Workers will be provided PPEs, and trainings will be imparted to them regarding their use. Site related OHS guidelines shall be displayed at site and will be implemented by the contractor and supervision consultant will monitor its implementation at site</p> |
| <p>8. Risks to community health and safety due to the transport, storage, and use and/ or disposal of materials such as explosives, fuel and other chemicals during construction and operation?</p> | <p>✓</p> | <p>Construction material will be transported to site while covered with tarpaulin to avoid impact on community. Oil/ fuel will be transferred safely at a workshop or fuel station to avoid risk.</p> |
| <p>9. Community safety risks due to both accidental and natural causes, especially where the structural elements or components of the project are accessible to members of the affected community or where their failure could result in injury to the community throughout project construction, operation and decommissioning?</p> | <p>✓</p> | <p>Entrance to working site will be restricted by installing barricade tape. Safety/ caution sign boards will be erected and flag men will be appointed to control traffic and keep irrelevant persons away from project site</p> |



Environment & Social Management Plan (ESMP), Canal Road Okara

| | | |
|--|----------|---|
| <p>10. Any impact on sensitive receptors (mentioned above)</p> | <p>✓</p> | <p>There are 5 schools along the entire stretch of road, where educational activities may be affected due to project interventions. It will be advised to implement traffic management plan during construction and ensure safety of children by applying SOPs related to construction safety while executing activities near schools. Further it will be required to monitor noise levels of machinery and equipment to keep them within safe limits</p> |
| <p>11. Any impact of negative nature on already existing infrastructure including public amenities</p> | <p>✓</p> | <p>The tough paver ramps of 03 schools will have to be dismantled and reconstructed after the widening of road from 14 to 24 feet. Further 01 electric pole will also have to be relocated.</p> |

Prepared by:

- i. Dr. Ashraf Bodla- Environmental Specialist, MMP
- ii. Saqib Sadiq-Sociologist, MMP

Annexure ii: IFC EHS Guidelines for Construction and Decommissioning

| | | |
|--|---|---|
| General EHS Guidelines [Complete version] at: www.ifc.org/ehsguidelines | | |
|  | Environmental, Health, and Safety (EHS) Guidelines GENERAL EHS GUIDELINES: CONSTRUCTION AND DECOMMISSIONING |  WORLD BANK GROUP |

4.0 Construction and Decommissioning

| | |
|---|----|
| 4.1 Environment..... | 89 |
| Noise and Vibration | 89 |
| Soil Erosion..... | 89 |
| Air Quality..... | 90 |
| Solid Waste..... | 90 |
| Hazardous Materials..... | 91 |
| Wastewater Discharges..... | 91 |
| Contaminated Land | 91 |
| 4.2 Occupational Health and Safety..... | 92 |
| 4.3 Community Health and Safety | 94 |
| General Site Hazards | 94 |
| Disease Prevention | 94 |
| Traffic Safety..... | 95 |

Applicability and Approach

This section provides additional, specific guidance on prevention and control of community health and safety impacts that may occur during new project development, at the end of the project life-cycle, or due to expansion or modification of existing project facilities. Cross referencing is made to various other sections of the General EHS Guidelines.

4.1 Environment { TC "4.1 Environment" \f C \l "2" }

Noise and Vibration

During construction and decommissioning activities, noise and vibration may be caused by the operation of pile drivers, earth moving and excavation equipment, concrete mixers, cranes and the transportation of equipment, materials and people. Some recommended noise reduction and control strategies to consider in areas close to community areas include:

- Planning activities in consultation with local communities so that activities with the greatest potential to generate noise are

planned during periods of the day that will result in least disturbance

- Using noise control devices, such as temporary noise barriers and deflectors for impact and blasting activities, and exhaust muffling devices for combustion engines.
- Avoiding or minimizing project transportation through community areas

Soil Erosion

Soil erosion may be caused by exposure of soil surfaces to rain and wind during site clearing, earth moving, and excavation activities. The mobilization and transport of soil particles may, in turn, result in sedimentation of surface drainage networks, which may result in impacts to the quality of natural water systems and ultimately the biological systems that use these waters.

Recommended soil erosion and water system management approaches include:

Sediment mobilization and transport

- Reducing or preventing erosion by:
 - Scheduling to avoid heavy rainfall periods (i.e., during the dry season) to the extent practical
 - Contouring and minimizing length and steepness of slopes
 - Mulching to stabilize exposed areas
 - Re-vegetating areas promptly
 - Designing channels and ditches for post-construction flows
 - Lining steep channel and slopes (e.g. use jute matting)
- Reducing or preventing off-site sediment transport through use of settlement ponds, silt fences, and water treatment, and modifying or suspending activities during extreme rainfall and high winds to the extent practical.



Clean runoff management

- Segregating or diverting clean water runoff to prevent it mixing with water containing a high solids content, to minimize the volume of water to be treated prior to release

Road design

- Limiting access road gradients to reduce runoff-induced erosion
- Providing adequate road drainage based on road width, surface material, compaction, and maintenance

Disturbance to water bodies

- Depending on the potential for adverse impacts, installing free-spanning structures (e.g., single span bridges) for road watercourse crossings
- Restricting the duration and timing of in-stream activities to lower low periods, and avoiding periods critical to biological cycles of valued flora and fauna (e.g., migration, spawning, etc.)
- For in-stream works, using isolation techniques such as berming or diversion during construction to limit the exposure of disturbed sediments to moving water
- Consider using trenchless technology for pipeline crossings (e.g., suspended crossings) or installation by directional drilling

Structural (slope) stability

- Providing effective short term measures for slope stabilization, sediment control and subsidence control until long term measures for the operational phase can be implemented
- Providing adequate drainage systems to minimize and control infiltration

Air Quality

Construction and decommissioning activities may generate emission of fugitive dust caused by a combination of on-site excavation and movement of earth materials, contact of construction machinery with bare soil, and exposure of bare soil and soil piles to wind. A secondary source of emissions may include exhaust from diesel engines of earth moving equipment, as well as from open burning of solid waste on-site. Techniques to consider for the reduction and control of air emissions from construction and decommissioning sites include:

- Minimizing dust from material handling sources, such as conveyors and bins, by using covers and/or control equipment (water suppression, bag house, or cyclone)
- Minimizing dust from open area sources, including storage piles, by using control measures such as installing enclosures and covers, and increasing the moisture content
- Dust suppression techniques should be implemented, such as applying water or non-toxic chemicals to minimize dust from vehicle movements
- Selectively removing potential hazardous air pollutants, such as asbestos, from existing infrastructure prior to demolition
- Managing emissions from mobile sources according to Section 1.1
- Avoiding open burning of solid (refer to solid waste management guidance in Section 1.6)

Solid Waste

Non-hazardous solid waste generated at construction and decommissioning sites includes excess fill materials from grading and excavation activities, scrap wood and metals, and small concrete spills. Other non-hazardous solid wastes include office, kitchen, and dormitory wastes when these types of operations are part of construction project activities. *Hazardous solid waste* includes contaminated soils, which could potentially be encountered on-site due to previous land use activities, or small



amounts of machinery maintenance materials, such as oily rags, used oil filters, and used oil, as well as spill cleanup materials from oil and fuel spills. Techniques for preventing and controlling non-hazardous and hazardous construction site solid waste include those already discussed in Section 1.6.

Hazardous Materials

Construction and decommissioning activities may pose the potential for release of petroleum based products, such as lubricants, hydraulic fluids, or fuels during their storage, transfer, or use in equipment. These materials may also be encountered during decommissioning activities in building components or industrial process equipment. Techniques for prevention, minimization, and control of these impacts include:

- Providing adequate secondary containment for fuel storage tanks and for the temporary storage of other fluids such as lubricating oils and hydraulic fluids,
- Using impervious surfaces for refueling areas and other fluid transfer areas
- Training workers on the correct transfer and handling of fuels and chemicals and the response to spills
- Providing portable spill containment and cleanup equipment on site and training in the equipment deployment
- Assessing the contents of hazardous materials and petroleum-based products in building systems (e.g. PCB containing electrical equipment, asbestos-containing building materials) and process equipment and removing them prior to initiation of decommissioning activities, and managing their treatment and disposal according to Sections 1.5 and 1.6 on Hazardous Materials and Hazardous Waste Management, respectively
- Assessing the presence of hazardous substances in or on building materials (e.g., polychlorinated biphenyls, asbestos-containing flooring or insulation) and decontaminating or properly managing contaminated building materials

Wastewater Discharges

Construction and decommissioning activities may include the generation of sanitary wastewater discharges in varying quantities depending on the number of workers involved. Adequate portable or permanent sanitation facilities serving all workers should be provided at all construction sites. Sanitary wastewater in construction and other sites should be managed as described in Section 1.3.

Contaminated Land

Land contamination may be encountered in sites under construction or decommissioning due to known or unknown historical releases of hazardous materials or oil, or due to the presence of abandoned infrastructure formerly used to store or handle these materials, including underground storage tanks. Actions necessary to manage the risk from contaminated land will depend on factors such as the level and location of contamination, the type and risks of the contaminated media, and the intended land use. However, a basic management strategy should include:

- Managing contaminated media with the objective of protecting the safety and health of occupants of the site, the surrounding community, and the environment post construction or post decommissioning
- Understanding the historical use of the land with regard to the potential presence of hazardous materials or oil prior to initiation of construction or decommissioning activities
- Preparing plans and procedures to respond to the discovery of contaminated media to minimize or reduce the risk to health, safety, and the environment consistent with the approach for Contaminated Land in Section 1.6
- Preparation of a management plan to manage obsolete, abandoned, hazardous materials or oil consistent with the approach to hazardous waste management described in Section 1.6.



Successful implementation of any management strategy may require identification and cooperation with whoever is responsible and liable for the contamination.

4.2 Occupational Health and Safety

TC "4.2 Occupational Health and Safety" \f C \l "2" }

Over-exertion

Over-exertion, and ergonomic injuries and illnesses, such as repetitive motion, over-exertion, and manual handling, are among the most common causes of injuries in construction and decommissioning sites. Recommendations for their prevention and control include:

- Training of workers in lifting and materials handling techniques in construction and decommissioning projects, including the placement of weight limits above which mechanical assists or two-person lifts are necessary
- Planning work site layout to minimize the need for manual transfer of heavy loads
- Selecting tools and designing work stations that reduce force requirements and holding times, and which promote improved postures, including, where applicable, user adjustable work stations
- Implementing administrative controls into work processes, such as job rotations and rest or stretch breaks

Slips and Falls

Slips and falls on the same elevation associated with poor housekeeping, such as excessive waste debris, loose construction materials, liquid spills, and uncontrolled use of electrical cords and ropes on the ground, are also among the most frequent cause of lost time accidents at construction and decommissioning sites. Recommended methods for the prevention of slips and falls from, or on, the same elevation include:

- Implementing good house-keeping practices, such as the sorting and placing loose construction materials or demolition debris in established areas away from foot paths
- Cleaning up excessive waste debris and liquid spills regularly
- Locating electrical cords and ropes in common areas and marked corridors
- Use of slip retardant footwear

Work in Heights

Falls from elevation associated with working with ladders, scaffolding, and partially built or demolished structures are among the most common cause of fatal or permanent disabling injury at construction or decommissioning sites. If fall hazards exist, a fall protection plan should be in place which includes one or more of the following aspects, depending on the nature of the fall hazard⁹⁵:

- Training and use of temporary fall prevention devices, such as rails or other barriers able to support a weight of 200 pounds, when working at heights equal or greater than two meters or at any height if the risk includes falling into operating machinery, into water or other liquid, into hazardous substances, or through an opening in a work surface
- Training and use of personal fall arrest systems, such as full body harnesses and energy absorbing lanyards able to support 5000 pounds (also described in this section in Working at Heights above), as well as fall rescue procedures to deal with workers whose fall has been successfully arrested. The tie in point of the fall arresting system should also be able to support 5000 pounds
- Use of control zones and safety monitoring systems to warn workers of their proximity to fall hazard zones, as well as

⁹⁵ Additional information on identification of fall hazards and design of protection systems can be found in the United States Occupational Health and Safety Administration's (US OSHA) web site: <http://www.osha.gov/SLTC/fallprotection/index.html>



securing, marking, and labeling covers for openings in floors, roofs, or walking surfaces

a turn while moving. Techniques for the prevention and control of these impacts include:

Struck By Objects

Construction and demolition activities may pose significant hazards related to the potential fall of materials or tools, as well as ejection of solid particles from abrasive or other types of power tools which can result in injury to the head, eyes, and extremities. Techniques for the prevention and control of these hazards include:

- Using a designated and restricted waste drop or discharge zones, and/or a chute for safe movement of wastes from upper to lower levels
- Conducting sawing, cutting, grinding, sanding, chipping or chiseling with proper guards and anchoring as applicable
- Maintaining clear traffic ways to avoid driving of heavy equipment over loose scrap
- Use of temporary fall protection measures in scaffolds and out edges of elevated work surfaces, such as hand rails and toe boards to prevent materials from being dislodged
- Evacuating work areas during blasting operations, and using blast mats or other means of deflection to minimize fly rock or ejection of demolition debris if work is conducted in proximity to people or structures
- Wearing appropriate PPE, such as safety glasses with side shields, face shields, hard hats, and safety shoes

- Planning and segregating the location of vehicle traffic, machine operation, and walking areas, and controlling vehicle traffic through the use of one-way traffic routes, establishment of speed limits, and on-site trained flag-people wearing high-visibility vests or outer clothing covering to direct traffic
- Ensuring the visibility of personnel through their use of high visibility vests when working in or walking through heavy equipment operating areas, and training of workers to verify eye contact with equipment operators before approaching the operating vehicle
- Ensuring moving equipment is outfitted with audible back-up alarms
- Using inspected and well-maintained lifting devices that are appropriate for the load, such as cranes, and securing loads when lifting them to higher job-site elevations.

Dust

- Dust suppression techniques should be implemented, such as applying water or non-toxic chemicals to minimize dust from vehicle movements
- PPE, such as dust masks, should be used where dust levels are excessive

Confined Spaces and Excavations

Examples of confined spaces that may be present in construction or demolition sites include: silos, vats, hoppers, utility vaults, tanks, sewers, pipes, and access shafts. Ditches and trenches may also be considered a confined space when access or egress is limited. In addition to the guidance provided in Section 2.8 the occupational hazards associated with confined spaces and excavations in construction and decommissioning sites should be prevented according to the following recommendations:

Moving Machinery

Vehicle traffic and use of lifting equipment in the movement of machinery and materials on a construction site may pose temporary hazards, such as physical contact, spills, dust, emissions, and noise. Heavy equipment operators have limited fields of view close to their equipment and may not see pedestrians close to the vehicle. Center-articulated vehicles create a significant impact or crush hazard zone on the outboard side of



- Controlling site-specific factors which may contribute to excavation slope instability including, for example, the use of excavation dewatering, side-walls support, and slope gradient adjustments that eliminate or minimize the risk of collapse, entrapment, or drowning
- Providing safe means of access and egress from excavations, such as graded slopes, graded access route, or stairs and ladders
- Avoiding the operation of combustion equipment for prolonged periods inside excavations areas where other workers are required to enter unless the area is actively ventilated

Other Site Hazards

Construction and decommissioning sites may pose a risk of exposure to dust, chemicals, hazardous or flammable materials, and wastes in a combination of liquid, solid, or gaseous forms, which should be prevented through the implementation of project-specific plans and other applicable management practices, including:

- Use of specially trained personnel to identify and remove waste materials from tanks, vessels, processing equipment or contaminated land as a first step in decommissioning activities to allow for safe excavation, construction, dismantling or demolition
- Use of specially trained personnel to identify and selectively remove potentially hazardous materials in building elements prior to dismantling or demolition including, for example, insulation or structural elements containing asbestos and Polychlorinated Biphenyls (PCBs), electrical components containing mercury⁹⁶
- Use of waste-specific PPE based on the results of an occupational health and safety assessment, including

respirators, clothing/protective suits, gloves and eye protection

4.3 Community Health and Safety

General Site Hazards

Projects should implement risk management strategies to protect the community from physical, chemical, or other hazards associated with sites under construction and decommissioning. Risks may arise from inadvertent or intentional trespassing, including potential contact with hazardous materials, contaminated soils and other environmental media, buildings that are vacant or under construction, or excavations and structures which may pose falling and entrapment hazards. Risk management strategies may include:

- Restricting access to the site, through a combination of institutional and administrative controls, with a focus on high risk structures or areas depending on site-specific situations, including fencing, signage, and communication of risks to the local community
- Removing hazardous conditions on construction sites that cannot be controlled affectively with site access restrictions, such as covering openings to small confined spaces, ensuring means of escape for larger openings such as trenches or excavations, or locked storage of hazardous materials

Disease Prevention

Increased incidence of communicable and vector-borne diseases attributable to construction activities represents a potentially serious health threat to project personnel and residents of local communities. Recommendations for the prevention and control of communicable and vector-borne diseases also applicable to

⁹⁶ Additional information on the management and removal of asbestos containing building materials can be found in ASTM Standard E2356 and E1368



construction phase activities are provided in Section 3.6 (Disease Prevention).

Traffic Safety

Construction activities may result in a significant increase in movement of heavy vehicles for the transport of construction materials and equipment increasing the risk of traffic-related accidents and injuries to workers and local communities. The incidence of road accidents involving project vehicles during construction should be minimized through a combination of education and awareness-raising, and the adoption of procedures described in Section 3.4 (Traffic Safety).

Annexure iii: COVID-19 Pandemic and Health Safety Measures

Given the unprecedented nature of the COVID-19 pandemic, contractors are bound to take all necessary precautions to maintain the health and safety related measures at site and to ensure suitable arrangements regarding hygiene requirements for the prevention of pandemic. Following are the measures that should be implemented at the construction site to avoid the spread of Covid-19:

| Activities | Adaptive Measures |
|---|--|
| Pre- Execution Phase | |
| A. Profile preparation | <ul style="list-style-type: none"> • Detail profile of project workforce • Enlist the names, addresses and contact # • Breakdown of the workforce (workers from local communities and those who have on site accommodation) • Assigning the task against each person • Schedule the key activities and their duration at site |
| B. Initial Screening | <ul style="list-style-type: none"> • All enlisted workforce should go through initial screening process • Ensuring the availability of Thermo gun at site • Record keeping against initial screening • Identifying all workers who are initially at more risk of contracting Covid-19 |
| During Execution Phase | |
| A. Preliminary Screening | <p>Regular Screening:</p> <ul style="list-style-type: none"> • Regular screening by using Thermo gun on daily basis before starting civil work at site • Checking and recording temperatures of workers and other people entering the site or requiring self-reporting prior to or on entering the site. • If a worker has symptoms of COVID-19 (e.g. fever, dry cough, fatigue) the worker should be removed immediately from work activities and isolated on designated site. • Co-workers (i.e. workers with whom the sick worker was in close contact) should be required to stop work, and to quarantine themselves for 14 days, even if they have no symptoms. <p>Sequential Screening:</p> <ul style="list-style-type: none"> • Concerned DHQ medical staff is requested for screening at regular intervals. List should also be shared with DHQ for avoiding future inconvenience or hire health safety officer on weekly basis. |
| B. Special Arrangements regarding PPEs | <ul style="list-style-type: none"> • Ensuring availability of hand washing facilities (sanitizers/soaps) at site • Presence of closed waste bins at key places throughout site, including at entrances/exits to work areas (toilet, canteen or food distribution, or provision of drinking water; in worker accommodation; at waste stations; at stores; and in common spaces). • Special arrangements regarding PPEs and sanitation at site • Record keeping of stock availability on daily basis |
| C. Restricted Movement/ | <ul style="list-style-type: none"> • Encourage employees to wash their hands at least for 20 seconds with soap and stay at least one meter away from people who are coughing or sneezing |

| Activities | Adaptive Measures |
|---|--|
| Demobilization of staff | <ul style="list-style-type: none"> • Breakdown of workers who reside at home (i.e. workers from the communities), workers who lodge within the local communities and workers in on-site accommodation. Workers accommodated on site should be required to minimize contact with people near the site, and in certain cases be prohibited from leaving the site for the duration of their contract, so that contact with local communities is avoided. • Workers from local communities, who return home daily, weekly or monthly, will be more difficult to manage. They should be subject to health checks at entry to the site (as set out above) and at some point, circumstances may make it necessary to require them to either use accommodation on site or not to come to work. • All workers should be provided separate accommodation. |
| D. Training sessions | <ul style="list-style-type: none"> • Health and safety training for Contractor's Personnel (which include project workers and all personnel that the Contractor uses on site, including staff and other employees of the Contractor and Subcontractors and any other personnel assisting the Contractor in carrying out project activities. • Sessions related to safety procedures, use of construction PPEs, occupational health and safety issues, and code of conduct specially privacy issues including social distancing. • Arranging daily briefings with workforce, reminding workers to self-monitor for possible symptoms (fever, cough) and to report to their supervisor or the COVID-19 focal point if they have symptoms or are feeling unwell. • Placing posters and sign boards around the site in local languages. • Appointing one person on daily basis among the workforce who will serve as trainer for conducting awareness session and encouraging the rest to take preventive measures. |
| E. Operationalization of Grievance Redress Mechanism | <ul style="list-style-type: none"> • Effective implementation of GRM at site • Encouraging to report any COVID-19 related health issue and concerns about the health of their co-workers and other staff as well. • In case of unavailability of the PPEs at site, grievance would be lodged directly to PMU. |
| F. Role of PMU | <ul style="list-style-type: none"> • PMU is required to arrange regular meetings with Contractors and workforce to monitor all procedural implementation of COVID-19 prevention related mechanism. • Arrange meeting with concerned DHQs for immediate support and guidance in case of emergency. • During inspection visit by PMU Staff, if a worker is found to has symptoms of COVID-19, the worker should be removed immediately from work activities and isolated on designated site. |
| Post Execution Phase | |
| A. Post Screening | <ul style="list-style-type: none"> • Screening should be done at the end of the day on daily basis, if a worker is found to have any symptoms of COVOD-19, he should be immediately reported to concerned health department. |
| B. Cleaning and waste disposal | <ul style="list-style-type: none"> • All waste (PPEs and sanitation related) shall be disposed properly at designated sites. |

Annexure iv: List of Persons Consulted

| Sr. No. | Name | Designation | Department/Contact No. |
|---------------------------------|-----------------------|--|---|
| Institution Consultation | | | |
| 1. | Zahid Iqbal | Additional Deputy Commissioner (General) | District Administration 044 9200035 |
| 2. | Zaheer Liaqat Baig | Administrator | MC Okara 0301 4488600 |
| 3. | Muhammad Nasim | Chief Officer | MC Okara 0333 8402836 |
| 4. | Mr. Ali Raza | Sub-Engineer | MC Okara 0312 6062810 |
| 5. | Rana Irfan Ali Masood | Executive Engineer | LESCO |
| 6. | Ahsan Bilal | Circle Head Draftsman | LESCO 0322 6990702 |
| 7. | Sarfraz Ali | Sub Divisional Officer | Irrigation 0345 7490533 |
| 8. | Javaid Suleman | Assistant | Forest 0345 7501415 |
| 9. | Rashid Ahmad | Head Clerk | Forest 0347 6744971 |
| 10. | Mahmood Ahmad | Sr. Clerk | Forest 0301 7336921 |
| 11. | Muhammad Tufail | Principal | Savvy School, Canal Road |
| 12. | Arshad Ali | Principal | Allied School, Canal Road 044 27067256 |
| Communities Consultation | | | |
| Canal Road | | | |
| | Name | Location | Contact No. |
| 1. | Muhammad Tufail | Canal Road | 35302-1869660-5 |
| 2. | Muhammad Aizaz | Canal Road | -- |
| 3. | Ch. M. Siddique | Canal Road | -- |
| 4. | Zohaib Ahmad | Canal Road | 03007095630 |
| 5. | M. Nadeem | Canal Road | 03027346310 |
| 6. | Haji M. Rafique | Canal Road | 03039972267 |
| 7. | Umar Rafique | Canal Road | 03027192508 |
| 8. | Muhammad Usama | Canal Road | 03226921008 |
| 9. | Ahmad Baloch | Canal Road | 03007140730 |

| | | | |
|-----|------------------|------------|-------------|
| 10. | Haji Naeem | Canal Road | 03137265099 |
| 11. | Sadiq Minhas | Canal Road | 03347424662 |
| 12. | Ibrar Hussain | Canal Road | 03226921008 |
| 13. | Muhammad Arsalan | Canal Road | 03059591034 |
| 14. | Muhammad Shafiq | Canal Road | 03004694073 |
| 15. | Muhammad Awais | Canal Road | 03217097613 |
| 16. | Sarfraz Ali | Canal Road | 03449112518 |
| 17. | Muhammad Arshad | Canal Road | 03017561240 |

Annexure v: Personal Protective Equipment According to Hazard⁴

| Objective | Workplace Hazards | Suggested PPE |
|-------------------------|---|---|
| Eye and face protection | Flying particles, molten metal, liquid chemicals, gases or vapors, light radiation. | Safety Glasses with side-shields, protective shades, etc. |
| Head protection | Falling objects, inadequate height clearance, and overhead power cords. | Plastic Helmets with top and side impact protection. |
| Hearing protection | Noise, ultra-sound. | Hearing protectors (ear plugs or ear muffs). |
| Foot protection | Falling or rolling objects, pointed objects. Corrosive or hot liquids. | Safety shoes and boots for protection against moving & falling objects, liquids and chemicals. |
| Hand protection | Hazardous materials, cuts or lacerations, vibrations, extreme temperatures. | Gloves made of rubber or synthetic materials (Neoprene), leather, steel, insulating materials, etc. |
| Respiratory protection | Dust, fogs, fumes, mists, gases, smokes, vapors. | Facemasks with appropriate filters for dust removal and air purification (chemicals, mists, vapors and gases). Single or multi-gas personal monitors, if available. |
| | Oxygen deficiency | Portable or supplied air (fixed lines). On-site rescue equipment. |
| Body/leg protection | Extreme temperatures, hazardous materials, biological agents, cutting and laceration. | Insulating clothing, body suits, aprons etc. of appropriate materials. |

⁴ Source: IFC Environmental, Health, and Safety (EHS) Guidelines

Annexure vi: Chance Find Procedures


Chance finds procedures which will be used during this Project are as follows:

- Stop the construction activities in the area of the chance find;
- Delineate the discovered site or area;
- Secure the site to prevent any damage or loss of removable objects. In cases of removable antiquities or sensitive remains, a night guard shall be present until the responsible local authorities and the Ministry in charge of Department of Archaeology take over;
- Notify the supervisory Engineer who in turn will notify the responsible local authorities and the Ministry immediately (within 24 hours or less);
- Responsible local authorities and the Ministry in charge of Department of Archaeology would oversee protecting and preserving the site before deciding on subsequent appropriate procedures. This would require a preliminary evaluation of the findings to be performed by the archaeologists of the Department of Archaeology and Museums (within 72 hours). The significance and importance of the findings should be assessed according to the various criteria relevant to cultural heritage; those include the aesthetic, historic, scientific or research, social and economic values;
- Decisions on how to handle the finding shall be taken by the responsible authorities and the Ministry in charge of Department of Archaeology. This could include changes in the layout (such as when finding an irremovable remain of cultural or archaeological importance) conservation, preservation, restoration and salvage;
- Implementation for the authority decision concerning the management of the finding shall be communicated in writing by the Ministry in charge of Department of Archaeology; and
- Construction work could resume only after permission is given from the responsible local authorities and the Ministry in charge of Department of Archaeology concerning safeguard of the heritage.



These procedures will be referred to as standard provisions in construction contracts, when applicable. During project supervision, the Site Engineer will monitor the above regulations relating to the treatment of any chance find encountered are observed.

ANNEXURE - F

Drawings



Detailed Design of Infrastructure Sub- Projects Sectoral Planning & Resident Supervision in 16 cities of Punjab (Package-V – Okara)



Road Works Drawings

Improvement, Widening and Raising from Tank Chowk to Akbar Chowk along Canal Road (STA 0+00 TO STA 6+152)

October 22








General Drawings

LIST OF DRAWINGS

| S. No. | DWG. No. | DRAWING TITLE |
|-------------------------|---------------------------------|--|
| GENERAL DRAWINGS | | |
| 1. | MMP-1076P05-OKR-RD-GN-001 | LIST OF DRAWINGS |
| 2. | MMP-1076P05-OKR-RD-GN-002 | GENERAL NOTES |
| 3. | MMP-1076P05-OKR-RD-GN-003 | LOCATION PLAN |
| 4. | MMP-1076P05-OKR-RD-GN-004 | TYPICAL PAVEMENT MARKINGS |
| 5. | MMP-1076P05-OKR-RD-GN-005 | ARROW MARKINGS |
| 6. | MMP-1076P05-OKR-RD-GN-005a | TYPICAL CATEYE DETAIL |
| 7. | MMP-1076P05-OKR-RD-GN-005b | CATEGORY - 1 TYPICAL SIGN DETAILS |
| 8. | MMP-1076P05-OKR-RD-GN-006 | TYPICAL MANHOLE DETAIL |
| CANAL ROAD | | |
| 9. | MMP-1076P05-OKR-RD-GN-007 | CANAL ROAD TYPICAL CROSS SECTION (RD 0+000 TO 2+000) |
| 10. | MMP-1076P05-OKR-RD-GN-008 | CANAL ROAD TYPICAL CROSS SECTION (RD 2+000 TO 4+690) |
| 11. | MMP-1076P05-OKR-RD-GN-009 | CANAL ROAD TYPICAL CROSS SECTION (RD 4+690 TO 4+825) |
| 12. | MMP-1076P05-OKR-RD-GN-010 | CANAL ROAD TYPICAL CROSS SECTION (RD 4+825 TO 6+152) |
| 13. | MMP-1076P05-OKR-RD-GN-012 | CANAL ROAD LIST OF CONTROL POINTS |
| 14. | MMP-1076P05-OKR-RD-TP-001 ~ 003 | CANAL ROAD TOPOGRAPHIC SURVEY |
| 15. | MMP-1076P05-OKR-RD-P-001 ~ 005 | CANAL ROAD PLAN AND PROFILE (STA 0+000 TO STA 6+152) |
| 16. | MMP-1076P05-OKR-SL-GN-001 | SINGLE ARM POLE DETAIL |
| | MMP-1076P05-OKR-SL-GN-002 | DOUBLE ARM POLE DETAIL |
| 17. | MMP-1076P05-OKR-SL-GN-003 | SINGLE AND DOUBLE ARM POLE FOUNDATION |
| 18. | MMP-1076P05-OKR-SL-GN-004 | CANAL ROAD SLD AND CONTROL PANEL DETAIL |
| 19. | MMP-1076P05-OKR-SL-P-001 ~ 003 | CANAL ROAD STREET LIGHT PLAN |
| 20. | MMP-1076P05-OKR-RD-DR-001 ~ 003 | CANAL ROAD DRAINAGE PLAN |
| 21. | | |
| 22. | | |
| 23. | | |
| 24. | | |
| 25. | | |
| 26. | | |
| 27. | | |
| 28. | | |
| 29. | | |
| 30. | | |
| 31. | | |

| S. No. | DWG. No. | DRAWING TITLE |
|--------|----------|---------------|
| 32. | | |
| 33. | | |
| 34. | | |
| 35. | | |
| 36. | | |
| 37. | | |
| 38. | | |
| 39. | | |
| 40. | | |
| 41. | | |
| 42. | | |
| 43. | | |
| 44. | | |
| 45. | | |
| 46. | | |
| 47. | | |
| 48. | | |
| 49. | | |
| 50. | | |
| 51. | | |
| 52. | | |
| 53. | | |
| 54. | | |
| 55. | | |
| 56. | | |
| 57. | | |
| 58. | | |
| 59. | | |
| 60. | | |
| 61. | | |
| 62. | | |
| 63. | | |

| | | | | | | | | | | |
|---|--|--|------|------------|-------------|---------|----------|---|-------------------|-------------|
| Consultants  CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292528 mmpdcc@mmpakistan.com http://www.mmpakistan.com | Client  GOVERNMENT OF PUNJAB  Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title LIST OF DRAWINGS Drawing No. MMP-1076P05-OKR-RD-GN-001 | Designed | M. Abdullah |
| | | | 0 | 24-10-2022 | | SA | PHK | | Drawn | M. Tayyab |
| | | | | | | | | Checked | Sajjad Anwar | |
| | | | | | | | | Approved | Pervez Hayat Khan | |
| | | | | | | | | Scale | AS SHOWN | |
| | | | | | | | | Rev No: | 0 | |

GENERAL NOTES:

- EXCEPT WHEN OTHERWISE INDICATED, ALL DIMENSIONS AND UNITS ARE IN THE IMPERIAL SYSTEM OF MEASUREMENT.
- ALL COORDINATES ARE MEASURED IN FEET AND CORRESPOND TO THE GIRD REFERENCE OF UNIVERSAL TRANSVERSE MERCATOR.
- ALL ELEVATIONS ARE REFERENCED TO MEAN SEA LEVEL.
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE LOCATION OF ALL UTILITIES OR AS OTHERWISE ENCOUNTERED DURING EXCAVATION PROCESS. ANY DAMAGE TO UTILITIES WILL BE RESTORED AT HIS OWN COST.
- BEFORE COMMENCEMENT OF WORK, CONTRACTOR SHALL VERIFY THE EXISTING ELEVATION SHOWN IN TENDER DRAWINGS ALONG WITH THE ENGINEER'S REPRESENTATIVE.
- ANY DISCREPANCIES ON DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF ENGINEER FOR THE CLARIFICATION BEFORE PROCEEDING WITH THE WORK INVOLVED.
- THE TENDERER SHOULD VISIT THE SITE AND ASSESS SCOPE AND NATURE OF THE WORKS SPECIALLY DISMANTLING ITEMS AND GET INFORMATION/ MEASUREMENTS AT HIS OWN AND SATISFY HIMSELF BEFORE QUOTING RATES.
- THE DEMOLISHED MATERIAL WILL BE HANDED OVER TO THE CONCERNED DEPARTMENT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- THE PROPOSED DESIGN OF PAVEMENT IS A TENTATIVE DESIGN AND IT IS BASED ON ASSUMED VALUE OF CBR 5%. HOWEVER AT CONSTRUCTION STAGE IS RECOMMENDED THAT CLIENT MAY PROVIDE THE GEOTECHNICAL INVESTIGATION REPORT AND DESIGN WILL BE REVISED ACCORDINGLY AS PER OUR TOR.
- THE GEOMETRIC DESIGN IS BASED ON THE TOPOGRAPHIC SURVEY. HOWEVER, AT CONSTRUCTION STAGE, IT IS RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE SURVEY AND ANY DISCREPANCY IF FOUND SHALL BE CORRECTED AND DESIGN MAY BE REVISED ACCORDINGLY.
- ALL PROFILE DRAWINGS SHALL BE READ IN CONJUNCTION WITH RELEVANT PLAN AND CROSS SECTIONAL DRAWINGS.
- ALL EXISTING STRUCTURES/UTILITY POLES, WHICH LIE IN THE PROPOSED CROSS SECTION, ARE REQUIRED TO BE DEMOLISHED/RELOCATED BY THE CONTRACTOR COORDINATION WITH THE CONCERNED UTILITY DEPARTMENT OR AS DIRECTED BY THE ENGINEER
- PAVEMENT WIDENING SHALL BE REQUIRED WHERE EXISTING PAVEMENT WIDTH IS LESS THAN THE WIDTH SHOWN ON THE TYPICAL CROSS SECTION OR SHOWN ELSEWHERE ON THE DRAWINGS.
- ALL DEFECTIVE PORTIONS OF SUB-GRADE/GANULAR SUB BASE COURSE FAILURE OF THE EXISTING PAVEMENT AS DETERMINED BY THE ENGINEER SHALL BE REMOVED AND RELAYED AS PER DRAWINGS AND SPECIFICATIONS OR AS DIRECTED BY THE ENGINEER.
- THE EXISTING MANHOLES LYING BELOW THE FINAL DESIGN LEVELS ARE REQUIRED TO BE RAISED AND MATCHED WITH FINAL DESIGN ELEVATION.
- ACCESS TO RESIDENTIAL AREAS WITHIN THE CONSTRUCTION ZONE SHALL NOT BE BLOCKED BY THE CONTRACTOR AT ANY TIME ALL EXISTING ACCESSES WILL BE RETAINED.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY TRAFFIC DIVERSIONS ON THE ROAD, CONSTRUCTION OF DETOUR, MAINTENANCE, SPRINKLING OF WATER, GRADING AND COMPACTION, TRAFFIC SAFETY DEVICES, BEACON LIGHTS WHEN AND WHERE REQUIRED, OR AS DIRECTED BY THE ENGINEER.
- GENERAL SPECIFICATIONS TO BE USED SHALL BE THE LATEST AVAILABLE EDITION OF **STANDARD SPECIFICATIONS FOR ROAD & BRIDGE CONSTRUCTION** PUBLISHED BY PUNJAB COMMUNICATION AND WORKS DEPARTMENT
- CLEANING AND MAINTENANCE OF GULLY GRATING CHAMBER IS THE RESPONSIBILITY OF MUNICIPAL COMMITTEE.
- GULLY GRATING CHAMBER ARE PROVIDED DUE TO ABSENCE OF DEDICATED INFRASTRUCTURE FOR SURFACE RUNOFF.

ABBREVIATIONS

| HORIZONTAL / VERTICAL CURVES | | |
|------------------------------|--|--------|
| S.NO. | DESCRIPTION | SYMBOL |
| 1 | STATION | STA |
| 2 | POINT OF INTERSECTION | PI |
| 3 | EASTING | E |
| 4 | NORTHING | N |
| 5 | ANGLE OF DEFLECTION | d |
| 6 | RADIUS | R |
| 7 | LENGTH OF TANGENT | T |
| 8 | LENGTH OF CIRCULAR CURVE | LC |
| 9 | EXTERNAL ORDINATE | E |
| 10 | DEGREE OF CURVE | D |
| 11 | RATE OF SUPER ELEVATION | SE |
| 12 | POINT OF COMMENCEMENT (CIRCULAR CURVE) | PC |
| 13 | POINT OF TERMINATION (CIRCULAR CURVE) | PT |
| 14 | VERTICAL POINT OF INTERSECTION | VPI |
| 15 | ELEVATION | EL |
| 16 | LENGTH OF HORIZONTAL/VERTICAL CURVE | L |
| 17 | MIDDLE ORDINATE | M |
| 18 | NORMAL CROSSFALL | NC |
| 19 | REVERSE CROWN | RC |
| 20 | SUPER ELEVATION RUNOFF | SR |
| 21 | TANGENT RUNOUT | TR |
| 22 | POINT OF COMPOUND CURVATURE | PCC |
| 23 | POINT OF REVERSE CURVE | PRC |
| 24 | VERTICAL POINT OF CURVATURE | VPC |
| 25 | VERTICAL POINT OF TANGENCY | VPT |
| 26 | VERTICAL GRADIENT | G |

LEGEND


| | | | | | | | |
|--------------------------------|--|------------|--|----------------|--|---------------------|------------|
| PROPOSED CENTERLINE | | BUILDING | | CENTER LINE | | TUBEWELL | |
| FRL | | CANAL | | ELECTRIC POLE | | MANHOLE | |
| NSL | | DRAIN | | PYLON | | SIGN BOARD | |
| EDGE OF TRAVELWAY | | ROAD | | LIGHT POLE | | HAND PUMP | |
| LANE | | TRACK | | TREE | | OPTICAL FIBER CABLE | |
| EDGE OF PAVED SHOULDER | | PCC | | RAILWAY LINE | | MOSQUE | |
| PROPOSED CARRIAGEWAY | | TUFF TILE | | TELEPHONE POLE | | ELEVATION | EL=210.256 |
| PROPOSED PAVERS | | FENCE | | FOOT PATH | | GRAVEYARD | |
| PROPOSED GULLY GRATING CHAMBER | | GREEN BELT | | KARB STONE | | | |

MISCELLANEOUS

| S.NO. | DESCRIPTION | SYMBOL |
|-------|-----------------------|--------|
| 1. | MAXIMUM | MAX. |
| 2. | MINIMUM | MIN. |
| 3. | FINISHED ROAD LEVEL | FRL |
| 4. | NATURAL SURFACE LEVEL | NSL |
| 5. | HIGH FLOOD LEVEL | HFL |
| 6. | SHOULDER | SHLDR |

| | | | | | | | | | | |
|--|--|--|------|------------|-------------|---------|----------|--|-------------------|-------------|
| Consultants CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292528 mmpdc@mmppakistan.com http://www.mmpakistan.com | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | GENERAL NOTES Drawing No. MMP-1076P05-OKR-RD-GN-002 | Designed | M. Abdullah |
| | | | 0 | 11-10-2022 | | SA | PHK | | Drawn | M. Tayyab |
| | | | | | | | | Checked | Sajjad Anwar | |
| | | | | | | | | Approved | Pervez Hayat Khan | |
| | | | | | | | | Scale | AS SHOWN | |
| | | | | | | | | Rev No: | 0 | |

Okara City Road Projects




| Sr.No. | Project Title |
|--------|---|
| 1 | Improvement, Widening and Raising from Tank Chowk to Akbar Chowk along Canal Road |

| Legend | |
|--------|--------------------------|
| NAME | |
| | Proposed Canal Road |
| | Canal |
| | Existing Primary Roads |
| | Existing Secondary Roads |
| | Railway Line |
| | MC Boundary PLGA 2319 |

Drawing file path & name: F:\PMDFC\Package_V_Roads_P&P\Okara Roads\4. LP\LP.dwg
User and Plot Date: Tayyab - Fri, 21 Oct 2022 3:18pm

| | | | | | | | | | | | |
|--|--|--|------|------------|-------------|---------|----------|-------------|---------------------------|----------|-------------------|
| Consultants CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292528 mmpdce@mmpakistan.com http://www.mmpakistan.com | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title | LOCATION PLAN | Designed | M. Abdullah |
| | | | 0 | 21-10-2022 | | SA | PHK | | | Drawn | M. Tayyab |
| | | | | | | | | Checked | Sajjad Anwar | Approved | Pervez Hayat Khan |
| | | | | | | | | Scale | AS SHOWN | Rev No: | 0 |
| | | | | | | | | Drawing No. | MMP-1076P05-OKR-RD-GN-003 | | |

© MM Pakistan
This document should not be relied on or used in circumstances other than those for which it was originally prepared and for which MMP was commissioned. MMP accepts no responsibility for this document to any other party other than the person by whom it was commissioned.




- NOTES:-**
1. ALL DIMENSIONS ARE IN INCHES UNLESS SHOWN OTHERWISE.
 2. CAT EYES TO BE PROVIDED AT 36' C/C ON EDGES AND CENTERLINE OR AS DIRECTED BY THE ENGINEER

TYPICAL PAVEMENT MARKING



L2- CONTINUOUS LINE (WHITE)

AT CENTERLINE OF HIGHWAY WHERE OVERTAKING PROHIBITED




L1- BROKEN GUIDE LINE (WHITE)

AT CENTERLINE OF HIGHWAY




L4- CONTINUOUS LINE (YELLOW)

AT EDGE OF PAVEMENT



L3- DASHED LINE (WHITE)

CONTINUITY LINE






L5- DASHED LINE (YELLOW)

AT EDGE OF PAVEMENT AT MINOR CROSSING




| | | | | | | | | | | |
|---|--|---|------|------------|-------------|---------|----------|---|-------------------|-------------|
| Consultants CENTRAL DESIGN CELL 2nd Floor, CT1 Building, 27-Empress Road, Lahore 042-36292528 mmpdc@mmpakistan.com http://www.mmpakistan.com | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title TYPICAL PAVEMENT MARKINGS Drawing No. MMP-1076P05-OKR-RD-GN-004 | Designed | M. Abdullah |
| | | | 0 | 29-09-2022 | | SA | PHK | | Drawn | M. Tayyab |
| | | | | | | | | Checked | Sajjad Anwar | |
| | | | | | | | | Approved | Pervez Hayat Khan | |
| | | | | | | | | Scale | AS SHOWN | |
| | | | | | | | | Rev No: | 0 | |


Drawing file path & name: F:\PMDFC\Package_V_Roads_P&P\Okara Roads\7. Typical Pavement marking details\Typical Pavement Marking details (ft).dwg
 User and Plot Date: Tayyab - Thu, 29 Sep 2022 - 6:11pm



ARROWS FOR PAVEMENT MARKING

NOTES:-
1. ALL DIMENSIONS ARE IN INCHES UNLESS SHOWN OTHERWISE.

| | | | | | | | | | | | |
|---|--|---|------|------------|-------------|---------|----------|--------------------------------|---------------------------|-------------|---|
| Consultants  CENTRAL DESIGN CELL 2nd Floor, CT1 Building, 27-Empress Road, Lahore 042-36292525-7 mmpdcd@mmpakistan.com http://www.mmpakistan.com | Client  GOVERNMENT OF PUNJAB  Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title ARROW MARKINGS | Designed | M. Abdullah | |
| | | | 0 | 29-09-2022 | | SA | PHK | | Drawn | M. Tayyab | |
| | | | | | | | | Checked | Sajjad Anwar | | |
| | | | | | | | | Approved | Pervez Hayat Khan | | |
| | | | | | | | | Scale | AS SHOWN | | |
| | | | | | | | | Drawing No. | MMP-1076P05-OKR-RD-GN-005 | Rev No: | 0 |




NOTE:-
DIMENSIONS SHOWN ARE INDICATIVE ONLY AND NOT NECESSARILY
BE FOLLOWED. HOWEVER ACTUAL DIMENSIONS SHALL BE GIVEN BY
MANUFACTURER/SUPPLIER

NOTES:-
1. ALL DIMENSIONS ARE IN MILLIMETER UNLESS SHOWN OTHERWISE.
2. CATEYE SPACING 30 FEET C/C

| | | | | | | | | | | |
|---|--|---|------|------------|-------------|---------|----------|--|----------|-------------------|
| Consultants CENTRAL DESIGN CELL 2nd Floor, CT1 Building, 27-Empress Road, Lahore 042-36292525-7 mmpdccc@mmpakistan.com http://www.mmpakistan.com | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title TYPICAL CATEYE DETAIL Drawing No. MMP-1076P05-OKR-RD-GN-005a | Designed | M. Abdullah |
| | | | 0 | 11-10-2022 | | SA | PHK | | Drawn | M. Tayyab |
| | | | | | | | | | Checked | Sajjad Anwar |
| | | | | | | | | | Approved | Pervez Hayat Khan |
| | | | | | | | | | Scale | AS SHOWN |
| | | | | | | | | Rev No: | 0 | |


Drawing file path & name: C:\Users\Tayyab\AppData\Local\Temp\AcPublish_2780\Typical Pavement Marking details (ft).dwg
User and Plot Date: Tayyab -- Tue, 11 Oct 2022 -- 11:50am



PEDESTRIAN CROSSING SIGN (W-11)

DIMENSION (mm)


| PARTS | SIGN SIZE | | |
|-------|-----------|-------|-------|
| | 90mm | 105mm | 120mm |
| a | 3.5 | 4.1 | - |
| b | 1.8 | 1.3 | - |
| b | 6.5 | 7.6 | - |
| c | 2.5 | 2.9 | - |
| e | 43.0 | 52.2 | - |
| e | 25.0 | 26.8 | - |



CHILDREN CROSSING SIGN (W-16)

DIMENSION (mm)


| PARTS | SIGN SIZE | | |
|-------|-----------|-------|-------|
| | 90mm | 105mm | 120mm |
| a | 3.5 | 4.1 | - |
| b | 1.8 | 1.3 | - |
| b | 6.5 | 7.6 | - |
| c | 4.5 | 5.3 | - |
| e | 28.5 | 33.3 | - |
| e | 17.5 | 43.8 | - |



TWO WAY TRAFFIC AHEAD (W-20)

DIMENSION (mm)

| PARTS | SIGN SIZE | | |
|-------|-----------|-------|-------|
| | 90mm | 105mm | 120mm |
| a | 3.5 | 4.1 | 4.7 |
| b | 1.8 | 1.2 | 1.3 |
| b | 6.5 | 7.6 | 8.7 |
| c | 4.5 | 4.7 | 5.3 |
| d | 9.0 | 10.5 | 12.0 |
| e | 18.0 | 22.2 | 25.3 |
| f | 5.0 | 5.8 | 6.7 |
| g | 3.5 | 4.1 | 4.7 |



MINOR ROAD CROSSING AT RIGHT ANGLE (W-21)




DIMENSION (mm)

| PARTS | SIGN SIZE | | |
|-------|-----------|-------|-------|
| | 90mm | 105mm | 120mm |
| a | 3.5 | 4.1 | 4.7 |
| b | 1.0 | 1.2 | 1.3 |
| b | 6.5 | 7.6 | 8.7 |
| c | 4.0 | 4.7 | 5.3 |
| d | 15.0 | 17.5 | 20.0 |
| e | 6.0 | 7.0 | 8.0 |
| f | 11.0 | 12.8 | 14.7 |
| g | 13.5 | 15.7 | 18.0 |
| h | 8.5 | 9.9 | 11.3 |



- NOTES:
1. ALL DIMENSIONS ARE IN CENTIMETERS UNLESS OTHERWISE SPECIFIED
 2. THE 90 cm SIGNS WILL BE USED
 3. ALL SIGNS HAVE WHITE BACKGROUND WITH BLACK WRITING / MARKINGS AND RED BORDER
 4. ALL SHEETING IS OF HIGH INTENSITY PRISMATIC REFLECTIVE SHEET FOR SIGNS.
 5. SIGN BOARD SHOULD BE PLACED 2 ft FROM EDGE OF SHOULDER, WITH 10 ft POLE.
 6. FOR TRAFFIC SAFETY NO FIX STRUCTURE/POLE/TREE SHOULD BE PRESENT WITHIN 2 ft OF EDGE OF ROADWAY.

Drawing file path & name: F:\PMDFC\Package_V_Roads_P&P\Okara Roads\7.1. Typical Road Signs\Typical Road Signs.dwg
User and Plot Date: Tayyab -- Tue, 11 Oct 2022 -- 11:50am

| | | | | | | | | | | |
|--|--|---|------|------------|-------------|---------|----------|--|----------------------------|-------------|
| Consultants CENTRAL DESIGN CELL 2nd Floor, CT1 Building, 27-Empress Road, Lahore 042-36292525-7 mmpdcd@mmpakistan.com http://www.mmpakistan.com | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title CATEGORY - 1 TYPICAL SIGN DETAILS | Designed | M. Abdullah |
| | | | 0 | 11-10-2022 | | SA | PHK | | Drawn | M. Tayyab |
| | | | | | | | | Checked | Sajjad Anwar | |
| | | | | | | | | Approved | Pervez Hayat Khan | |
| | | | | | | | | Scale | AS SHOWN | |
| | | | | | | | | Drawing No. | MMP-1076P05-OKR-RD-GN-005b | |
| | | | | | | | | Rev No: | 0 | |



TYPICAL KERB STONE DETAIL A



NOTES:-

1. ALL DIMENSIONS ARE IN FEET UNLESS SHOWN OTHERWISE.
2. TYPICAL KERB DETAIL B TO BE PROVIDED WHERE EXISTING DRIVEWAY IS PRESENT OR AS DIRECTED BY THE ENGINEER.


| | | | | | | | | | | |
|---|--|---|------|-----------|-------------|---------|----------|---------------------------------|---------------------------|-------------|
| Consultants CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292528 mmpdccc@mmpakistan.com http://www.mmpakistan.com | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title TYPICAL MANHOLE DETAIL | Designed | M. Abdullah |
| | | | 0 | 2-12-2022 | | SA | PHK | | Drawn | M.Tayyab |
| | | | | | | | | Checked | Sajjad Anwar | |
| | | | | | | | | Approved | Pervez Hayat Khan | |
| | | | | | | | | Scale | AS SHOWN | |
| | | | | | | | | Drawing No. | MMP-1076P05-OKR-RD-GN-006 | |
| | | | | | | | | Rev No: | 0 | |
| | | | | | | | | Status | PRE | |





ہمدیوے فوگے گے بے



PROPOSED ROAD SECTION



EXISTING ROAD SECTION



TYPICAL ROADWAY SECTION
(0+000 TO 2+000)
SCALE 1/4"=1'-0"

NOTES:-


1. ALL DIMENSIONS ARE IN FEET EXCEPT SHOWN OTHERWISE.
2. EXISTING TST SHALL BE REMOVED.
3. EXISTING ROAD BASE WILL BE ADJUSTED ACCORDING TO PROFILE LEVEL.
4. DRAINAGE SLOPE SHALL BE REWORK DURING SURFACE PREPARATION.
5. EXISTING LEVEL AT THE CROSSINGS / INTERSECTIONS SHALL BE MATCHED AS PER SITE CONDITION OR AS DIRECTED BY THE ENGINEER.
6. TWO CURB STONES WILL BE REMOVED EVERY 50 FT TO ALLOW FOR SURFACE DRAINAGE.

| | | | | | | | | | | | |
|--|--|---|------|-----------|-------------|---------|----------|--|-------------------|-------------|-----|
| Consultants CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292528 mmpdce@mmpakistan.com http://www.mmpakistan.com | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title CANAL ROAD TYPICAL CROSS SECTION (0+000 TO 2+000) Drawing No. MMP-1076P05-OKR-RD-GN-007 | Designed | M. Abdullah | |
| | | | 0 | 2-11-2022 | | SA | PHK | | Drawn | M.Tayyab | |
| | | | | | | | | Checked | Sajjad Anwar | | |
| | | | | | | | | Approved | Pervez Hayat Khan | | |
| | | | | | | | | Scale | AS SHOWN | | |
| | | | | | | | | Rev No: | 0 | Status | PRE |



Drawing file path & name: F:\PMDFC\Package_V_Roads_P&P\Okara Roads\6. Typical Cross Sections\Okara Roads Typical Cross Sections and Drain.dwg
 User and Plot Date: Tayyab - Wed, 02 Nov 2022 - 11:25pm

© MM Pakistan
 This document should not be relied on or used in circumstances other than those for which it was originally prepared and for which MMP was commissioned. MMP accepts no responsibility for this document to any other party other than the person by whom it was commissioned.

PROPOSED ROAD SECTION



EXISTING ROAD SECTION



TYPICAL ROADWAY SECTION
(2+000 TO 4+690)
SCALE 1/4"=1'-0"

NOTES:-


1. ALL DIMENSIONS ARE IN FEET EXCEPT SHOWN OTHERWISE.
2. EXISTING TST SHALL BE REMOVED.
3. EXISTING ROAD BASE WILL BE ADJUSTED ACCORDING TO PROFILE LEVEL.
4. DRAINAGE SLOPE SHALL BE REWORK DURING SURFACE PREPARATION.
5. EXISTING LEVEL AT THE CROSSINGS / INTERSECTIONS SHALL BE MATCHED AS PER SITE CONDITION OR AS DIRECTED BY THE ENGINEER.
6. TWO CURB STONES WILL BE REMOVED EVERY 50 FT TO ALLOW FOR SURFACE DRAINAGE.

| | | | | | | | | | | |
|---|--|--|------|-----------|-------------|---------|----------|---|---------------------------|-------------|
| Consultants CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292528 mmpdce@mmpakistan.com http://www.mmpakistan.com | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK | Rev. | Date | Description | Checked | Approved | Title CANAL ROAD TYPICAL CROSS SECTION (2+000 TO 4+690) | Designed | M. Abdullah |
| | | | 0 | 2-11-2022 | | SA | PHK | | Drawn | M.Tayyab |
| Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | | | | | | | | Checked | Sajjad Anwar | |
| | | | | | | | | Approved | Pervez Hayat Khan | |
| | | | | | | | | Scale | AS SHOWN | |
| | | | | | | | | Drawing No. | MMP-1076P05-OKR-RD-GN-008 | |
| | | | | | | | | Rev No: | 0 | |
| | | | | | | | | Status | PRE | |



Drawing file path & name: F:\PMDFC\Package_V_Roads_P&P\Okara Roads\Typical Cross Sections and Drain.dwg
 User and Plot Date: Tayyab - Wed, 02 Nov 2022 - 11:25pm

© MM Pakistan
 This document should not be relied on or used in circumstances other than those for which it was originally prepared and for which MMP was commissioned. MMP accepts no responsibility for this document to any other party other than the person by whom it was commissioned.

PROPOSED ROAD SECTION



EXISTING ROAD SECTION




TYPICAL ROADWAY SECTION
(4+690 TO 4+825)
SCALE 1/4"=1'-0"

NOTES:-



1. ALL DIMENSIONS ARE IN FEET EXCEPT SHOWN OTHERWISE.
2. EXISTING TST SHALL BE REMOVED.
3. EXISTING ROAD BASE WILL BE ADJUSTED ACCORDING TO PROFILE LEVEL.
4. DRAINAGE SLOPE SHALL BE REWORK DURING SURFACE PREPARATION.
5. EXISTING LEVEL AT THE CROSSINGS / INTERSECTIONS SHALL BE MATCHED AS PER SITE CONDITION OR AS DIRECTED BY THE ENGINEER.
6. TWO CURB STONES WILL BE REMOVED EVERY 50 FT TO ALLOW FOR SURFACE DRAINAGE.

| | | | | | | | | | | | |
|--|--|---|------|-----------|-------------|---------|----------|---|-------------------|-------------|-----|
| Consultants CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292528-7 042-36292528 mmpdce@mmpakistan.com http://www.mmpakistan.com | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title CANAL ROAD TYPICAL CROSS SECTION (4+690 TO 4+825) Drawing No. MMP-1076P05-OKR-RD-GN-009 | Designed | M. Abdullah | |
| | | | 0 | 2-11-2022 | | SA | PHK | | Drawn | M.Tayyab | |
| | | | | | | | | Checked | Sajjad Anwar | | |
| | | | | | | | | Approved | Pervez Hayat Khan | | |
| | | | | | | | | Scale | AS SHOWN | | |
| | | | | | | | | Rev No: | 0 | Status | PRE |

PROPOSED ROAD SECTION



EXISTING ROAD SECTION



TYPICAL ROADWAY SECTION
(4+825 TO 6+152)
SCALE 1/4"=1'-0"

NOTES:-

1. ALL DIMENSIONS ARE IN FEET EXCEPT SHOWN OTHERWISE.
2. EXISTING TST SHALL BE REMOVED.
3. EXISTING ROAD BASE WILL BE ADJUSTED ACCORDING TO PROFILE LEVEL.
4. DRAINAGE SLOPE SHALL BE REWORK DURING SURFACE PREPARATION.
5. EXISTING LEVEL AT THE CROSSINGS / INTERSECTIONS SHALL BE MATCHED AS PER SITE CONDITION OR AS DIRECTED BY THE ENGINEER.
6. TWO CURB STONES WILL BE REMOVED EVERY 50 FT TO ALLOW FOR SURFACE DRAINAGE.

| | | | | | | | | | | | |
|--|--|---|------|-----------|-------------|---------|----------|---|-------------------|-------------|-----|
| Consultants CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292525-7 042-36292528 mmpdce@mmpakistan.com http://www.mmpakistan.com | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title CANAL ROAD TYPICAL CROSS SECTION (4+825 TO 6+152) Drawing No. MMP-1076P05-OKR-RD-GN-010 | Designed | M. Abdullah | |
| | | | 0 | 2-11-2022 | | SA | PHK | | Drawn | M.Tayyab | |
| | | | | | | | | Checked | Sajjad Anwar | | |
| | | | | | | | | Approved | Pervez Hayat Khan | | |
| | | | | | | | | Scale | AS SHOWN | | |
| | | | | | | | | Rev No: | 0 | Status | PRE |




Topographic Survey

OK1
N:11190473.13
E:1145643.45
Z: 579.99

OK2
N:11190252.91
E:1145439.05
Z: 589.11



| List of Control Points | | | | |
|------------------------|-------------|------------|-----------|-------------|
| Point | Northing | Easting | Elevation | Description |
| 1 | 11190473.13 | 1145643.45 | 579.99 | OK1 |
| 2 | 11190252.91 | 1145439.05 | 589.11 | OK2 |
| 11 | 11183323.21 | 1147505.68 | 594.21 | OK 18 |
| 12 | 11183470.54 | 1147651.58 | 593.18 | OK 19 |



Consultants



CENTRAL DESIGN CELL
2nd Floor, CTI Building,
27-Empress Road, Lahore
042-36292525-7
042-36292528
mmpdccc@mmpakistan.com
http://www.mmpakistan.com

Client



GOVERNMENT OF PUNJAB



Punjab Municipal Development
Fund Company
Department (PMDFC)

Financing Agency

WORLD BANK

Project


Punjab Cities Program (PCP)
Detailed Design of Infrastructure
Sub-Projects, Sectoral Planning & Resident
Supervision in 16 Cities of Punjab(Package-5)




| Rev. | Date | Description | Checked | Approved |
|------|------------|-------------|---------|----------|
| 0 | 30-09-2022 | | SA | SA |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

| Title | |
|-----------------------------------|---------------------------|
| CANAL ROAD LIST OF CONTROL POINTS | |
| Drawing No. | MMP-1076P05-OKR-RD-GN-012 |

| | |
|----------|--------------|
| Designed | M. Abdullah |
| Drawn | M. Tayyab |
| Checked | Sajjad Anwar |
| Approved | Sajjad Anwar |
| Scale | 1" : 500' |
| Rev No: | 0 |


Drawing file path & name: F:\PMDFC\Package_V_Roads_P&P\Okara Roads\13. Topographic Survey\Okara Canal Road Topographic Sheets.dwg
User and Plot Date: Tayyab - Fri, 30 Sep 2022 - 6:21pm








| | | | | | | | | | | |
|--|--|---|------|------------|-------------|---------|----------|---|--------------|-------------|
| Consultants  CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292528 mmpdccc@mmpakistan.com http://www.mmpakistan.com | Client  GOVERNMENT OF PUNJAB  Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title CANAL ROAD TOPOGRAPHIC SURVEY Drawing No. MMP-1076P05-OKR-RD-TP-001 | Designed | M. Abdullah |
| | | | 0 | 30-09-2022 | | SA | SA | | Drawn | M. Tayyab |
| | | | | | | | | Checked | Sajjad Anwar | |
| | | | | | | | | Approved | Sajjad Anwar | |
| | | | | | | | | Scale | 1" : 100' | |
| | | | | | | | | Rev No: | 0 | |

© MM Pakistan
This document should not be relied on or used in circumstances other than those for which it was originally prepared and for which MMP was commissioned. MMP accepts no responsibility for this document to any other party other than the person by whom it was commissioned.

Drawing file path & name: F:\PMDFC\Package_V_Roads_P&P\Okara Roads\13. Topographic Survey\Okara Canal Road Topographic Sheets.dwg
User and Plot Date: Tayyab - Fri, 30 Sep 2022 - 6:21 pm



| | | | | | | | | | | |
|--|--|---|------|------------|-------------|---------|----------|---|--------------|-------------|
| Consultants  CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292528 mmpdccc@mmpakistan.com http://www.mmpakistan.com | Client  GOVERNMENT OF PUNJAB  Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title CANAL ROAD TOPOGRAPHIC SURVEY Drawing No. MMP-1076P05-OKR-RD-TP-002 | Designed | M. Abdullah |
| | | | 0 | 30-09-2022 | | SA | SA | | Drawn | M. Tayyab |
| | | | | | | | | Checked | Sajjad Anwar | |
| | | | | | | | | Approved | Sajjad Anwar | |
| | | | | | | | | Scale | 1" : 100' | |
| | | | | | | | | Rev No: | 0 | |




Consultants




MMP

CENTRAL DESIGN CELL
2nd Floor, CTI Building,
27-Empress Road, Lahore
042-36292528
mmpdcc@mmpakistan.com
http://www.mmpakistan.com

Client



GOVERNMENT OF PUNJAB



Punjab Municipal Development
Fund Company
Department (PMDFC)

Financing Agency

WORLD BANK

Project

Punjab Cities Program (PCP)
Detailed Design of Infrastructure
Sub-Projects, Sectoral Planning & Resident
Supervision in 16 Cities of Punjab(Package-5)

| Rev. | Date | Description | Checked | Approved |
|------|------------|-------------|---------|----------|
| 0 | 30-09-2022 | | SA | SA |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Title

CANAL ROAD TOPOGRAPHIC SURVEY

Drawing No.


MMP-1076P05-OKR-RD-TP-003

| | |
|----------|--------------|
| Designed | M. Abdullah |
| Drawn | M. Tayyab |
| Checked | Sajjad Anwar |
| Approved | Sajjad Anwar |
| Scale | 1" : 100' |
| Rev No: | 0 |

Drawing file path & name: F:\PMDFC\Package_V_Roads_P&P\Okara Roads\13. Topographic Survey\Okara Canal Road Topographic Sheets.dwg
User and Plot Date: Tayyab - Fri, 30 Sep 2022 - 6:21pm




Plan and Profile Drawings



LEGEND

| | | | |
|---------------------|--|------------------------|--|
| PROPOSED CENTERLINE | | EDGE OF PAVED SHOULDER | |
| EDGE OF TRAVELWAY | | PROPOSED CARRIAGEWAY | |
| LANE | | | |



| Station | 0+050 | 0+100 | 0+150 | 0+200 | 0+250 | 0+300 | 0+350 | 0+400 | 0+450 | 0+500 | 0+550 | 0+600 | 0+650 | 0+700 | 0+750 | 0+800 | 0+850 | 0+900 | 0+950 | 1+000 | 1+050 | 1+100 | 1+150 | 1+200 | 1+250 | | | |
|---------------------|------------|--------|-------------------------|--------|--------|-------------------------|--------|------------|--------|--------|--------|--------|--------|--------|--------|--------|--------------------------|--------|--------|-------------|--------|--------|--------|--------|--------|--|--|--|
| FRL | 592.10 | 592.20 | 592.17 | 592.02 | 591.83 | 591.74 | 591.73 | 591.78 | 591.83 | 591.88 | 591.93 | 591.98 | 592.03 | 592.08 | 592.13 | 592.18 | 592.23 | 592.27 | 592.29 | 592.29 | 592.30 | 592.30 | 592.31 | 592.31 | 592.32 | | | |
| NSL | 591.67 | 591.57 | 591.59 | 591.53 | 591.34 | 591.34 | 591.43 | 591.57 | 591.49 | 591.36 | 591.19 | 591.19 | 591.19 | 591.19 | 591.20 | 591.30 | 591.40 | 591.32 | 591.34 | 591.44 | 591.49 | 591.47 | 591.55 | 591.61 | 591.72 | | | |
| Level Difference | 0.42 | 0.62 | 0.58 | 0.49 | 0.50 | 0.40 | 0.30 | 0.21 | 0.34 | 0.53 | 0.75 | 0.80 | 0.84 | 0.90 | 0.94 | 0.88 | 0.83 | 0.95 | 0.95 | 0.85 | 0.81 | 0.83 | 0.76 | 0.70 | 0.60 | | | |
| Horizontal Geometry | L=4531.56' | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Vertical Geometry | L= 54.63' | | L= 150.00' K= 198.95 | | | L= 150.00' K= 272.73 | | L= 470.21' | | | | | | | | | L= 150.00' K= 1666.67 | | | L= 3845.36' | | | | | | | | |
| Superelevation | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

Consultants



Client



Financing Agency

WORLD BANK


Project

Punjab Cities Program (PCP)
Detailed Design of Infrastructure
Sub-Projects, Sectoral Planning & Resident
Supervision in 16 Cities of Punjab(Package-5)

| Rev. | Date | Description | Checked | Approved |
|------|-----------|-------------|---------|----------|
| 0 | 2-11-2022 | | SA | PHK |


| Title | |
|--|---------------------------|
| CANAL ROAD PLAN AND PROFILE (STA 0+000.00 TO STA 1+260.00) | |
| Drawing No. | MMP-1076P05-OKR-RD-PP-001 |

| | |
|----------|--------------------------|
| Designed | M. Abdullah |
| Drawn | M. Tayyab |
| Checked | Sajjad Anwar |
| Approved | Pervez Hayat Khan |
| Scale | H= 1" : 100' V= 1" : 10' |
| Rev No: | 0 |



LEGEND


| | | | |
|---------------------|--|------------------------|--|
| PROPOSED CENTERLINE | | EDGE OF PAVED SHOULDER | |
| EDGE OF TRAVELWAY | | PROPOSED CARRIAGEWAY | |
| LANE | | | |



| Station | 1+300 | 1+350 | 1+400 | 1+450 | 1+500 | 1+550 | 1+600 | 1+650 | 1+700 | 1+750 | 1+800 | 1+850 | 1+900 | 1+950 | 2+000 | 2+050 | 2+100 | 2+150 | 2+200 | 2+250 | 2+300 | 2+350 | 2+400 | 2+450 | 2+500 |
|---------------------|------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| FRL | 592.32 | 592.33 | 592.33 | 592.34 | 592.34 | 592.35 | 592.35 | 592.36 | 592.36 | 592.37 | 592.37 | 592.38 | 592.39 | 592.39 | 592.40 | 592.40 | 592.41 | 592.41 | 592.42 | 592.42 | 592.43 | 592.43 | 592.44 | 592.44 | 592.44 |
| NSL | 591.83 | 591.86 | 591.83 | 591.83 | 591.82 | 591.77 | 591.68 | 591.67 | 591.78 | 591.90 | 591.86 | 591.79 | 591.71 | 591.62 | 591.53 | 591.47 | 591.63 | 591.80 | 591.96 | 591.99 | 592.03 | 592.08 | 591.89 | 591.71 | 591.57 |
| Level Difference | 0.49 | 0.47 | 0.51 | 0.51 | 0.53 | 0.58 | 0.67 | 0.69 | 0.58 | 0.46 | 0.51 | 0.59 | 0.67 | 0.77 | 0.87 | 0.93 | 0.78 | 0.61 | 0.45 | 0.43 | 0.39 | 0.35 | 0.54 | 0.73 | 0.87 |
| Horizontal Geometry | L=4531.56' | | | | | | | | | | | | | | | | | | | | | | | | |
| Vertical Geometry | L=3845.36' | | | | | | | | | | | | | | | | | | | | | | | | |
| Superelevation | | | | | | | | | | | | | | | | | | | | | | | | | |


| | | | | | | | | | | |
|--|---|--|------|-----------|-------------|---------|----------|---|----------|--------------------------|
| Consultants <small>CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292528 mmpdco@mmpakistan.com http://www.mmpakistan.com</small> | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title CANAL ROAD PLAN AND PROFILE (STA 1+260.00 TO STA 2+520.00) Drawing No. MMP-1076P05-OKR-RD-PP-002 | Designed | M. Abdullah |
| | | | 0 | 2-11-2022 | | SA | PHK | | Drawn | M. Tayyab |
| | | | | | | | | | Checked | Sajjad Anwar |
| | | | | | | | | | Approved | Pervez Hayat Khan |
| | | | | | | | | | Scale | H= 1" : 100' V= 1" : 10' |
| | | | | | | | | | Rev No: | 0 |

Drawing file path & name: C:\Users\Tayyab\AppData\Local\Temp\AcPublish_14432\Okara Canal Road P&P.dwg
 User and Plot Date: Tayyab - Wed, 02 Nov 2022 - 11:25pm



LEGEND


| | | | |
|---------------------|--|------------------------|--|
| PROPOSED CENTERLINE | | EDGE OF PAVED SHOULDER | |
| EDGE OF TRAVELWAY | | PROPOSED CARRIAGEWAY | |
| LANE | | | |



| Station | 2+550 | 2+600 | 2+650 | 2+700 | 2+750 | 2+800 | 2+850 | 2+900 | 2+950 | 3+000 | 3+050 | 3+100 | 3+150 | 3+200 | 3+250 | 3+300 | 3+350 | 3+400 | 3+450 | 3+500 | 3+550 | 3+600 | 3+650 | 3+700 | 3+750 | | | |
|---------------------|-------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--|--|--|
| FRL | 592.45 | 592.45 | 592.46 | 592.46 | 592.47 | 592.47 | 592.48 | 592.48 | 592.49 | 592.49 | 592.50 | 592.50 | 592.51 | 592.51 | 592.52 | 592.52 | 592.53 | 592.53 | 592.54 | 592.54 | 592.55 | 592.55 | 592.56 | 592.56 | 592.57 | | | |
| NSL | 591.63 | 591.62 | 591.60 | 591.59 | 591.64 | 591.64 | 591.62 | 591.67 | 591.68 | 591.66 | 591.75 | 591.79 | 591.76 | 591.76 | 591.79 | 591.86 | 591.93 | 591.97 | 591.95 | 591.97 | 592.09 | 592.09 | 592.04 | 591.87 | 591.77 | | | |
| Level Difference | 0.81 | 0.83 | 0.86 | 0.87 | 0.83 | 0.84 | 0.85 | 0.81 | 0.81 | 0.84 | 0.75 | 0.71 | 0.74 | 0.75 | 0.73 | 0.67 | 0.60 | 0.57 | 0.59 | 0.57 | 0.46 | 0.46 | 0.52 | 0.70 | 0.80 | | | |
| Horizontal Geometry | L=4531.56' | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Vertical Geometry | L= 3845.36' | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Superelevation | | | | | | | | | | | | | | | | | | | | | | | | | | | | |


| | | | | | | | | | | |
|---|---|--|------|-----------|-------------|---------|----------|---|--------------------------|-------------|
| Consultants <small>CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292528 mmpdccc@mmpakistan.com http://www.mmpakistan.com</small> | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title CANAL ROAD PLAN AND PROFILE (STA 2+520.00 TO STA 3+780.00) Drawing No. MMP-1076P05-OKR-RD-PP-003 | Designed | M. Abdullah |
| | | | 0 | 2-11-2022 | | SA | PHK | | Drawn | M. Tayyab |
| | | | | | | | | Checked | Sajjad Anwar | |
| | | | | | | | | Approved | Pervez Hayat Khan | |
| | | | | | | | | Scale | H= 1" : 100' V= 1" : 10' | |
| | | | | | | | | Rev No: | 0 | |

Drawing file path & name: C:\Users\Tayyab\AppData\Local\Temp\AcPublish_14432\Okara Canal Road P&P.dwg
 User and Plot Date: Tayyab - Wed, 02 Nov 2022 - 11:25pm




LEGEND

| | | | |
|---------------------|--|------------------------|--|
| PROPOSED CENTERLINE | | EDGE OF PAVED SHOULDER | |
| EDGE OF TRAVELWAY | | PROPOSED CARRIAGEWAY | |
| LANE | | | |




| Station | 3+800 | 3+850 | 3+900 | 3+950 | 4+000 | 4+050 | 4+100 | 4+150 | 4+200 | 4+250 | 4+300 | 4+350 | 4+400 | 4+450 | 4+500 | 4+550 | 4+600 | 4+650 | 4+700 | 4+750 | 4+800 | 4+850 | 4+900 | 4+950 | 5+000 | | | |
|---------------------|------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|-------------------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--|--|--|
| FRL | 592.57 | 592.58 | 592.58 | 592.59 | 592.59 | 592.60 | 592.60 | 592.61 | 592.61 | 592.62 | 592.62 | 592.63 | 592.63 | 592.64 | 592.64 | 592.65 | 592.65 | 592.66 | 592.66 | 592.67 | 592.67 | 592.67 | 592.65 | 592.60 | 592.53 | | | |
| NSL | 591.75 | 591.76 | 591.80 | 591.89 | 591.96 | 592.01 | 591.97 | 591.93 | 591.89 | 591.89 | 591.95 | 592.00 | 592.04 | 592.10 | 592.19 | 592.33 | 592.44 | 592.36 | 592.35 | 592.46 | 592.52 | 592.54 | 592.50 | 592.38 | 592.30 | | | |
| Level Difference | 0.82 | 0.80 | 0.78 | 0.70 | 0.63 | 0.59 | 0.63 | 0.68 | 0.72 | 0.73 | 0.67 | 0.63 | 0.60 | 0.54 | 0.45 | 0.31 | 0.22 | 0.29 | 0.31 | 0.21 | 0.15 | 0.13 | 0.15 | 0.22 | 0.23 | | | |
| Horizontal Geometry | L=4531.56' | | | | | | | | | | | | L=604.66' R=2500.00' | | | | | | | | | | | | | | | |
| Vertical Geometry | L=3845.36' | | | | | | | | | | | | L=150.00' K=937.50 | | | | | | | | | | | | | | | |
| Superelevation | 84.56' | | | | | | | | | | | | | | | | | | | | | | | | | | | |

| | | | | | | | | | | |
|---|--|---|------|-----------|-------------|---------|---|---|--------------------------|-------------|
| Consultants CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292528 mmpdccc@mmpakistan.com http://www.mmpakistan.com | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title CANAL ROAD PLAN AND PROFILE (STA 3+780.00 TO STA 5+040.00) | Designed | M. Abdullah |
| | | | 0 | 2-11-2022 | | SA | PHK | | Drawn | M. Tayyab |
| | | | | | | | Drawing No. MMP-1076P05-OKR-RD-PP-004 | Checked | Sajjad Anwar | |
| | | | | | | | | Approved | Pervez Hayat Khan | |
| | | | | | | | | Scale | H= 1" : 100' V= 1" : 10' | |
| | | | | | | | | Rev No: | 0 | |



LEGEND

| | | | |
|---------------------|--|------------------------|--|
| PROPOSED CENTERLINE | | EDGE OF PAVED SHOULDER | |
| EDGE OF TRAVELWAY | | PROPOSED CARRIAGEWAY | |









| Station | 5+050 | 5+100 | 5+150 | 5+200 | 5+250 | 5+300 | 5+350 | 5+400 | 5+450 | 5+500 | 5+550 | 5+600 | 5+650 | 5+700 | 5+750 | 5+800 | 5+850 | 5+900 | 5+950 | 6+000 | 6+050 | 6+100 | 6+150 |
|---------------------|-------------------------|--------|-----------|--------|-------------------------|--------|--------|--------|--------|--------|-----------------------|--------|---------------------|--------|-----------|--------|-------------------------|--------|----------|--------|--------|--------|--------|
| FRL | 592.45 | 592.41 | 592.43 | 592.53 | 592.66 | 592.78 | 592.91 | 593.03 | 593.16 | 593.28 | 593.41 | 593.53 | 593.66 | 593.76 | 593.70 | 593.48 | 593.11 | 592.94 | 593.01 | 593.08 | 593.29 | 593.93 | 594.70 |
| NSL | 592.21 | 592.08 | 592.06 | 592.22 | 592.35 | 592.48 | 592.61 | 592.70 | 592.79 | 593.06 | 593.31 | 593.42 | 593.34 | 593.28 | 593.24 | 593.02 | 592.68 | 592.40 | 592.50 | 592.64 | 592.75 | 593.31 | 594.67 |
| Level Difference | 0.24 | 0.33 | 0.37 | 0.31 | 0.30 | 0.30 | 0.30 | 0.33 | 0.36 | 0.22 | 0.10 | 0.12 | 0.32 | 0.48 | 0.46 | 0.46 | 0.43 | 0.54 | 0.50 | 0.44 | 0.54 | 0.62 | 0.04 |
| Horizontal Geometry | L=604.66' R=2500.00' | | L=52.20' | | L=535.66' R=2200.00' | | | | | | | | L=188.99' | | | | L=209.55' R=1000.00' | | L=29.38' | | | | |
| Vertical Geometry | L=137.43' K=343.58 | | L=481.90' | | | | | | | | L=150.00' K=142.39 | | L=75.00' K=78.66 | | L=100.00' | | L=75.00' K=53.71 | | L=64.50' | | | | |
| Superelevation | | | | | | | | | | | | | | | | | | | | | | | |

| | | | | | | | | | | |
|---|--|--|------|-----------|-------------|---------|----------|---|---------------------------|-------------|
| Consultants CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292528 mmpdccc@mmpakistan.com http://www.mmpakistan.com | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title CANAL ROAD PLAN AND PROFILE (STA 5+040.00 TO STA 6+152.00) | Designed | M. Abdullah |
| | | | 0 | 2-11-2022 | | SA | PHK | | Drawn | M. Tayyab |
| | | | | | | | | Checked | Sajjad Anwar | |
| | | | | | | | | Approved | Pervez Hayat Khan | |
| | | | | | | | | Scale | H= 1" : 100' V= 1" : 10' | |
| | | | | | | | | Drawing No. | MMP-1076P05-OKR-RD-PP-005 | |
| | | | | | | | | Rev No: | 0 | |





Street Lights Plan

Drawing file path & name: F:\PMDFC\Package_V_Roads_P&P\Okara Roads\14_Street Lights\0_Street Light Plant\Typical\CANAL ROAD OKARA ELECTRICAL_SL.dwg
User and Plot Date: Toyab - Mon, 03 Oct 2022 - 6:40pm



NOTES:-
1. ALL DIMENSIONS ARE IN MILLIMETER UNLESS SHOWN OTHERWISE.

| | | | | | | | | | | |
|---|--|--|------|-----------|-------------|---------|----------|-----------------------------------|---------------------------|---------------|
| Consultants CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292528 mmpdcci@mmpakistan.com http://www.mmpakistan.com | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK | Rev. | Date | Description | Checked | Approved | Title SINGLE ARM POLES DETAILS | Designed | Ahsan Rasheed |
| | | | 0 | 3-10-2022 | | BA | PHK | | Drawn | Ahsan Rasheed |
| Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | | | | | | | | Checked | Bilal Ashraf | |
| | | | | | | | | Approved | Pervez Hayat Khan | |
| | | | | | | | | Scale | AS SHOWN | |
| | | | | | | | | Drawing No. | MMP-1076P05-OKR-SL-GN-001 | |
| | | | | | | | | Rev No: | 0 | |



NOTES:-
 1. ALL DIMENSIONS ARE IN FEET UNLESS SHOWN OTHERWISE.




Drawing file path & name: F:\PMDFC\Package_V_Roads_P&P\Okara Roads\14_Street Lights\03Street Light Plant\Typical\CANAL ROAD OKARA ELECTRICAL_SL.dwg
 User and Plot Date: Toyab - Mon, 03 Oct 2022 - 6:40pm

| | | | | | | | | | | |
|--|--|---|------|-----------|-------------|---------|----------|--|----------|-------------------|
| Consultants CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292528 mmpdce@mmpakistan.com http://www.mmpakistan.com | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title SINGLE AND DOUBLE ARM POLE FOUNDATION Drawing No. MMP-1076P05-OKR-SL-GN-003 | Designed | Ahsan Rasheed |
| | | | 0 | 3-10-2022 | | BA | PHK | | Drawn | Ahsan Rasheed |
| | | | | | | | | | Checked | Bilal Ashraf |
| | | | | | | | | | Approved | Pervez Hayat Khan |
| | | | | | | | | | Scale | AS SHOWN |
| | | | | | | | | Rev No: | 0 | |

© MM Pakistan
 This document should not be relied on or used in circumstances other than those for which it was originally prepared and for which MMP was commissioned. MMP accepts no responsibility for this document to any other party other than the person by whom it was commissioned.

Drawing file path & name: F:\PMDFC\Package_V_Roads_P&P\Okara Roads\14_Street Lights\Typical\CANAL ROAD OKARA ELECTRICAL_SL.dwg
User and Plot Date: Toyab - Mon, 03 Oct 2022 - 6:41pm

TENTATIVE CONSTRUCTIONAL DETAIL OF:- DISTRIBUTION BOARD.




NOTE:-
DIMENSIONS SHOWN ARE INDICATIVE ONLY AND NOT NECESSARILY BE FOLLOWED. HOWEVER ACTUAL DIMENSIONS OF DB SHALL BE GIVEN BY DB MANUFACTURER/SUPPLIER

- NOTES:-**
- ALL DIMENSIONS ARE IN MILLIMETER UNLESS SHOWN OTHERWISE.

| | | | | | | | | | | |
|--|--|---|------|-----------|-------------|---------|----------|---|----------|-------------------|
| Consultants CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-3629252-7 042-3629252-8 mmpdco@mmpakistan.com http://www.mmpakistan.com | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title CANAL ROAD SLD AND CONTROL PANEL DETAIL Drawing No. MMP-1076P05-OKR-SL-GN-004 | Designed | Ahsan Rasheed |
| | | | 0 | 3-10-2022 | | BA | PHK | | Drawn | Ahsan Rasheed |
| | | | | | | | | | Checked | Bilal Ashraf |
| | | | | | | | | | Approved | Pervez Hayat Khan |
| | | | | | | | | | Scale | AS SHOWN |
| | | | | | | | | Rev No: | 0 | |


Drawing file path & name: F:\PMDFC\Package_V_Roads_P&P\Okara Roads\14_Street Lights\Okara Canal Road Street Light Plan.dwg
 User and Plot Date: Tayyab - Wed, 02 Nov 2022 - 11:46pm



| | | | | | | | | | | |
|---|--|--|------|-----------|-------------|---------|----------|--|--------------------------|-------------|
| Consultants CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292525-7 042-36292528 mmpdccc@mmpakistan.com http://www.mmpakistan.com | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK | Rev. | Date | Description | Checked | Approved | Title CANAL ROAD STREET LIGHT PLAN | Designed | M. Abdullah |
| | | | 0 | 2-11-2022 | | SA | SA | | Drawn | M. Tayyab |
| Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | | | | | | | | Checked | Sajjad Anwar | |
| | | | | | | | | Approved | Sajjad Anwar | |
| | | | | | | | | Scale | 1" : 100' | |
| | | | | | | | | Rev No: | 0 | |
| | | | | | | | | Drawing No. | MMP-1076P05-OKR-SL-P-001 | |

© MM Pakistan
 This document should not be relied on or used in circumstances other than those for which it was originally prepared and for which MMP was commissioned. MMP accepts no responsibility for this document to any other party other than the person by whom it was commissioned.

Drawing file path & name: F:\PMDFC\Package_V_Roads_P&P\Okara Roads\14_Street Lights\Okara Canal Road Street Light Plan.dwg
User and Plot Date: Tayyab - Wed, 02 Nov 2022 - 11:46pm





LEGEND

| | |
|--|---|
| | SINGLE ARM STREET LIGHT POLE (10 METER) |
| | STREET LIGHT CONTROL PANEL |
| | 25 KVA POLE MOUNTED TRANSFORMER |

| | | | | | | | | | | |
|---|--|---|------|-----------|-------------|---------|----------|--|--------------|-------------|
| Consultants CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292528 mmpdccc@mmpakistan.com http://www.mmpakistan.com | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title CANAL ROAD STREET LIGHT PLAN Drawing No. MMP-1076P05-OKR-SL-P-002 | Designed | M. Abdullah |
| | | | 0 | 2-11-2022 | | SA | SA | | Drawn | M. Tayyab |
| | | | | | | | | Checked | Sajjad Anwar | |
| | | | | | | | | Approved | Sajjad Anwar | |
| | | | | | | | | Scale | 1" : 100' | |
| | | | | | | | | Rev No: | 0 | |

© MM Pakistan
This document should not be relied on or used in circumstances other than those for which it was originally prepared and for which MMP was commissioned. MMP accepts no responsibility for this document to any other party other than the person by whom it was commissioned.



LEGEND

| | |
|--|---|
| | SINGLE ARM STREET LIGHT POLE (10 METER) |
| | STREET LIGHT CONTROL PANEL |
| | 25 KVA POLE MOUNTED TRANSFORMER |



Drawing file path & name: F:\PMDFC\Package-V_Roads_P&P\Okara Roads\14_Street Lights\Okara Canal Road Street Light_Plan.dwg
 User and Plot Date: Tayyab - Wed, 02 Nov 2022 - 11:46pm

| | | | | | | | | | | | |
|---|--|---|------|-----------|-------------|---------|----------|--|--------------------------|-------------|---|
| Consultants CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292528 mmpdccc@mmpakistan.com http://www.mmpakistan.com | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title CANAL ROAD STREET LIGHT PLAN | Designed | M. Abdullah | |
| | | | 0 | 2-11-2022 | | SA | SA | | Drawn | M. Tayyab | |
| | | | | | | | | Checked | Sajjad Anwar | | |
| | | | | | | | | Approved | Sajjad Anwar | | |
| | | | | | | | | Scale | 1" : 100' | | |
| | | | | | | | | Drawing No. | MMP-1076P05-OKR-SL-P-003 | Rev No: | 0 |

© MM Pakistan
 This document should not be relied on or used in circumstances other than those for which it was originally prepared and for which MMP was commissioned. MMP accepts no responsibility for this document to any other party other than the person by whom it was commissioned.






Drainage Plan




NOTES:-

1. PROVIDE GULLY GRATING CHAMBER AS PER PHED STD/PD NO. 3 OF 1977.

| | | | | | | | | | | |
|--|--|---|------|-----------|-------------|---------|----------|---|--------------|-------------|
| Consultants  CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292528 mmpdccc@mmpakistan.com http://www.mmpakistan.com | Client  GOVERNMENT OF PUNJAB  Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title CANAL ROAD DRAINAGE PLAN Drawing No. MMP-1076P05-OKR-RD-DR-001 | Designed | M. Abdullah |
| | | | 0 | 2-11-2022 | | SA | SA | | Drawn | M. Tayyab |
| | | | | | | | | Checked | Sajjad Anwar | |
| | | | | | | | | Approved | Sajjad Anwar | |
| | | | | | | | | Scale | 1" : 100' | |
| | | | | | | | | Rev No: | 0 | |


Drawing file path & name: C:\Users\Tayyab\AppData\Local\Temp\Temp\Okara Canal Road Drainage Plan.dwg
User and Plot Date: Tayyab - Wed, 02 Nov 2022 - 11:46pm



NOTES:-




1. PROVIDE GULLY GRATING CHAMBER AS PER PHED STD/PD NO. 3 OF 1977.

| | | | | | | | | | | |
|---|--|---|------|-----------|-------------|---------|----------|--|--------------|-------------|
| Consultants CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292525-7 042-36292528 mmpdccc@mmpakistan.com http://www.mmpakistan.com | Client GOVERNMENT OF PUNJAB Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title CANAL ROAD DRAINAGE PLAN Drawing No. MMP-1076P05-OKR-RD-DR-002 | Designed | M. Abdullah |
| | | | 0 | 2-11-2022 | | SA | SA | | Drawn | M. Tayyab |
| | | | | | | | | Checked | Sajjad Anwar | |
| | | | | | | | | Approved | Sajjad Anwar | |
| | | | | | | | | Scale | 1" : 100' | |
| | | | | | | | | Rev No: | 0 | |



NOTES:-

1. PROVIDE GULLY GRATING CHAMBER AS PER PHED STD/PD NO. 3 OF 1977.

| | | | | | | | | | | |
|---|--|---|------|-----------|-------------|---------|----------|---|--------------|-------------|
| Consultants  CENTRAL DESIGN CELL 2nd Floor, CTI Building, 27-Empress Road, Lahore 042-36292528 mmpdcc@mmpakistan.com http://www.mmpakistan.com | Client  GOVERNMENT OF PUNJAB  Punjab Municipal Development Fund Company Department (PMDFC) | Financing Agency WORLD BANK Project Punjab Cities Program (PCP) Detailed Design of Infrastructure Sub-Projects, Sectoral Planning & Resident Supervision in 16 Cities of Punjab(Package-5) | Rev. | Date | Description | Checked | Approved | Title CANAL ROAD DRAINAGE PLAN Drawing No. MMP-1076P05-OKR-RD-DR-003 | Designed | M. Abdullah |
| | | | 0 | 2-11-2022 | | SA | SA | | Drawn | M. Tayyab |
| | | | | | | | | Checked | Sajjad Anwar | |
| | | | | | | | | Approved | Sajjad Anwar | |
| | | | | | | | | Scale | 1" : 100' | |
| | | | | | | | | Rev No: | 0 | |